

## **STATEMENT OF WORK BEDDING (310)**

**These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.**

### **DESIGN**

---

#### **Deliverables:**

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
  - d. List of facilitating/component practices
  - e. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
    - i. Soils and slope
    - ii. Water budget (e.g. volume, velocity, movement)
    - iii. Bed crown height, width and length
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Operation and Maintenance Plan
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.3).
5. Design modifications during installation as required.
6. Documentation needed for the practice depends on the specific conditions at the site where it will be installed. However in New Mexico, the minimum required documentation is: Direction, grade, and length of natural slope, direction and grade of design slope, size and shape of parallel channels, and adequacy of the downstream outlet.
7. The local SWCD can help identify local permits and regulatory requirements. (Refer to Item 1.b above)

### **INSTALLATION**

---

#### **Deliverables:**

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
  - a. Actual materials used (Part 512, Subpart D Quality Assurance Activities, 512.33)
  - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

### **CHECK OUT**

---

#### **Deliverables:**

1. As-Built documentation.
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.3).
3. Progress reporting.
4. Refer to the requirements in Design Deliverable Item 6. As a minimum, the completed direction and grade of the bedding and the size and shape of the parallel channels shall be measured and documented to show that the installed practice meets the standard, specification, and design requirements.

**STATEMENT OF WORK  
BEDDING (310)**

**REFERENCES**

---

Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Bedding - 310

- NRCS National Engineering Manual (NEM)
- NRCS National Agronomy Manual (NAM)
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook