

STATEMENT OF WORK
Field Border (386)
TENNESSEE

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Section 503.00 through 503.22).
 - c. List all required and/or facilitating practices.
 - d. Practice standard criteria-related computations and analyses to develop plans and specifications including, but not limited to:
 - i. Border width and lengths.
 - ii. Vegetative species selection and planting/seeding rate.
 - iii. Site and seedbed preparation required.
 - iv. Erosion calculations using RUSLE2.
 - v. Wildlife considerations.
 - e. Evaluation and completion of TN-CPA-25, Environmental Effects for Conservation and Areawide Plans.
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements of conservation practice standard Field Border (Code 386).
3. Documentation of discussion of Operation and Maintenance Plan in Assistance Notes.
4. Certification that the design meets practice standard criteria and complies with applicable laws and regulations.
5. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-installation conference with client.
2. Staking and layout according to plans and specifications including applicable layout notes.
3. Installation guidance as needed.
4. Facilitate and implement required design modifications with client and original designer.
5. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations, and NRCS policies during installation.
6. Certification that the installation process and materials meet design requirements.

CHECK OUT

Deliverables

1. Records of installation.
 - a. Extent of practice units applied.
 - b. Actual materials used.
2. Certification that the installation meets NRCS standards and specifications.
3. Progress reporting.

REFERENCES

- NRCS Tennessee Field Office Technical Guide (e-FOTG), Section IV, Conservation Practice Standard Field Border (386)
- NRCS National Agronomy Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook