

STATEMENT OF WORK Agrichemical Handling Facility (309) Vermont

These deliverables apply to this individual practice. For deliverables for other planned practices, refer to those specific Statements of Work.

DESIGN

Deliverables:

- 1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A Engineering Activities Affecting Utilities 503.00 through 503.06).
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM Subpart 531a).
 - ii. Structural, Mechanical and Appurtenance design
 - iii. Maximize Clean Water Diversion.
 - iv. Hydraulic Loading Rate.
 - v. Environmental Considerations (e.g. location, air and water quality).
 - vi. Vegetation.
- 2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
- 3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
- 4. Operation and Maintenance Plan
- 5. Certifications that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03(b) (2)).
- 6. Design modifications during installation as required.

INSTALLATION

Deliverables

- 1. Pre-Installation conference with client and contractor.
- 2. Verification that client has obtained required permits.
- 3. Staking and layout according to plans and specifications including applicable layout notes.
- 4. Installation inspection (according to inspection plan as appropriate).
- 5. Actual materials used.
- 6. Inspection records
- 7. Facilitate and implement required design modifications with client and original designer.
- 8. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
- 9. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT

Deliverables

- 1. As-Built documentation.
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
- 2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03(c) (1)).
- 3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard Agrichemical Handling Facility - 309.
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook