

STATEMENT OF WORK
Grade Stabilization Structure (410)

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables

1. Design documentation that will demonstrate that the criteria in Florida NRCS practice standard have been met and are compatible with other planned and applied practices
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503 - Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM Part 531 - Geology, Subpart A - Geological Investigations)
 - ii. Hydrology/Hydraulics
 - iii. Structural including hazard class as appropriate
 - iv. Vegetative requirements
 - v. Environmental Considerations
 - vi. Safety Considerations (NEM Part 503 - Safety, Subpart A - Engineering Activities Affecting Utilities)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits
3. Design Report and Inspection Plan as appropriate (NEM Part 511 - Design, Subpart B - Documentation and Part 512 - Construction, Subpart D - Quality Assurance Activities)
4. Operation and Maintenance Plan
5. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Part 505 - Non-NRCS Engineering Services, Subpart A - Compliance of engineering Work With Laws and Regulations (505.3(a))
6. Design modifications during installation as required

INSTALLATION

Deliverables

1. Pre Installation conference with client and contractor. Signed form FL-ENG-40, Verification of Pre-Construction Conference
2. Verification that client has obtained required permits
3. Staking and layout according to plans and specifications including applicable layout notes
4. Installation inspection (according to inspection plan as appropriate)
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation

STATEMENT OF WORK
Grade Stabilization Structure (410)

7. Certification that the installation process and materials meets design and permit requirements

CHECK OUT

Deliverables

1. As-Built documentation
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets Florida NRCS standards and specifications and is in compliance with permits
3. Progress reporting

REFERENCES

- Florida NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Grade Stabilization Structure, 410
- NRCS National Engineering Manual (NEM)
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook

STATE CONTACT

Jesse T. Wilson
State Conservation Engineer
(352) 338-9555
jesse.wilson@fl.usda.gov