

GA NRCS PROGRAM COST LIST - FY 2007

ENGINEERING PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
316	Animal Mortality Facility	Incinerator < 100 lbs/day capacity	EACH	\$4,350.00	Includes Freight and Secondary Burners	EQIP
316	Animal Mortality Facility	Incinerator 101 - 300 lbs/day capacity	EACH	\$5,000.00	Includes Freight and Secondary Burners	EQIP
316	Animal Mortality Facility	Incinerator 301 - 500 lbs/day capacity	EACH	\$6,400.00	Includes Freight and Secondary Burners	EQIP
316	Animal Mortality Facility	Incinerator 501 - 750 lbs/day capacity	EACH	\$7,300.00	Includes Freight and Secondary Burners	EQIP
316	Animal Mortality Facility	Incinerator > 750 lbs/day capacity	EACH	\$11,610.00	Includes Freight and Secondary Burners	EQIP
316	Animal Mortality Facility	Freezer	EACH	\$3,000.00	Cost is per chicken house - Use Actual Cost Not to Exceed \$3,000.00 (submit to State Office for approval.)	EQIP
316	Animal Mortality Facility	Concrete/Grading for pad under incinerator/freezer	SF	\$2.40	4" fiber reinforced concrete. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
316	Animal Mortality Facility	Vegetation/Critical Area	AC	\$990.00		

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
360	Closure of Waste Impoundments	Dewatering (pump-out)	EACH	\$4,000.00	Intended for Waste Impoundments containing less than 80,000 CF of storage.	EQIP
360	Closure of Waste Impoundments	Dewatering (pump-out)	CF	\$0.05	Intended for Waste Impoundments containing more than 80,000 CF of storage.	EQIP
360	Closure of Waste Impoundments	Earthwork	CY	\$3.20		EQIP
360	Closure of Waste Impoundments	Vegetation/Critical Area	AC	\$990.00		EQIP
360	Closure of Waste Impoundments	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
317	Composter	Wood Frame - metal roof (stand alone or side shed)	SF	\$6.20	Does not include walls and short posts for walls.	EQIP
317	Composter	Wood Frame - metal roof (within stack house frame)	SF	\$11.10		EQIP
317	Composter	Steel Frame - metal roof (used in conjunction with stackhouse)	SF	\$10.40	Does not include walls and short posts for walls.	EQIP
317	Composter	5' High Walls - wood (Single sided walls)	LF	\$16.40	Pressure Treated 2x6 - (materials and labor). Includes short posts.	EQIP
317	Composter	4' High Walls - wood (Single sided walls)	LF	\$14.70	Pressure Treated 2x6 - (materials and labor). Includes short posts.	EQIP
317	Composter	5' High Walls - wood (Double sided walls)	LF	\$25.40	Pressure Treated 2x6 - (materials and labor). Interior bin walls. Includes posts.	EQIP
317	Composter	4' High Walls - wood (Double sided walls)	LF	\$22.10	Pressure Treated 2x6 - (materials and labor). Interior bin walls. Includes posts.	EQIP
317	Composter	Slab - Fiber reinforced Concrete	CY	\$193.00	4" fiber reinforced concrete (Includes grading/shaping up to 6" deep over the entire building footprint)	EQIP
317	Composter	Earthwork	CY	\$3.20	For use when earthwork greater than 6" deep is required over the entire building footprint.	EQIP
317	Composter	Entrance Pad - Gravel/Geotextile/Grading	SF	\$1.60	At Heavy Use Area Cost (pad limited to width of door by 12' from entrance)	EQIP
317	Composter	Entrance Pad - Concrete/Grading	SF	\$2.40	At Heavy Use Area Cost (4" pad limited to width of door by 12' from entrance). Includes 6" deep grading.	EQIP
317	Composter	Vegetation/Critical Area	AC	\$990.00		EQIP
317	Composter	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

1. Concrete walls may be used at applicant's expense.

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
362	Diversions	Earthwork	LF	\$1.30		EQIP
362	Diversions	Vegetation/Critical Area	AC	\$990.00		EQIP
362	Diversions	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
561	Heavy Use Area	Gravel/Geotextile/Grading	SF	\$1.60	Includes GAB, Geotextile, Grading/shaping	EQIP
561	Heavy Use Area	Concrete/Grading	SF	\$2.40	4" fiber reinforced concrete. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
561	Heavy Use Area	Concrete - Steel reinforced slab	SF	\$4.50	6" steel reinforced concrete slab. Used on watering ramps. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
561	Heavy Use Area	Earthwork	CY	\$8.30	Only for watering ramps	EQIP
561	Heavy Use Area	Geotextile	SF	\$0.30	Includes pins, laps and trenching edges.	EQIP
561	Heavy Use Area	Stone - Surge	TN	\$35.00	Used on higher velocity streams for watering ramps.	EQIP
561	Heavy Use Area	Stone - Riprap	TN	\$50.00	Used on higher velocity streams for watering ramps.	EQIP
561	Heavy Use Area	Geotextile and Stone - GAB/DOT No. 3/DOT No. 4	SF	\$1.50	Includes laps and trench costs. Used on watering ramps. Does not include earthwork.	EQIP
561	Heavy Use Area	Vegetation/Critical Area	AC	\$990.00		EQIP
561	Heavy Use Area	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
410	Grade Stab. Structure	Earthwork	CY	\$3.20		EQIP
410	Grade Stab. Structure	Steel reinforced concrete walls and footings	CY	\$395.00		EQIP
410	Grade Stab. Structure	Slab - Fiber reinforced Concrete	CY	\$193.00	(Includes grading/shaping up to 6" deep over the entire slab)	EQIP
410	Grade Stab. Structure	Slab - Steel reinforced Concrete	CY	\$245.00	(Includes grading/shaping up to 6" deep over the entire slab)	EQIP
410	Grade Stab. Structure	Rip Rap	TN	\$50.00		EQIP
410	Grade Stab. Structure	Vegetation/Critical Area	AC	\$990.00		EQIP
410	Grade Stab. Structure	Pipe - 6"	LF	\$6.50	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 8"	LF	\$12.20	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 12"	LF	\$14.90	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 18"	LF	\$23.40	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 24"	LF	\$30.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 30"	LF	\$44.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 36"	LF	\$55.10	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 42"	LF	\$71.60	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Pipe - 48"	LF	\$88.10	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	EQIP
410	Grade Stab. Structure	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

***All Costs are 100% Costs and
Unless Otherwise Noted Include Installation

GA NRCS PROGRAM COST LIST - FY 2007

ENGINEERING PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
442	Irrigation Sprinkler System	Hose Reel	AC	\$885.00	For Ag. Watse Only. Application area based on nitrogen (SEE EQIP WASTE CALCULATOR)	EQIP
442	Irrigation Sprinkler System	Center Pivot	AC	\$885.00	For Ag. Watse Only. Application area based on nitrogen (SEE EQIP WASTE CALCULATOR)	EQIP
442	Irrigation Sprinkler System	Solid Set	AC	\$1,144.00	For Ag. Watse Only. Application area based on nitrogen. 2 guns per area (SEE EQIP WASTE CALCULATOR)	EQIP
442	Irrigation Sprinkler System	End gun shut-off	EA.	\$1,400.00	System upgrade	EQIP
442	Irrigation Sprinkler System	End Gun Booster Pump	EA.	\$2,600.00	System upgrade	EQIP
442	Irrigation Sprinkler System	Low Drop Extension sprinklers	LF.	\$8.00	System upgrade	EQIP
442	Irrigation Sprinkler System	Medium or Low Pressure sprinklers	LF.	\$5.40	System upgrade	EQIP
442	Irrigation Sprinkler System	Medium Pressure Impacts	LF.	\$6.40	System upgrade	EQIP
442	Irrigation Sprinkler System	Variable Rate Irrigation - Sprinkler Valves	EA.	\$34.50		EQIP
442	Irrigation Sprinkler System	Variable Rate Irrigation - Control Panel	EA.	\$10,050.00	Includes labor costs.	EQIP
442	Irrigation Sprinkler System	Variable Rate Irrigation - Control Nodes	EA.	\$1,625.00		EQIP
442	Irrigation Sprinkler System	Solid Set for specialty crops	AC	\$2,500.00	Used on specialty crops less than 4 acres in size. Entire system cost. Pump, pipe and impact sprinklers.	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
443	Irrigation Subsurface System	Micro Irrigation - Vegetables or Orchards	AC	\$850.00	System conversion. Must show water savings. Limited to 100 Acres	EQIP
443	Irrigation Subsurface System	Micro Irrigation - Permanent subsurface for row crops	AC	\$1,000.00	System conversion. Must show water savings. Limited to 100 Acres	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
634	Manure Transfer	Pipe - 2"	LF	\$4.30	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Pipe - 3"	LF	\$6.70	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Pipe - 4"	LF	\$8.70	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Pipe - 6"	LF	\$12.10	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Pipe - 8"	LF	\$19.60	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Pipe - 12"	LF	\$25.80	Maximum cost for PVC Pressure Pipe.	EQIP
634	Manure Transfer	Slab - Fiber reinforced Concrete	CY	\$193.00	Used for pump pads, thrust blocks, etc. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
634	Manure Transfer	Slab - Steel reinforced Concrete	CY	\$245.00	Used for gutters/waste conveyance channels. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
634	Manure Transfer	Manure Flush System (Gravity) 2500 gal.	EACH	\$650.00		EQIP
634	Manure Transfer	Manure Flush System (Gravity) 10000-12000 gal.	EACH	\$2,000.00		EQIP
634	Manure Transfer	Manure Flush System (Gravity) 20000-30000 gal.	EACH	\$3,800.00		EQIP
634	Manure Transfer	Flush Valve	EACH	\$1,300.00		EQIP
634	Manure Transfer	Recycle Pump-1 hp	EACH	\$1,425.00	Wastewater. Single Phase	EQIP
634	Manure Transfer	Recycle Pump-2 hp	EACH	\$1,610.00	Wastewater. Single Phase	EQIP
634	Manure Transfer	Washdown Tank - 1000 gal.	EACH	\$300.00		EQIP
634	Manure Transfer	Washdown Tank - 2000 gal.	EACH	\$400.00		EQIP
634	Manure Transfer	Washdown Tank - 3000 gal.	EACH	\$700.00		EQIP
634	Manure Transfer	Washdown Tank - 4000 gal.	EACH	\$900.00		EQIP
634	Manure Transfer	Pump 1.5 HP Fixed in place (single phase)	EACH	\$1,235.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 2 HP Fixed in place (single phase)	EACH	\$1,437.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 3 HP Fixed in place (single phase)	EACH	\$3,521.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 5 HP - Fixed in place (single phase)	EACH	\$3,827.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 7.5 HP Fixed in place (single phase)	EACH	\$9,274.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 10 HP - Fixed in place (single phase)	EACH	\$9,704.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 15 HP - Fixed in place (single phase)	EACH	\$5,400.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 15 HP - Fixed in place (three phase)	EACH	\$9,708.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 20 HP (three phase) - Fixed in place	EACH	\$11,270.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 30 HP (three phase) - Fixed in place	EACH	\$12,025.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 40 HP (three phase) - Fixed in place	EACH	\$13,863.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Pump 60 HP (three phase) - Fixed in place	EACH	\$17,379.00	Wastewater pump. Price including motor.	EQIP
634	Manure Transfer	Booster Pump 1 hp - Fixed in place	EACH	\$615.00	Wastewater pump.	EQIP
634	Manure Transfer	Booster Pump 1 1/2 hp - Fixed in place	EACH	\$765.00	Wastewater pump.	EQIP
634	Manure Transfer	Booster Pump 2 hp - Fixed in place	EACH	\$935.00	Wastewater pump.	EQIP
634	Manure Transfer	Pump-out Accessories	SYSTEM	\$2,500.00	Includes 2-tees, 1-8" Z pipe, 1-pressure relief valve, 1-pump out pipe, 1-intake strainer and installation.	EQIP
634	Manure Transfer	Prefabricated Junction Boxes	EACH	\$1,481.00		EQIP
634	Manure Transfer	PTO Pump	EACH	\$6,000.00		EQIP
634	Manure Transfer	Vegetation/Critical Area	AC	\$990.00		EQIP
634	Manure Transfer	Transformer	EACH	\$850.00		EQIP
634	Manure Transfer	Starter Panel	EACH	\$1,300.00		EQIP
634	Manure Transfer	Phase converter	EACH	\$4,500.00		EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
558	Roof Runoff Management	Structural method to control roof runoff	LF	\$5.70	Price is by Length of Building. Could include Gutters, gravel ditch, concrete ditch, collection pipe, etc.	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
574	Spring Development	System Cost	EACH	\$1,015.00	Includes concrete pipe or collection box, gravel and earthwork.	EQIP
574	Spring Development	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

GA NRCS PROGRAM COST LIST - FY 2007

ENGINEERING PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
580	Steambank and Shoreline Protection	Low level of protection	SF	\$1.40	Includes shaping bank, critical area vegetation and erosion control fabric.	EQIP
580	Steambank and Shoreline Protection	Medium level of protection	SF	\$4.35	Includes shaping bank, critical area vegetation, livestock, rootwad, or revetments.	EQIP
580	Steambank and Shoreline Protection	High level of protection	SF	\$9.60	Includes shaping bank and installing Riprap, Gabion, etc.	EQIP
580	Steambank and Shoreline Protection	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

1. Costs are by area of treated surface and not linear foot of stream

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
578	Stream Crossing	Geotextile	SF	\$0.30	Includes pins, laps and trenching edges.	EQIP
578	Stream Crossing	Geoweb + install - 6" thick	SF	\$3.89	Includes installation, DOES NOT include aggregate or geotextile.	EQIP
578	Stream Crossing	Concrete - Steel reinforced slab	CY	\$245.00	6" steel reinforced concrete slab. (Includes grading/shaping up to 6" deep over the entire slab)	EQIP
578	Stream Crossing	Earthwork	CY	\$8.30	Only for stream crossings	EQIP
578	Stream Crossing	Stone - GAB/DOT No. 3/DOT No. 4	TN	\$26.30		EQIP
578	Stream Crossing	Stone - Surge	TN	\$35.00		EQIP
578	Stream Crossing	Stone - Riprap	TN	\$50.00		EQIP
578	Stream Crossing	Pipe - 18" Culvert	LF	\$23.40	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Pipe - 24" Culvert	LF	\$30.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Pipe - 30" Culvert	LF	\$44.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Pipe - 36" Culvert	LF	\$55.10	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Pipe - 42" Culvert	LF	\$71.60	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Pipe - 48" Culvert	LF	\$88.10	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
578	Stream Crossing	Vegetation/Critical Area	AC	\$990.00		EQIP
578	Stream Crossing	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
600	Terrace	Grading and Shaping	LF	\$0.40		EQIP
600	Terrace	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
620	Underground Outlet	Corrugated Plastic Tubing w/Snap Coupling 6"	LF	\$5.70		EQIP
620	Underground Outlet	Corrugated Plastic Tubing w/Snap Coupling 8"	LF	\$6.80		EQIP
620	Underground Outlet	Corrugated Plastic Tubing w/Snap Coupling 10"	LF	\$8.50		EQIP
620	Underground Outlet	Corrugated Plastic Tubing w/Snap Coupling 12"	LF	\$11.30		EQIP
620	Underground Outlet	Perforated Corrugated Plastic Tubing w/Sock 4"	LF	\$4.10		EQIP
620	Underground Outlet	Perforated Corrugated Plastic Tubing w/Sock 6"	LF	\$5.70		EQIP
620	Underground Outlet	Perforated Corrugated Plastic Tubing w/Sock 8"	LF	\$6.80		EQIP
620	Underground Outlet	Free Standing Perforated Inlets 6"	EACH	\$52.00		EQIP
620	Underground Outlet	Animal Guard Outlets 6"	EACH	\$9.10		EQIP
620	Underground Outlet	Animal Guard Outlets 8"	EACH	\$11.90		EQIP
620	Underground Outlet	Animal Guard Outlets 10"	EACH	\$15.30		EQIP
620	Underground Outlet	Animal Guard Outlets 12"	EACH	\$24.40		EQIP
620	Underground Outlet	Earthwork	CY	\$3.20	Used to excavate outlet tail ditch, outlet protection may be needed.	EQIP
620	Underground Outlet	Stone - Surge	TN	\$35.00	Outlet protection	EQIP
620	Underground Outlet	Vegetation/Critical Area	AC	\$990.00		EQIP
620	Underground Outlet	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
313	Waste Storage Facility	Wood Frame - Metal Roof	SF	\$11.10	Does not include walls and short posts for walls.	EQIP
313	Waste Storage Facility	Steel Frame - metal roof	SF	\$10.40	Does not include walls and short posts for walls.	EQIP
313	Waste Storage Facility	5' High Walls - wood (Single sided walls)	LF	\$16.40	Pressure Treated 2x6 - (materials and labor). Includes short posts.	EQIP
313	Waste Storage Facility	4' High Walls - wood (Single sided walls)	LF	\$14.70	Pressure Treated 2x6 or 3/4 in. plywood - (materials and labor). Includes short posts.	EQIP
313	Waste Storage Facility	Steel reinforced concrete walls and footings	CY	\$395.00		EQIP
313	Waste Storage Facility	Slab - Fiber reinforced Concrete	CY	\$193.00	(Includes grading/shaping up to 6" deep over the entire slab)	EQIP
313	Waste Storage Facility	Slab - Steel reinforced Concrete	CY	\$245.00	(Includes grading/shaping up to 6" deep over the entire slab)	EQIP
313	Waste Storage Facility	Entrance Pad - Gravel/Geotextile/Grading	SF	\$1.60	At Heavy Use Area Cost (pad limited to width of door by 12' from entrance)	EQIP
313	Waste Storage Facility	Entrance Pad - Concrete/Grading	SF	\$2.40	At Heavy Use Area Cost (4' pad limited to width of door by 12' from entrance)	EQIP
313	Waste Storage Facility	Earthwork	CY	\$3.20		EQIP
313	Waste Storage Facility	Skimmer/Porous Board Fence Combination	EA	\$500.00		EQIP
313	Waste Storage Facility	Guardrails w/ 6" x 8" column framing	LF	\$7.00	5 ft walls using new guardrails. NOTE: Max. wall height is 5 ft.	EQIP
313	Waste Storage Facility	Compacted Clay Liner	CY	\$5.60		EQIP
313	Waste Storage Facility	Liner additive - Soda Ash	TN	\$560.00	Applied at designed recommended rates	EQIP
313	Waste Storage Facility	Liner additive - Bentonite	TN	\$280.00	Applied at designed recommended rates	EQIP
313	Waste Storage Facility	Vegetation/Critical Area	AC	\$990.00		EQIP

GA NRCS PROGRAM COST LIST - FY 2007

ENGINEERING PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
313	Waste Storage Facility	Pipe - 8"	LF	\$12.20	Maximum cost for pipe. HDPE or PVC	EQIP
313	Waste Storage Facility	Pipe - 10"	LF	\$14.00	Maximum cost for pipe. HDPE or PVC	EQIP
313	Waste Storage Facility	Pipe - 12"	LF	\$14.90	Maximum cost for pipe. HDPE or PVC	EQIP
313	Waste Storage Facility	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP
313	Waste Storage Facility	40hd - Winter Feeder	EACH	\$26,000.00	Entire structure cost: Frame, floor and wall.	EQIP
313	Waste Storage Facility	60hd - Winter Feeder	EACH	\$35,000.00	Entire structure cost: Frame, floor and wall.	EQIP
313	Waste Storage Facility	80hd - Winter Feeder	EACH	\$41,000.00	Entire structure cost: Frame, floor and wall.	EQIP

1. No earthen floors will be allowed for stackhouses.
2. Concrete walls used only for Hen Litter. Concrete walls for other poultry systems will be paid at applicant's expense

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
638	Water and Sediment Control Basin	Earthwork	CY	\$3.20		EQIP
638	Water and Sediment Control Basin	Vegetation/Critical Area	AC	\$990.00		EQIP
638	Water and Sediment Control Basin	Pipe - 6"	LF	\$6.50	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
638	Water and Sediment Control Basin	Pipe - 8"	LF	\$12.20	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
638	Water and Sediment Control Basin	Pipe - 12"	LF	\$14.90	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
638	Water and Sediment Control Basin	Pipe - 18"	LF	\$23.40	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
638	Water and Sediment Control Basin	Pipe - 24"	LF	\$30.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE)	EQIP
638	Water and Sediment Control Basin	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
614	Watering Facility	Tank - 100 - 300 gallon	EA	\$350.00	Permanently installed tank that meets NRCS standards.	EQIP
614	Watering Facility	Tank - 301 - 500 gallon	EA	\$450.00	Permanently installed tank that meets NRCS standards.	EQIP
614	Watering Facility	Tank - > 500 gallon	EA	\$650.00	Permanently installed tank that meets NRCS standards.	EQIP
614	Watering Facility	Tank Installation	EA	\$109.00	Price per tank. Price for installation only. Includes price of float valve and any appurtenances needed.	EQIP
614	Watering Facility	HUA - Gravel/Geotextile/Grading	SF	\$1.60	Includes GAB, Geotextile, Grading/shaping	EQIP
614	Watering Facility	HUA - Concrete/Grading	SF	\$2.40	4" fiber reinforced concrete	EQIP
614	Watering Facility	Pump 1/2 HP Fixed in place	EACH	\$584.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pump 3/4 HP Fixed in place	EACH	\$682.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pump 1 HP Fixed in place	EACH	\$806.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pump 2 HP Fixed in place	EACH	\$812.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pump 3 HP Fixed in place	EACH	\$1,069.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pump 5 HP - Fixed in place	EACH	\$1,514.00	Freshwater pump, price includes motor.	EQIP
614	Watering Facility	Pipe - 1/2"	LF	\$3.00	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Pipe - 3/4"	LF	\$3.10	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Pipe - 1"	LF	\$3.20	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Pipe - 1 1/4"	LF	\$3.30	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Pipe - 1 1/2"	LF	\$3.40	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Pipe - 2"	LF	\$3.60	Maximum cost for Sch. 40 PVC Pipe.	EQIP
614	Watering Facility	Vegetation/Critical Area	AC	\$990.00		EQIP
614	Watering Facility	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

1. Mirafount or equivalent drinkers will be paid at the 301-500 gallon tank price.
2. Heavy use areas are included in the 614 practice code as a subsidiary item.
Do not include a separate heavy use area practice code.

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
642	Water Well	Well Installation	Each	\$6,000.00	This is a total cost to install a functioning well. Includes well pump, curbing, etc.	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
359	Waste Treatment Lagoon	Earthwork	CY	\$3.20	Does not include compacted clay liner	EQIP
359	Waste Treatment Lagoon	Compacted Clay Liner	CY	\$5.60		EQIP
359	Waste Treatment Lagoon	Liner additive - Soda Ash	TN	\$560.00	Applied at designed recommended rates	EQIP
359	Waste Treatment Lagoon	Liner additive - Bentonite	TN	\$220.00	Applied at designed recommended rates	EQIP
359	Waste Treatment Lagoon	Pipe - 8"	LF	\$12.20	Maximum cost for pipe. HDPE or PVC	EQIP
359	Waste Treatment Lagoon	Pipe - 10"	LF	\$14.00	Maximum cost for pipe. HDPE or PVC	EQIP
359	Waste Treatment Lagoon	Pipe - 12"	LF	\$14.90	Maximum cost for pipe. HDPE or PVC	EQIP
359	Waste Treatment Lagoon	Vegetation/Critical Area	AC	\$990.00		EQIP
359	Waste Treatment Lagoon	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

GA NRCS PROGRAM COST LIST - FY 2007

AGRONOMIC PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
342	Critical Area Treatment	Earthwork	AC	\$1,239.00		EQIP
342	Critical Area Treatment	Earthwork	CY	\$3.20	Typically used for rills, gullies and washes.	EQIP
342	Critical Area Treatment	Vegetation Establishment	AC	\$990.00		EQIP
342	Critical Area Treatment	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

Note: Use earthwork by area or volume but not both.

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
382	Fencing	Woven Wire	LF	\$2.60		EQIP
382	Fencing	Welded Wire Panels	LF	\$3.50		EQIP
382	Fencing	Four Strand Barbwire	LF	\$2.15		EQIP
382	Fencing	Five Strand Barbwire	LF	\$2.40		EQIP
382	Fencing	Electric High Tensil Smooth	LF	\$1.55	Includes energizers	EQIP
382	Fencing	Non Electric	LF	\$1.10		EQIP
382	Fencing	Single Gate (10-14 ft)	Each	\$150.00		EQIP
382	Fencing	Double Gate (10-14 ft)	Each	\$200.00		EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
393	Filter Strip	NWSG Estab., Planting - 3 species mix, 4.5lbs/ac 30 ft wide	FT	\$0.14		EQIP
393	Filter Strip	Heavy Chem. Site Prep. For introduced grasses (1 spraying)	AC	\$110.00		EQIP
393	Filter Strip	Heavy Chem. Site Prep. For introduced grasses (2 spraying)	AC	\$220.00		EQIP
393	Filter Strip	Light Disking-1/3 of area each year	AC	\$15.00		EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
666	Forest Stand Improvement	Pre-Commercial Thinning (to maximum 550 stems/AC)	AC	\$140.00		EQIP
666	Forest Stand Improvement	Pre-Commercial Thinning (to maximum 400 stems/AC)	AC	\$200.00		EQIP
666	Forest Stand Improvement	Thin to less than 90 BA	AC	\$30.00		EQIP
666	Forest Stand Improvement	Thin to less than 70 BA	AC	\$60.00		EQIP
666	Forest Stand Improvement	Thin to less than 50 BA	AC	\$120.00		EQIP
666	Forest Stand Improvement	Releasing Desirable Young Trees	AC	\$84.00		EQIP
666	Forest Stand Improvement	Non-commercial Thinning	AC	\$130.00		WHIP
666	Forest Stand Improvement	Vegetation Establishment	AC	\$990.00		EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
381	Silvopasture Establishment	Planting - Pine	AC	\$67.00		EQIP
381	Silvopasture Establishment	Loblolly/Slash	EACH	\$0.05		EQIP
381	Silvopasture Establishment	Long Leaf Bareroot	EACH	\$0.09		EQIP
381	Silvopasture Establishment	Long Leaf Containerized	EACH	\$0.16		EQIP
381	Silvopasture Establishment	Light Site Preparation-Chem or Mech.	AC	\$85.00		EQIP
381	Silvopasture Establishment	Mowing-Site Prep.	AC	\$37.00		EQIP
381	Silvopasture Establishment	Scalping	AC	\$52.00		EQIP
381	Silvopasture Establishment	Subsoiling-Site Prep.	AC	\$35.00		EQIP
381	Silvopasture Establishment	Vegetation Establishment, seeding	AC	\$200.00	Includes seed, seedbed prep, planting, and fertilizer	EQIP
381	Silvopasture Establishment	Vegetation Establishment, sprigging	AC	\$300.00	Includes sprigs, planting, and fertilizer	EQIP
381	Silvopasture Establishment	Vegetation Establishment, no-till	AC	\$150.00	Includes seed, planting, and fertilizer	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
655	Forest Trails and Landings	Water Bars	EACH	\$80.00		EQIP
655	Forest Trails and Landings	Broad Based Dips	EACH	\$160.00		EQIP
655	Forest Trails and Landings	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
412	Grass Waterway	Grading and Shaping	AC	\$1,239.00		EQIP
412	Grass Waterway	Vegetation Establishment	AC	\$990.00		EQIP
412	Grass Waterway	Erosion Control Mat	SF	\$0.70		EQIP
412	Grass Waterway	Mobilization	EACH	\$630.00	Average cost per job, only for hired outside contractors	EQIP

GA NRCS PROGRAM COST LIST - FY 2007

AGRONOMIC PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
422	Hedgerow Planting	Hedgerow -Tree and Shrub Plantings 30 ft wide	FT	\$1.00		WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
512	Pasture and Hayland Planting	Vegetation Establishment, seeding	AC	\$200.00	Includes seed, seedbed prep, planting, and fertilizer	EQIP
512	Pasture and Hayland Planting	Vegetation Establishment, sprigging	AC	\$300.00	Includes sprigs, planting, and fertilizer	EQIP
512	Pasture and Hayland Planting	Vegetation Establishment, no-till	AC	\$150.00	Includes seed, planting, and fertilizer	EQIP
512	Pasture and Hayland Planting	Vegetation Establishment-interseeding legumes, existing pasture	AC	\$34.00	Includes seed & planting.	EQIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
595	Pest Management	Control invasive species/ herbicide only	AC	\$110.00		WHIP
595	Pest Management	Control invasive species/mechanical only	AC	\$400.00		WHIP
595	Pest Management	Mobilization	EA	\$630.00	Average cost per job, only for hired outside contractors	WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
338	Prescribed Burning	Burning (Includes Firebreaks)	AC	\$30.00		EQIP, WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
391	Riparian Forest Buffer	Tree & Shrub Planting - includes components for Zone 1 and 2	AC.	\$265.00	Includes seed, seedbed prep, planting, and fertilizer	EQIP, WHIP
391	Riparian Forest Buffer	NWSG Establishment with cover crop Zone 3	AC	\$200.00	Includes sprigs, planting, and fertilizer	EQIP, WHIP
391	Riparian Forest Buffer	Heavy Chem. Site Prep. For introduced grasses (1 spraying)	AC.	\$110.00	Includes seed, planting, and fertilizer	EQIP, WHIP
391	Riparian Forest Buffer	Heavy Chem. Site Prep. For introduced grasses (2 spraying)	AC.	\$220.00	Includes seed & planting.	EQIP, WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
612	Tree and Shrub Establishment	Planting - Hardwood	AC	\$85.00		EQIP, WHIP
612	Tree and Shrub Establishment	Planting - Pine	AC	\$67.00		EQIP, WHIP
612	Tree and Shrub Establishment	V-Blade Planting	AC	\$78.00		EQIP, WHIP
612	Tree and Shrub Establishment	Loblolly/Slash	Each	\$0.05		EQIP
612	Tree and Shrub Establishment	Long Leaf Bareroot	Each	\$0.09		EQIP, WHIP
612	Tree and Shrub Establishment	Long Leaf Containerized	Each	\$0.16		EQIP, WHIP
612	Tree and Shrub Establishment	Hardwood	Each	\$2.00	Includes all species	EQIP, WHIP
612	Tree and Shrub Establishment	Shrubs (Bareroot)	Each	\$0.10	Includes all species	EQIP, WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
490	Forest Site Preparation	Harrowing-Site prep.	AC	\$50.00		EQIP, WHIP
490	Forest Site Preparation	Heavy Chem. Site Prep. For introduced grasses (1 spraying)	AC	\$110.00		EQIP, WHIP
490	Forest Site Preparation	Heavy Chem. Site Prep. For introduced grasses (2 spraying)	AC	\$220.00		EQIP, WHIP
490	Forest Site Preparation	Heavy Chem. Site Prep. For introduced grasses (3 spraying)	AC	\$330.00		EQIP, WHIP
490	Forest Site Preparation	Heavy Site Preparation-Chem or Mech	AC	\$200.00		EQIP, WHIP
490	Forest Site Preparation	Light Site Preparation-Chem or Mech.	AC	\$85.00		EQIP, WHIP
490	Forest Site Preparation	Light Site Preparation-Herbaceous	AC	\$47.00		EQIP, WHIP
490	Forest Site Preparation	Mowing-Site Prep.	AC	\$37.00		EQIP, WHIP
490	Forest Site Preparation	Scalping	AC	\$52.00		EQIP, WHIP
490	Forest Site Preparation	Subsoiling-Site Prep.	AC	\$35.00		EQIP, WHIP
490	Forest Site Preparation	Prescribed Burning - Site Prep.	AC	\$30.00		EQIP, WHIP
490	Forest Site Preparation	Mobilization	EA	\$630.00		EQIP, WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
472	Use Exclusion	Four Strand Barbwire	LF	\$2.15		WHIP
472	Use Exclusion	Five Strand Barbwire	LF	\$2.40		WHIP
472	Use Exclusion	Non Electric	LF	\$1.10		WHIP
472	Use Exclusion	Single Gate (10-14 ft)	Each	\$150.00		WHIP
472	Use Exclusion	Double Gate (10-14 ft)	Each	\$200.00		WHIP

GA NRCS PROGRAM COST LIST - FY 2007

AGRONOMIC PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
645	Upland Wildlife Habitat Mgt.	Forest Openings-Heavy Site Preparation-Chem or Mech-Woody Veg.	AC	\$200.00		WHIP
645	Upland Wildlife Habitat Mgt.	Forest Openings-Light Site Preparation-Chem or Mech.-Woody Veg	AC	\$85.00		WHIP
645	Upland Wildlife Habitat Mgt.	Forest Openings-Prescribed Burning-Site Prep.	AC	\$30.00		WHIP
645	Upland Wildlife Habitat Mgt.	Forest Openings-Light Disking	AC	\$15.00		WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
658	Wetland Creation	Earthwork	CY	\$3.20		WHIP
658	Wetland Creation	Vegetation/Critical Area	AC	\$990.00		WHIP
658	Wetland Creation	Pipe - 6"	LF	\$6.50	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
658	Wetland Creation	Pipe - 8"	LF	\$12.20	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
658	Wetland Creation	Pipe - 12"	LF	\$14.90	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
658	Wetland Creation	Pipe - 18"	LF	\$23.40	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
658	Wetland Creation	Pipe - 24"	LF	\$30.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
658	Wetland Creation	Flash board Riser-max cost	EA	\$1,200.00		WHIP
658	Wetland Creation	Tree & Shrub Planting incl. components	AC	\$200.00		WHIP
658	Wetland Creation	Mobilization	EA	\$630.00	Average cost per job, only for hired outside contractors	WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
659	Wetland Enhancement	Earthwork	CY	\$3.20		WHIP
659	Wetland Enhancement	Vegetation/Critical Area	AC	\$990.00		WHIP
659	Wetland Enhancement	Pipe - 6"	LF	\$6.50	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
659	Wetland Enhancement	Pipe - 8"	LF	\$12.20	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
659	Wetland Enhancement	Pipe - 12"	LF	\$14.90	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
659	Wetland Enhancement	Pipe - 18"	LF	\$23.40	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
659	Wetland Enhancement	Pipe - 24"	LF	\$30.80	Maximum cost for any type of pipe (CMP, Steel, Alum., HDPE). Includes trenching and installation.	WHIP
659	Wetland Enhancement	Flash board Riser-max cost	EA	\$1,200.00		WHIP
659	Wetland Enhancement	Tree & Shrub Planting incl. components	AC	\$200.00		WHIP
659	Wetland Enhancement	Clemson Barrior	LF	\$83.00		WHIP
659	Wetland Enhancement	Mobilization	EA	\$630.00	Average cost per job, only for hired outside contractors	WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
644	Wetland Management	Woodduck boxes with predator guard	EA	\$80.00		WHIP
644	Wetland Management	Seeding Japanese Millet	AC	\$45.00		WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
657	Wetland Restoration	Ditch plug-earth work	CY	\$3.20		WHIP
657	Wetland Restoration	Micro/marco habitat-ave depth of 9", max depth of 18"	CY	\$3.20		WHIP
657	Wetland Restoration	Tree & Shrub Planting incl. components	AC	\$200.00		WHIP
657	Wetland Restoration	Mobilization	EA	\$630.00	Average cost per job, only for hired outside contractors	WHIP

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
647	Wildlife Buffer	NWSG with herbaceous species establishment, Planting	AC	\$200.00		WHIP
647	Wildlife Buffer	Native herbaceous species establishment, planting only	AC	\$110.00		WHIP
647	Wildlife Buffer	Heavy Chem. Site Prep. For introduced grasses (1 spraying)	AC	\$110.00		WHIP
647	Wildlife Buffer	Heavy Chem. Site Prep. For introduced grasses (2 spraying)	AC	\$220.00		WHIP
647	Wildlife Buffer	Light Disking-1/3 of area each year	AC	\$15.00		WHIP
647	Wildlife Buffer	Unmowed hay buffer (April 1 - Sept 15)	AC	\$50.00		WHIP

GA NRCS PROGRAM COST LIST - FY 2007

INCENTIVE PRACTICES

CODE	PRACTICE	ITEM	UNIT	UNIT COST	NOTES	PROGRAM
329	Residue Mgt, No-Till/Strip Till	Corn, Cotton or Soybean	AC.	\$20.00	Flat Rate Incentive payment -	EQIP
329	Residue Mgt, No-Till/Strip Till	Peanuts (1 year of 3 year rotation)	AC.	\$60.00	Flat Rate Incentive payment -	EQIP
329	Residue Mgt, No-Till/Strip Till	Vegetables (1 year of 3 year rotation)	AC.	\$80.00	Flat Rate Incentive payment -	EQIP
340	Cover Crop	Cover Crop - Incentive Payment (SMALL GRAIN)	AC.	\$10.00	Flat Rate Incentive payment - 1 to 3 years - required with No-till	EQIP, WHIP
340	Cover Crop	Cover Crop - Incentive Payment (LEGUME)	AC.	\$20.00	Flat Rate Incentive payment - 1 to 3 years - required with No-till	EQIP, WHIP
386	Field Borders	Field Border - incentive	AC.	\$60.00	Flat Rate Incentive payment - 1 to 3 years	EQIP
391	Riparian Forest Buffer	Riparian Buffer - incentive	AC.	\$60.00	Flat Rate Incentive payment - 1 to 3 years	EQIP
393	Filter Strips	Filter Strips - incentive	LF.	\$60.00	Flat Rate Incentive payment - 1 to 3 years	EQIP
528	Prescribed Grazing	Includes Nutrient Mgt., Pest Management	AC.	\$10.00	Flat Rate Incentive payment - 1 to 3 years	EQIP
330	Contour Farming	Contour Farming	AC.	\$10.00	Flat Rate Incentive payment - 1 to 3 years	EQIP
449	Irrigation Water Management	IWM Plan (center pivot evaluation by private company)	EA.	\$500.00	Flat Rate Incentive payment - 1 year	EQIP
449	Irrigation Water Management	IWM Plan	AC.	\$10.00	Flat Rate Incentive payment - per year for 3 years	EQIP
100	Comprehensive Nutrient Management Plan	Comprehensive NMP w/ application (base amount)	EA.	\$1,000.00	Flat Rate Incentive payment - 1 time payment	EQIP
100	Comprehensive Nutrient Management Plan	Comprehensive NMP w/ application (add to base amount)	AC.	\$15.00	Flat Rate Incentive payment - per year for 3 years	EQIP
633	Waste Utilization	For dry waste application (in addition to \$15/acre)	AC.	\$30.00	Flat Rate Incentive payment - cap of \$5,000 per year for 3 years (Receipt or Bill of Sale of Equipment purchase required)	EQIP
634	Manure Transfer	Poultry Litter Transfer from designated counties	TON	\$10.00	Flat Rate Incentive payment - 1 year	EQIP
647	Early Successional Habitat	Species specific - 100 ac. Maximum	AC.	\$10.00	Flat Rate Incentive payment - 1 to 3 years	EQIP