

STATEMENT OF WORK
Pond (378)
Hawaii

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables

All design documents shall be developed in accordance with the requirements of the [NRCS Hawaii Field Office Technical Guide \(eFOTG\)](#), Section IV, Conservation Practice Standard and the Conservation Practice Specification.

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Impacts on adjacent properties and structures.
 - d. Compliance with NRCS national and state utility safety policy ([NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06](#)).
 - e. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics ([NEM Subpart 531a](#)).
 - ii. *Site Topographic Survey*.
 - iii. Hydrology/Hydraulics.
 - iv. *Downstream location of structures and buildings*.
 - v. Structural including hazard class as appropriate.
 - vi. Vegetation.
 - vii. *Quantities*.
 - viii. *Estimated Cost*.
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Design Report and Inspection Plan as appropriate ([NEM Part 511, Subpart B Documentation, 511.11](#) and [Part 512, Subchapter D Quality Assurance Activities, 512.30 through 512.32](#)).
4. Operation and Maintenance Plan. *The [NRCS Hawaii Field Office Technical Guide \(eFOTG\)](#), Section IV, Operation and Maintenance Guide for the practice shall be completed and used as the Operation and Maintenance Plan.*
5. Certifications that the design meets practice standard criteria and comply with applicable laws and regulations ([NEM Subpart A, 505.03 \(b\) \(2\)](#)).
6. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used.
 - b. Inspection records.

STATEMENT OF WORK
Pond (378)
Hawaii

5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied.
 - b. Drawings.
 - c. Final quantities.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits ([NEM Subpart A, 505.03 \(c\) \(1\)](#)).
3. Progress reporting.

REFERENCES

- [NRCS Hawaii Field Office Technical Guide \(eFOTG\)](#), Section IV, Pond (378) Conservation Practice Standard, Conservation Practice Specification, and Operation and Maintenance Guide
- [NRCS National Environmental Compliance Handbook](#)
- [NRCS Cultural Resources Handbook](#)
- [NRCS National Engineering Manual \(NEM\)](#)