Payment Schedule Results

Practice	Cost Share		Payment
Code	<u>Program</u>	ractice/Activity Nan ractice/Activity Typ Unit Type	Rate
130	EQIP	DWMP // MP w/Topographic St Number	\$1,177.50
130	EQIP-HU	DWMP // MP w/Topographic St Number	\$1,413.00
130	WHIP	DWMP MP w/Topographic St Number	NA

IA Geographic <u>Area</u> Statewide Statewide Statewide

\$0.00

Payment Schedule Development Methodology

	9	EQIP	EQIP-HU	WHIP			
		Program	Program	Program	EQIP	EQIP-HU	WHIP
		Payment	Payment	Payment	Payment	Payment	Payment
Cost Category	Cost/Unit	<u>Percentage</u>	<u>Percentage</u>	<u>Percentage</u>	<u>Rate</u>	Rate	Rate
Materials	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Equipment/Installation	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Labor	\$1,570.00	75%	90%	NA	\$1,177.50	\$1,413.00	NA
Mobilization	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Operation & Maintenance (Annual)	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Acquisition of Technical Knowledge	\$0.00	75%	90%	NA	\$0.00	\$0.00	NA
Forgone Income (Annual)	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Risk	\$0.00	0%	0%	NA	\$0.00	\$0.00	NA
Administration & Permit Costs	<u>\$0.00</u>	0%	0%	NA	\$0.00	\$0.00	<u>NA</u>
Total:	\$1,570.00				\$1,177.50	\$1,413.00	NA

Cost Data

Typical Implementation Sce

The cost associated with development of a conservation plan to support the Drainage Water Management (DWM) system which will meet the requirements of the FOTG Drainage Water Management Practice Standard (554). A typical conservation plan for this scenario would be to develop a drainage water management plan for a 20 acre, existing patterned tiled, cropland field with plans for the installation of several water control structures to control ground water levels for the purposes of improving water quality and or improved soil environment for plant growth. Detailed topographic information is not available. A topographic survey will be needed to develop the plan.

Geographic Area: Statewide Unit for Cost Estimate: Number

Practice Life (Years): Discount Rate (%/Year): 4.2%

Cost/Unit

\$0.00 **Materials**

Equipment/Installation \$0.00

\$1,570.00 **Labor**

Meet with stake holders: 1 person 0.5 hours Topographic survey: 2 person crew - 8 hours total

Tile pattern configuration investigation: 1 person - 4 hours total

Post processing survey data: 1 person - 2 hours 3 dimensional map creation - 1 person - 3 hours

Management Plan Creation:

- Maps 2 hours - Locating water control str(s) 1 hour - Operation and Maintenance 1 hour - Monitoring 1 hour

Plan delivery to Landowner and NRCS all deliverables - 1 person 3 hours

3 to 4 trips to and from the site: 4 hours

\$0.00 **Mobilization**

Operation & Maintenance (Annual)

\$0.00

Acquisition of Technical Knowledge

\$0.00

Forgone Income (Annual) None

Risk \$0.00

None

\$0.00 **Administration & Permit Costs**

None

Total Cost Estimate: \$1,570.00