

**STATEMENT OF WORK**  
**Fence (382)**  
**Kansas**  
**December 2011**

**State contact: State Resource Conservationist**

**These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific statements of work.**

## **DESIGN**

---

### **Deliverables**

1. Design documentation that will demonstrate that the criteria in the Natural Resources Conservation Service (NRCS) practice standard have been met and are compatible with other planned and applied practices.
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. Compliance with NRCS national and state utility safety policy (National Engineering Manual [NEM] Sections 503.0 through 503.06 and NEM Part KS503)
  - d. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to the following:
    - i. Location/alignment
    - ii. Height
    - iii. Size
    - iv. Spacing
    - v. Type of material
2. Written plans and specifications (including sketches and drawings) shall be provided to the client that adequately describe the requirements to install the practice (Form KS-ECS-382, Fence).
3. Identify fields where practice is to be applied on a conservation plan map.
4. Certification that the design meets practice standard criteria and complies with applicable laws and regulations (NEM Part 505.03(a)(3)).
5. Design modifications during installation as required.
6. If enrolled in a conservation program, this practice must meet all conditions and requirements of program enrollment that may exceed the practice standard.

Note: Refer to Form KS-ECS-382

## **INSTALLATION**

---

### **Deliverables**

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
  - a. Actual materials used (NEM Part 512.33)
  - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws and regulations and NRCS policies during installation.
7. Certification that the installation process and materials meet design and permit requirements.

Note: Refer to Form KS-ECS-382

**STATEMENT OF WORK  
Fence (382)  
Kansas  
December 2011**

**CHECKOUT**

---

**Deliverables**

1. As-built documentation.
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits [NEM Part 505.03(c)(1)].
3. Progress reporting.
4. Follow-up conference with client and contractor.

Note: Refer to Form KS-ECS-382

**REFERENCES**

---

- NRCS electronic Field Office Technical Guide (eFOTG), Section IV, Conservation Practice 382, Fence
- NRCS Form KS-ECS-382
- NRCS NEM.
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook