

CONSTRUCTION SPECIFICATION

MI-151. STRUCTURE REMOVAL

1. **SCOPE**

The work shall consist of the removal, salvage and disposal of structures (including fences) shown on the drawings or that must be removed to perform other items of work.

2. **MARKING**

Each structure unit to be removed will be marked by the NRCS inspector. Structures to remain undisturbed or to be salvaged will be designated by special markings.

3. **SALVAGE**

Structures that are designated to be salvaged shall be carefully removed and neatly placed in the specified storage areas. Salvaged structures that are capable of being disassembled shall be dismantled into individual members or sections. Such structures shall be neatly matchmarked with paint prior to disassembly. All pins, nuts, bolts, washers, plates, and other loose parts shall be marked or tagged to indicate their proper locations in the structure and shall be fastened to the appropriate structural member or packed in suitable containers. Materials from fences designated to be salvaged shall be placed outside the work area on the property from which they were removed. Wire shall be rolled into uniform rolls of convenient size. Posts and rails shall be neatly piled.

4. **DISPOSAL OF REFUSE MATERIALS**

Unless otherwise specified, refuse materials resulting from structure removal shall be burned or buried at locations approved by the NRCS inspector or otherwise disposed of as specified or approved by the NRCS inspector. Disposal by burning shall be in accordance with local rules and regulations.