

STATEMENT OF WORK
Diversion (362)
Missouri

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN**Deliverables:**

1. Survey notes which show that a thorough and detailed site survey was completed.
 - a. Survey notes shall be in accordance with NRCS Technical Release 62, Engineering Field Handbook, Chapter 1 and/or standard industry practice.
 - b. If survey equipment with automatic / electronic data collection devices is used, a print out of the data and/or a reference to the location where the electronic file is stored shall be included in the file.
 - c. Elevations shall be referenced to a bench mark. A temporary bench mark with an assumed elevation is acceptable.
2. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Hydrology/Hydraulics
 - Drainage Area
 - Rainfall and Runoff Volumes
 - Elevation-Storage Volume Relationship
 - Spillway Capacities (type, sizes, elevations)
 - Earthfill and Excavation Quantities
 - ii. Outlet capacity and stability
 - iii. Vegetation
 - (See Critical Area Planting 342 Statement of Work)
 - iv. Environmental Considerations
3. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits...
4. Operation and Maintenance Plan
5. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03 (a) (3)).
6. Design modifications during installation as required.

INSTALLATION**Deliverables**

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

STATEMENT OF WORK
Diversion (362)
Missouri

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied
 - Profile and cross section of channel and ridge
 - Adequacy and dimensions of outlet
 - Vegetation establishment if required (See Critical Area Planting 342 Statement of Work)
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Diversion, 362
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook