

STATEMENT OF WORK
Manure Pile Area (NY749)
New York State

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

Items marked with an asterisk (*) will be delivered to the Designated Conservationist

DESIGN**Deliverables:**

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM Subpart 531a)
 - ii. Capacity, Maximum Amount of Manure Allowed on the Manure Pile Area
 - iii. Clean Water Exclusion by Diversion, Dike or other Structure
 - iv. Environmental Considerations (e.g. air quality, bio-security, leaching, flow-path to nearby surface water)
 - v. Safety Considerations (NEM Part 503-Safety, Subpart A, 503.10 through 503.12)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits...
3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
4. ***Operation and Maintenance Plan.**
5. ***In cases where the practice location has changed, a statement to NRCS notifying the agency of the change in location as well as a map showing the new practice location. The statement will include the landowner's name, program name, contract number and practice name.**
6. ***Signed Warranty of Technical Services Provided** form indicating compliance with practice standard criteria and applicable laws and regulations.
7. Design modifications during installation as required.

INSTALLATION**Deliverables**

1. Delay of installation until TSP receives written verification from NRCS that all NEPA requirements have been satisfied for this practice.
2. Pre Installation conference with client and contractor.
3. Verification that client has obtained required permits.
4. Staking and layout according to plans and specifications including applicable layout notes.
5. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used (Part 512, Subchapter D Quality Assurance Activities, 512.33)
 - b. Inspection records
6. Facilitate and implement required design modifications with client and original designer
7. ***Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.**
8. ***Signed Warranty of Technical Services Provided** form indicating compliance with practice standard criteria and applicable laws and regulations.

STATEMENT OF WORK
Manure Pile Area (NY749)
New York State

CHECK OUT

Deliverables

1. ***As-Built documentation.**
 - a. **Extent of practice units applied**
 - b. **Drawings**
 - c. **Final quantities**
2. ***Signed *Warranty of Technical Services Provided* form indicating compliance with practice standard criteria and applicable laws and regulations.**
3. **Progress reporting.**

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Manure Pile Area, NY749
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook
- National Engineering Handbook (NEH), Part 651, Agricultural Waste Management Field Handbook (AWMFH)
- National Engineering Handbook Part 637, Chapter 2