

STATEMENT OF WORK (SOW)
IRRIGATION WATER CONVEYANCE - DITCH AND CANAL LINING, PLAIN CONCRETE (428A)
SOUTH DAKOTA
CONTACT: JAY COBB (605) 352-1260
ISSUED OCTOBER 29, 2004

These deliverables apply to this individual practice. For other planned practice deliverables, please refer to those specific SOW's.

DESIGN

Deliverables

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices:
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Compliance with NRCS national and state utility safety policy (NEM, Part 503-Safety, Subpart A, Engineering Activities Affecting Utilities, 503.00 through 503.06).
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Capacity.
 - ii. Channel velocity/Stability.
 - iii. Concrete details (e.g., type, thickness, admixtures)
 - iv. Environmental Considerations.
2. Sufficient copies of written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Operation and maintenance plan.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM, Subpart A, 505.03 (a)(3)).
5. Develop a cost estimate from the established cost lists for installation of the systems as identified on the approved construction drawings.
6. Provide an anticipated installation schedule.
7. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used (NEM, Part 512, Subpart D, Quality Assurance Activities, 512.33),
 - b. Inspection records.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, Tribal, and local laws, regulations, and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT

Deliverables

1. As-Built documentation:
 - a. Extent of practice units applied.
 - b. Drawings.
 - c. Final quantities.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits NEM, Subpart A, 505.03(c)(1)).
3. Progress reporting.

REFERENCES

- NRCS South Dakota Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Irrigation Water Conveyance Ditch and Canal Lining, Plain Concrete (428A)
- NRCS NEM
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook