

**STATEMENT OF WORK (SOW)  
MANURE TRANSFER (634)  
SOUTH DAKOTA  
CONTACT: JAY COBB (605) 352-1260  
ISSUED OCTOBER 29, 2004**

These deliverables apply to this individual practice. For other planned practice deliverables, please refer to those specific SOW's.

## **DESIGN**

---

### **Deliverables**

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices:
  - a. Practice purpose(s) as identified in the conservation plan.
  - b. List of required permits to be obtained by the client.
  - c. Impacts on adjacent properties and structures.
  - d. Compliance with NRCS national and state utility safety policy (NEM, Part 503-Safety, Subpart A, Engineering Activities Affecting Utilities, 503.00 through 503.06).
  - e. List of facilitating practices.
  - f. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
    - i. Geology and Soil Mechanics (NEM, Subpart 531a).
    - ii. Hydraulics.
    - iii. Structural and Mechanical Components.
    - iv. Environmental Considerations (e.g., air quality, biosecurity).
    - v. Safety Considerations (NEM, Part 503-Safety, Subpart A, 503.06 through 503.12).
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Design Report and Inspection Plan as appropriate (NEM, Part 511, Subpart B, Documentation, 511.11, and Part 512, Subpart D, Quality Assurance Activities, 512.30 through 512.32).
4. Operation and Maintenance Plan.
5. Certifications that the design meets practice standard criteria and comply with applicable laws and regulations (NEM, Subpart A, 505.03(b)(2)).
2. Design modifications during installation as required.

## **INSTALLATION**

---

### **Deliverables**

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate):
  - a. Actual materials used (NEM, Part 512, Subpart D, Quality Assurance Activities, 512.33.)
  - b. Inspection records.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, Tribal, and local laws, regulations, and NRCS policies during installation.
7. Certification that the installation process and materials meet design and permit requirements.

## **CHECK OUT**

---

### **Deliverables**

1. As-Built documentation:
  - a. Extent of practice units applied.
  - b. Drawings.
  - c. Final quantities.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM, Subpart A, 505.03(c)(1)).
3. Progress reporting.

## REFERENCES

---

- NRCS South Dakota Technical Guide (eFOTG), Section IV, Conservation Practice Standard Manure Transfer (634)
- NRCS Agricultural Waste Management Field Handbook
- NRCS NEM
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook