

## **STATEMENT OF WORK Land Clearing (460) Virginia**

**These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific Statements of Work.**

### **DESIGN**

---

#### **Deliverables:**

1. Design documentation that will demonstrate that the criteria in the NRCS practice standard have been met and are compatible with other planned and applied practices:
  - a. Identify, discuss and document client needs, and recommend method of resolution.
  - b. Practice purpose(s) as identified in the conservation plan.
  - c. List of required permits to be obtained by the client.
  - d. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06). This includes contacting MISS UTILITY (811 or 1-800-552-7001) a minimum of 3 days before beginning construction.
  - e. List of associated practices (conservation practice name and number).
  - f. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
    - i. Determination of appropriate method, intensity and timing to efficiently and safely remove trees, stumps and other vegetation.
    - ii. Designating appropriate setbacks from wetlands, water bodies and streams.
    - iii. Mitigation of erosion, runoff, soil compaction and soil displacement to acceptable levels during the transition period to the desired land use.
2. Written plans and specifications, including sketches and drawings, shall be provided to the client that adequately describe the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements in the Land Clearing (460) conservation practice standard.
3. Operation and Maintenance Plan.
4. Certification that the design meets NRCS standards and specifications and is in compliance with permits (NEM VA505.03, Amendment VA-18).

### **INSTALLATION**

---

#### **Deliverables:**

1. Pre-installation conference with client.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Application guidance as needed.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.

### **CHECK OUT**

---

#### **Deliverables:**

1. Records of application.
  - a. Extent of practice units applied.
  - b. Actual mitigation measures used and applied.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM VA505.03, Amendment VA-18).
3. Progress reporting.

**STATEMENT OF WORK  
Land Clearing (460)  
Virginia**

**REFERENCES**

---

- VA NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Land Clearing, 460.
- VA NRCS Field Office Technical Guide (eFOTG), Section IV, Operation and Maintenance Plan – Land Clearing, 460.
- NRCS National Forestry Handbook (NFH), Part 636.4.
- NRCS National Engineering Manual (NEM).
- 210-V-NEM Part 505-Non-NRCS Engineering, Amendment VA-18.
- NRCS National Environmental Compliance Handbook.
- NRCS Cultural Resources Procedures Handbook.