

CONSTRUCTION SPECIFICATION

VA-711. REMOVAL OF WATER

1. **SCOPE**

The work will consist of the removal of surface water and ground water as needed to perform the required construction.

2. **DIVERTING SURFACE WATER**

Protective measures needed to divert streamflow and other surface water will be built, maintained and operated during construction.

3. **DEWATERING CONSTRUCTION AND BORROW SITES**

The construction site will be dewatered and kept free of standing water or excessively muddy conditions as needed for proper execution of the construction work. Dewatering will include furnishing, installing, operating and maintaining all water containment facilities, conveyance channels, diversion facilities, pumps and piping assemblies, and other necessary equipment as needed.

4. **REMOVAL OF TEMPORARY WORKS**

After the temporary works have served their purposes or prior to the Contractor leaving the site, they will be removed or graded to present a sightly appearance without interfering with permanent drainage systems or stream flows.

5. **EROSION AND POLLUTION CONTROL**

All temporary works will be accomplished in such a manner that erosion and the transmission of sediment and other pollutants are minimized. All work will be in compliance with all federal, state and local laws, ordinances and regulations governing such operations.