

USDA – NATURAL RESOURCES CONSERVATION SERVICE – VERMONT
Conservation Security Program Operation and Maintenance Factors
(Annual cost of O&M as a percentage of installation cost)
December 2002

<u>Conservation Practice Name and Code</u>	<u>Unit</u>	<u>O&M Factor</u>
Access Road – 560	feet	.15
Agrichemical Handling Facility - 596	number	.01
Animal Trails and Walkways - 575	feet	.12
Brush Management – 314	acre	.01
Conservation Cover – 327	acre	.03
Conservation Crop Rotation – 328	acre	.00
Contour Buffer Strips – 332	acre	.02
Contour Farming – 330	acre	.00
Contour Stripcropping – 585	acre	.01
Cover and Green Manure – 340	acre	.00
Critical Area Planting – 342	acre	.03
Diversion – 362	feet	.02
Early Successional Habitat Development – 647	acre	.03
Fence – 382	feet	.02
Field Border – 386	feet	.01
Filter Strip – 393	acre	.02

<u>Conservation Practice Name and Code</u>	<u>Unit</u>	<u>O&M Factor</u>
Fish Passage – 396	number	.03
Forage Harvest Management – 511	acre	.00
Forest Site Preparation – 490	acre	.00
Forest Stand Improvement – 666	acre	.03
Forest Trails and Landings – 655	acre	.15
Grade Stabilization Structure – 410	number	.01
Grassed Waterway – 412	acre	.02
Heavy Use Area Protection – 561	acre	.05
Hedgerow Planting – 422	feet	.05
Land Clearing – 460	acre	.00
Land Smoothing – 466	acre	.00
Lined Waterway or Outlet – 468	feet	.10
Mulching – 484	acre	.00
Nutrient Management – 590	acre	.00
Obstruction Removal – 500	acre	.00
Open Channel – 582	feet	.05
Pasture and Hayland Planting – 512	acre	.01
Pest Management – 595	acre	.00

<u>Conservation Practice Name and Code</u>	<u>Unit</u>	<u>O&M Factor</u>
Pipeline – 516	feet	.02
Pond – 378	number	.01
Pond Sealing – 521A, B, C	number	.01
Prescribed Burning – 338	acre	.01
Prescribed Grazing – 528A	acre	.00
Residue Management – 329A, B, C	acre	.00
Residue Management, Seasonal – 344	acre	.00
Restoration and Management of Declining Habitats – 643	acre	.03
Riparian Forest Buffer – 391	acre	.01
Riparian Herbaceous Buffer – 390	acre	.01
Roof Runoff Management – 558	number	.03
Sediment Basin – 350	number	.03
Spring Development – 574	number	.05
Stream Channel Stabilization – 584	feet	.02
Stream Habitat Management – 395	acre	.02
Streambank and Shoreline Protection – 580	feet	.03
Structure for Water Control – 587	number	.01
Subsurface Drain – 606	feet	.03

<u>Conservation Practice Name and Code</u>	<u>Unit</u>	<u>O&M Factor</u>
Surface Drainage Field Ditch – 607	feet	.03
Surface Drainage Main or Lateral – 608	feet	.03
Tree/Shrub Establishment – 612	acre	.01
Tree/Shrub Pruning – 660A	acre	.00
Underground Outlet – 620	feet	.01
Upland Wildlife Habitat Management – 645	acre	.00
Use Exclusion – 472	acre	.03
Water and Sediment Control Basin – 638	number	.03
Water Well – 642	number	.01
Watering Facility – 614	number	.02
Wetland Creation – 658	acre	.01
Wetland Enhancement – 659	acre	.01
Wetland Restoration – 657	acre	.01
Wetland Wildlife Habitat Management – 644	acre	.00
Windbreak/Shelterbelt Establishment – 380	feet	.01
Windbreak/Shelterbelt Renovation – 650	feet	.01