

SURFACE DRAINAGE MAIN OR LATERAL SPECIFICATIONS

CLEARING

The channel area shall be cleared of trees, logs, stumps, and other materials necessary for construction. Care must be taken to protect all trees to be saved for environmental purposes. All material shall be disposed of by an acceptable method as shown on the plans.

EXCAVATION

Channels shall be excavated to line and grade as shown on the plans or as staked in the field. The excavated surface shall be reasonably smooth. Construction activities shall be carried on in a manner that will not restrict flow from upstream channels. Care must be taken to reduce and prevent pollution of water.

SPOIL

Spoil shall be disposed of as shown on the plans or as marked in the field.

STRUCTURES

All structures and other related protection devices shall be installed as the work progresses to permit proper functioning of the ditch and to prevent environmental damage during the installation period.

VEGETATION

Vegetation shall be planted at times and rates shown in the plans or in the specifications for each job.