

**NATURAL RESOURCES CONSERVATION SERVICE
MISSOURI CONSTRUCTION SPECIFICATION**

SEDIMENT BASIN

CODE 350

GENERAL

Construction operations shall be carried out in such a manner and sequence such that erosion and air and water pollution will be minimized and held within legal limits. **A land disturbance permit from the Missouri Department of Natural Resources may be needed if the disturbed area is greater than one acre in size.**

The completed job shall present a workmanlike appearance and shall conform to the line, grades, and elevations shown on the drawings or as staked in the field.

All operations shall be carried out in a safe and skillful manner. Safety and health regulations shall be observed and appropriate safety measures used.

Foundation preparation

The foundation area shall be cleared of trees, logs, stumps, roots, brush, boulders, sod, and rubbish. A minimum of 3 inches of topsoil and sod shall be stripped from foundation area. The topsoil and sod are to be stockpiled.

Existing stream channels crossing the foundation area shall be sloped 2:1 or flatter and deepened and widened as necessary to remove unconsolidated sediments, stumps, roots, and other objectionable material and to accommodate compaction equipment.

After stripping, the foundation area will be prepared to assure bonding with the fill by removing loose dry material, scarifying, diking, adjusting moisture, and compacting as necessary.

CUTOFF TRENCH

The minimum depth shown on the drawing is an estimate. Final depth of cutoff trench shall be determined by observation. Side slopes of cutoff trench shall be 1 1/2:1 or flatter, as needed to be stable. Sand, gravel, and other water conducting materials shall be removed to prevent leakage under the dam.

When rock or other hard layers are encountered, a bulldozer mounted single tooth ripper shall be used to loosen all weathered material. Stair-step rock or hard ledges will require handwork to remove all loose materials and hand backfill with clay before machine backfill is started.

In some cases, it will be necessary to thoroughly clean the bottom of rock core trenches to ensure good bond and prevent leakage.

FILL PLACEMENT

The material placed in the fill shall be free of detrimental amounts of sod, roots, frozen soil, stones over 6 inches in diameter (except for rock fills), and other objectionable material. To the extent they are suitable, excavated materials are to be used as fill material. The distribution and gradation of materials shall be such that there will be no lenses, pockets, streaks, or layers of material differing substantially in texture or gradation from the surrounding material. Where it is necessary to use material of varying texture and gradation, the more plastic material shall be placed in the center and upstream portions of the fill. Foundation areas and cutoff trenches shall be kept free of standing water when fill is being placed on them.

The placing and spreading of the fill shall be started at the lowest point of the foundation and the fill shall be brought up in approximately horizontal layers not to exceed 9 inches in thickness. Each layer shall be spread, processed, and shall be compacted by one of the following methods, as specified on the drawings:

- Dozer - Complete coverage by tread or track of hauling or spreading equipment. Each lift shall not exceed 5 inches in thickness.
- Roller - two passes of standard tamping type roller over the entire area to be compacted. Complete coverage by the treads of loaded hauling equipment is considered equivalent to two (2) passes of tamping roller. Each lift shall not exceed 9 inches in thickness.

The tamping-type roller shall have tampers or feet projecting not less than six (6) inches from the surface of the drum and shall have a minimum static load on each tamper of 250 pounds per square inch of tamping area. Tamping rollers with minimum static load on each tamper of 125 pounds per square inch of tamping area may be used if the number of passes is increased to four (4) or the thickness of lifts is reduced to four (4) inches. (Sheepsfoot or wedgefoot drum rollers are considered tamping rollers.)

An opening in the fill for drainage during construction is permitted. Care must be taken when the fill closure is made to assure proper compaction and bond of the fill material to the existing fill. The opening shall have a bottom width wide enough to allow equipment to work in a horizontal plane. As the drainage opening is filled, the side slopes of the existing fill shall be excavated until solid material is uncovered and good bond can be attained.

MOISTURE CONTROL

The minimum moisture content of the fill material and foundation shall be such that, when kneaded in the hand, the fill material will form a ball which does not readily separate. The maximum moisture content is when conditions are too wet for efficient use of the hauling and compaction equipment.

BORROW AREAS

All borrow areas outside the pool area shall be graded and left so they are well drained, protected from erosion, and may be seeded. Borrow areas inside the pool area shall have side slopes of 2:1 or flatter.

PLACEMENT OF TOPSOIL

Available topsoil should be placed on the auxiliary spillway, the downstream slope, top, exposed surface of the upstream slope of the dam, and any other disturbed areas.

VEGETATION

Refer to JS-AGRON-25 for seeding and mulching recommendations or equivalent.

Additional Details: _____

