

STATEMENT OF WORK
Channel Bank Vegetation (322)
Oklahoma

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM part 503-Safety, Section 503.00 through 503.22)
 - d. List all required and/or facilitating practices
 - e. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - i. Channel side slopes
 - ii. Bank stabilization techniques
 - iii. Vegetative species selected, rates, dates, seedbed preparation and seeding method
 - iv. Cover crop or mulch requirements
 - v. Nutrients required
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Operation and maintenance plan
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations
5. Design modifications during installation as required

Note: Conservation practice Critical Area Planting (342) will be required with this practice for establishment procedures, planting rate, planting dates and method of planting. OK-CPA-4 and/or OK-CPA-4A will be used to document vegetative plantings. A planner certified in nutrient management will be required.

INSTALLATION

Deliverables

1. Pre-installation conference with client
2. Verification that client has obtained required permits
3. Staking and layout according to plans and specifications including applicable layout notes
4. Installation guidance as needed
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation
7. Certification that the installation process and materials meets design and permit requirements

Note: Conservation practice Critical Area Planting (342) will be required with this practice for establishment procedures, planting rate, planting dates and method of planting. OK-CPA-4 and/or OK-CPA-4A will be used to document vegetative plantings. A planner certified in nutrient management will be required.

CHECK OUT

Deliverables

1. Records of application
 - a. Extent of practice units applied
 - b. Actual materials used
2. Certify and document that all the criteria listed in the Design Deliverables meet NRCS standards and specifications and are in compliance with permits.
3. Progress reporting

Note: Conservation practice Critical Area Planting (342) will be required with this practice for establishment procedures, planting rate, planting dates and method of planting. OK-CPA-4 and/or OK-CPA-4A will be used to document vegetative plantings. A planner certified in nutrient management will be required.

STATEMENT OF WORK
Channel Bank Vegetation (322)
Oklahoma

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard Channel Bank Vegetation-322
- NRCS National Engineering Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook