

**STATEMENT OF WORK (SOW)
WASTE STORAGE FACILITY (313)
SOUTH DAKOTA
CONTACT: JAY COBB (605) 352-1260
ISSUED MARCH 1, 2006**

These deliverables apply to this individual practice. For other planned practice deliverables, please refer to those specific SOW's.

DESIGN

Deliverables

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices:
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Compliance with NRCS national and state utility safety policy NEM, Part 503 -Safety, Subpart A, Engineering Activities Affecting Utilities, 503.00 through 503.06).
 - d. List of facilitating practices.
 - e. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM, Subpart 531a).
 - ii. Storage Volume and Maximum Operating Level.
 - iii. Structural, Mechanical, and Appurtenances.
 - iv. Nutrient Management Plan.
 - v. Maximize Clean Water Diversion.
 - vi. Environmental Considerations (e.g., liner failure, location, breaching, air quality).
 - vii. Safety Considerations (NEM, Part 503-Safety, Subpart A, 503.06 through 503.12).
2. Sufficient copies of written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Specific detailed requirements for Waste Storage Facility design and the development of construction plans and specifications are outlined in the South Dakota Engineering and Spot Checking Manual (SDEDSCM), under the Waste Management Structure Practice Requirements. Where specific forms or job sheets are mentioned in the SDEDSCM, an equivalent may be substituted. The guidance contained in this manual shall be considered as the minimum acceptable for this practice.
4. Design Report and Inspection Plan as appropriate (NEM, Part 511, Subpart B, Documentation, 511.11, and Part 512, Subpart D, Quality Assurance Activities, 512.30 through 512.32).
5. Operation and Maintenance Plan.
6. Certifications that the design meets practice standard criteria and comply with applicable laws and regulations (NEM, Subpart A, 505.03(b)(2)).
7. Develop a cost estimate from the established cost lists for installation of the systems as identified on the approved construction drawings.
8. Provide an anticipated installation schedule.
9. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate):
 - a. Actual materials used (NEM, Part 512, Subpart D, Quality Assurance Reviews, 512.33).
 - b. Inspection records.
5. Specific detailed requirements for Waste Storage Facility installation are outlined in the SDEDSCM, under the Waste Management Structure Practice Requirements. Where specific forms or job sheets are mentioned in the SDEDSCM, an equivalent may be substituted. The guidance contained in this manual shall be considered as the minimum acceptable for this practice.

INSTALLATION

Deliverables Cont.

6. Design Modifications and Changes:
 - a. Facilitate and implement required design modifications with client and original designer.
 - b. Any modification or change which results in a cumulative increase in the contract price will be discussed with the District Conservationist and the client.
7. Advise client/NRCS on compliance issues with all federal, state, Tribal, and local laws, regulations, and NRCS policies during installation.
8. Certification that the installation process and materials meet design and permit requirements.

CHECK OUT

Deliverables

1. As-Built documentation:
 - a. Extent of practice units applied.
 - b. Drawings.
 - c. Final quantities.
2. Provide the NRCS, client, and contractor copies of the final As-Built quantities.
3. Revise the cost estimate prepared during the design phase to reflect design modifications and quantity variations.
4. Provide a written justification for changes and modifications which resulted in a cumulative increase of the contract price.
5. Specific detailed requirements for Waste Storage Facility checkout design and the development on construction plans and specifications are outlined in the SDEDSM, under the Waste Management Structure Practice Requirements. Where specific forms or job sheets are mentioned in the SDEDSM, an equivalent may be substituted. The guidance contained in this manual shall be considered as the minimum acceptable for this practice.
6. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM, Subpart A, 505.03(c)(1)).
7. Progress reporting.

REFERENCES

- South Dakota Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Waste Storage Facility (313)
- NRCS Agricultural Waste Management Field Handbook
- NRCS NEM
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook
- SDEDSM