

**STATEMENT OF WORK**  
**WILDLIFE WATERING FACILITY**  
**CODE (648)**

**DESIGN (PLANNING REQUIREMENTS)**

---

**Deliverables:**

- 1 Document the planned purpose and specification(s) in the practice narrative, or on a separate sheet that is referenced in the practice narrative.
  - a. Practice purpose(s) as identified in the conservation plan.
  - b. List of required permits to be obtained by the client
  - c. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
    - i. Capacity
    - ii. Overflow protection
    - iii. Materials
    - iv. Climatic considerations (e.g. evaporation, freezing, etc.)
    - v. Target species and number of animals
- 2 Written plans and specifications including sketches and drawings shall be provided to the client that adequately describe the requirements to install the practice and obtain necessary permits
- 3 Practice narrative will be included in the Conservation Plan of Operations (the Contract Support Document may serve as the Conservation Plan of Operations in certain situations).
- 4 Operation and maintenance plan
- 5 Certification that the design meets practice standard criteria and comply with applicable laws and regulations
- 6 Design modifications during installation as required

**INSTALLATION**

---

**Deliverables**

- 1 Pre-application conference with client and contractor.
- 2 Verification that client has obtained required permits.
- 3 Staking and layout according to plans and specifications including applicable layout notes
- 4 Application inspection
  - a. Actual materials used
  - b. Inspection records
- 5 Facilitate and implement required design modifications with client and original designer
- 6 Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation
- 7 Certification that the application process and materials meet design and permit requirements
- 8 Provide application guidance as needed.

## **CHECK OUT**

---

### **Deliverables**

- 1 As-built documentation
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities of materials used
- 2 Certification that the application meets NRCS Standards and Specifications and permit requirements.
- 3 Document findings in the Conservation Assistance Notes, Conservation Plan of Operations, and if applicable, the Contract Support Document (the Contract Support Document may serve as the Conservation Plan of Operations in certain situations.
- 4 Progress reporting.

## **REFERENCES**

---

See references listed in Conservation Practice Standard