## UNITED STATES DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE , TEXAS

## OPERATION AND MAINTENANCE PLAN ROOF RUNOFF STRUCTURE

Sponsor/Land user:			Date:		
Address:					
Legal description of practice location:	SEC	T	R		

A properly operated and maintained roof runoff management system is an asset to your farm. This system was designed and installed to divert roof runoff water before becoming in contact with agriculture wastes. The estimated life span of this installation is at least 10 years. The life of this installation can be assured and usually increased by developing and carrying out a good operation and maintenance program.

This practice will require you to perform periodic maintenance to maintain satisfactory performance. Here are some recommendations to help you develop a good operation and maintenance program.

## **GENERAL RECOMMENDATIONS**

- Maintain all gutters and downspouts free from foreign material that reduces their ability to function.
- Maintain all fasteners to securely hold all gutters and downspouts in place.
- Maintain all underground conveyance lines free from debris and obstructions.
- Maintain all screens and strainers in place and in good working condition.
- Maintain all gutters and downspouts in good working condition and promptly repair if damaged.
- Remove any trees or branches that deposit debris and reduce the capacity of the system.

## SPECIFIC RECOMMENDATIONS FOR YOUR INSTALLATION CONTACT YOUR LOCAL NATURAL RESOURCES CONSERVATION SERVICE OFFICE

USDA-NRCS-TX OM-PS-558 2/2 AUGUST 2001

FOR ANY ADDITIONAL TECHNICAL ASSISTANCE YOU MIGHT NEED FOR

STRUCTURE.

IMPLEMENTATION OF THIS OPERATION AND MAINTENANCE PLAN FOR YOUR