

STATEMENT OF WORK

Pond Sealing or Lining – Soil Dispersant Treatment- 521B

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in practice standard have been met and are compatible with planned and applied practices
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM part 503-Safety, Section 503.00 through 503.6)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Hydrogeology
 - ii. Type of Liner
 - iii. Application Rate, Liner Thickness, Compaction and Moisture Requirements
 - iv. Liner Protection
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
4. Operation and maintenance plan
5. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.3)
6. Design modifications during installation as required

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor
2. Verification that client has obtained required permits
3. Staking and layout according to plans and specifications including applicable layout notes
4. Installation inspection
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation
7. Certification that the installation process and materials meets design and permit requirements

CHECK OUT

Deliverables

1. As-built documentation
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.3)
3. Progress reporting

**STATEMENT OF WORK
Pond Sealing or Lining – Soil Dispersant Treatment- 521B**

REFERENCES

- Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard, Pond Sealing or Lining - 521abcd
- National Engineering Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook
- Field Office Technical Guide (eFOTG), Section IV, Job Sheet, Pond Sealing or Lining – 521A Flexible Membrane
- Field Office Technical Guide (eFOTG), Section IV, Job Sheet, Pond Sealing or Lining – 521B/C Sealing a Pond with Additives

CONTACT INFORMATION

Bill Prince
State Environmental Engineer
334-887-4513
Bill.Prince@al.usda.gov