Practice: 367 - Roofs and Covers

Scenario: #1 - Flexible Roof

Scenario Description:

A flexible membrane or fabric-like roof placed on a steel truss hoop-like supports and supporting foundation. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

Associated practices include Waste Storage Facility (313), Animal Mortality Facility (316), Composting Facility (317), Roof Runoff Structure (558), and Waste Treatment (629).

Before Situation:

Applicable where the exclusion of precipitation from an animal waste storage and/or treatment facility will improve of an existing or planned system. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

After Situation:

A flexible membrane or fabric-like roof placed on a steel truss hoop-like supports and supporting foundation. Roof or cover will be engineered and installed in accordance with appropriate building codes and permits. Typical size is 1,000 square feet and is over an approved animal waste management facility as a component of a CNMP. It is designed to prevent precipitation to allow proper management of animal waste streams (manure or compost streams), thus mitigating the negative factors from the "before practice implementation".

Scenario Feature Measure: Footprint of the building

Scenario Unit: Square Foot Scenario Typical Size: 1,000

Scenario Cost: \$8,223.94 Scenario Cost/Unit: \$8.22

Cost Details (by category): **Price Component Name Component Description** Unit **Quantity Cost** (\$/unit) Materials 1667 Hoop Truss Arch Structure with fabric cover - less than 30' Roof, Hoop Truss Arch Square \$7.63 1000 \$7.630.00 Structure, less than 30' wide width, includes materials, equipment, and installation. Foot Does not include foundation preparation. Mobilization 1139 Equipment with 70-150 HP or typical weights between \$232.71 2 \$465.42 Mobilization, medium Each 14,000 and 30,000 pounds. equipment 2 Mobilization, very small 1137 Equipment that is small enough to be transported by a pick- Each \$64.26 \$128.52 up truck with typical weights less than 3,500 pounds. Can equipment be multiple pieces of equipment if all hauled simultaneously.

Practice: 367 - Roofs and Covers

Scenario: #2 - Timber or Steel Sheet Roof

Scenario Description:

A timber framed building with a timber or steel "sheet" roof and supporting foundation. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

Associated practices include Waste Storage Facility (313), Animal Mortality Facility (316), Composting Facility (317), Agrichemical Handling Facility (309), Roof Runoff Structure (558), and Waste Treatment (629).

Before Situation:

Applicable where the exclusion of precipitation from an animal waste storage and/or treatment facility will improve of an existing or planned system. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

After Situation:

A timber framed building with a timber or steel "sheet" roof and supporting foundation. Engineered and installed in accordance with appropriate building codes and permits. Typical size is 1,000 square feet and is over an approved animal waste management facility as a component of a CNMP. It is designed to prevent precipitation to allow proper management of animal waste streams (manure or compost streams), thus mitigating the negative factors from the "before practice implementation".

Scenario Feature Measure: Footprint of building

Scenario Unit: Square Foot Scenario Typical Size: 1,000

Scenario Cost: \$7,321.23 Scenario Cost/Unit: \$7.32

Cost Details (by category Component Name	/): ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials						
Roof, Post Frame Building, 30' to 60' wide	1676	Post Frame Building, no sides, - 30' to 60' width. Building sites with expected snow loads up to 30 lbs per square foot and wind exposure in semi protected areas (wooded or terrain with numerous closely spaced obstructions). Includes materials, shipping, equipment, and installation. Does not include foundation preparation.	Square Foot	\$6.96	1000	\$6,960.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$232.71	1	\$232.71
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick- up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	- Each	\$64.26	2	\$128.52