

**Practice: 484 - Mulching**

**Scenario: #1 - Natural Material - Full Coverage**

**Scenario Description:**

Application of straw mulch or other other state approved natural material to reduce erosion and facilitate the establishment of vegetative cover. Mulch provides full coverage and is typically used with critical area planting. Assumes 125 bales/acre (3 bales/1000 sq ft)

**Before Situation:**

Typical scenario ranges from a 0.1 to 1.0 acre disturbed site around a newly constructed structural practice. The potential for soil erosion is high and mulch is needed to stabilize the soil and facilitate the establishment of vegetative cover.

**After Situation:**

Straw mulch has been applied to areas needing mulch. Erosion and sedimentation is reduced, water and soil quality is protected, and vegetative cover is established.

**Scenario Feature Measure:** Area Covered by Mulch

**Scenario Unit:** Acre

**Scenario Typical Size:** 1

**Scenario Cost:** \$476.00

**Scenario Cost/Unit:** \$476.00

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$33.55	0.5	\$16.78
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$17.54	10	\$175.40
<b>Materials</b>						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$113.53	2.5	\$283.83

**Practice: 484 - Mulching**

**Scenario: #2 - Natural Material - Partial Coverage**

**Scenario Description:**

Application of straw mulch or other other state approved natural material (such as wood chips, compost, or hay) to reduce erosion, moderate soil temperature and suppress weeds. Typically used to provide partial coverage (either in-row or between rows) to suppress weeds. Payment based on total acres mulched, assuming 3-5 ft. swatch and 10-12 ft. row spacing. Area/strips mulched should receive 100% cover.

**Before Situation:**

Site conditions vary. Typically scenarios include new tree and shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Water quantity and soil moisture is a concern.

**After Situation:**

Straw or other natural mulch is applied in rows by hand or by mechanized means. Soil moisture is conserved, energy use associated with irrigation is decreased, and weed growth is suppressed.

**Scenario Feature Measure:** Total Acres Mulched

**Scenario Unit:** Acre

**Scenario Typical Size:** 2

**Scenario Cost:** \$484.53

**Scenario Cost/Unit:** \$242.26

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$21.16	5	\$105.80
<b>Labor</b>						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$18.98	5	\$94.90
<b>Materials</b>						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$113.53	2.5	\$283.83

**Practice: 484 - Mulching**

**Scenario: #3 - Erosion Control Blanket**

**Scenario Description:**

Installation of erosion control blanket on critical areas with steep slopes, grassed waterways or diversions. Blanket is typically made of coconut coir, wood fiber, straw and is typically covered on both sides with polypropylene netting. Used to help control erosion and establish vegetative cover.

**Before Situation:**

There are areas of concentrated flow and a grassed waterway is being installed. Soil erosion is a concern and there is little to no vegetation.

**After Situation:**

The erosion control blanket is placed on concentrated flow areas and secured with ground stables. Soil erosion is minimized and vegetative cover is established.

**Scenario Feature Measure:** Area Covered by Mulch

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 45,000

**Scenario Cost:** \$5,890.32

**Scenario Cost/Unit:** \$0.13

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$17.54	8	\$140.32
<b>Materials</b>						
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	\$1.15	5000	\$5,750.00

**Practice: 484 - Mulching**

**Scenario: #4 - Synthetic Material**

**Scenario Description:**

Installation of geotextile, biodegradable plastic, polyethylene plastic, or other state approved synthetic mulch to conserve soil moisture, moderate soil temperature, suppress weed growth and provide erosion control. Payment based on actual area covered by mulching material.

**Before Situation:**

Site conditions vary. Typically scenarios include new tree and shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Water quantity and soil moisture is a concern.

**After Situation:**

Synthetic mulch is applied in rows with a mulch layer or by other mechanized means. Soil moisture is conserved, energy use associated with irrigation is decreased, and weed growth is suppressed.

**Scenario Feature Measure:** Area Covered by Mulch

**Scenario Unit:** Acre

**Scenario Typical Size:** 1

**Scenario Cost:** \$9,292.80

**Scenario Cost/Unit:** \$9,292.80

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<i>Equipment/Installation</i>						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$1.92	4840	\$9,292.80

**Practice: 484 - Mulching**

**Scenario: #5 - Tree and Shrub**

**Scenario Description:**

Weed barrier fabric or other suitable natural or synthetic mulch is installed with a new tree and shrub planting. Typically used to prevent weed competition during the installation of conservation practices. Rate is per tree/shrub and assumes 1 square yard of weed barrier fabric and 5 staples/tree.

**Before Situation:**

Site conditions vary. Typical scenario is an installation of 100 native trees and shrubs to enhance wildlife habitat. Sites are often remote and trees may not be planted in rows, requiring each tree to be mulched individually

**After Situation:**

Weed barrier fabric squares are installed with 5 sod staples each, around individual trees and shrubs to control weed competition. Weeds are controlled and tree/shrub growth is minimally influenced by weed competition.

**Scenario Feature Measure:** Number of Trees Mulched

**Scenario Unit:** Each

**Scenario Typical Size:** 100

**Scenario Cost:** \$192.00

**Scenario Cost/Unit:** \$1.92

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<i>Equipment/Installation</i>						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$1.92	100	\$192.00