

STATEMENT OF WORK
Water Harvesting Catchment (636)
Arizona (May 2010)

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in practice standard have been met and are compatible with planned and applied practices
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client
 - c. Compliance with Federal, State, Tribal and local utility safety laws and NRCS policy found in the NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06, and Supplement, §AZ503.02, Subpart A. A completed and signed Utility Check Sheet, NRCS-ENG-006 form or equivalent, must be included as part of the case file.
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Capacity
 - ii. Overflow Protection
 - iii. Materials
 - i. Climatic Considerations (e.g. evaporation, freezing)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. The drawings shall meet all the graphic and content requirements as set forth in the National Engineering Manual (NEM) Part 541 "Drafting" Subpart A "Drawings" and shall include, but are not limited to:
 - a. Project location map
 - b. The "Call Before You Dig-(Call 811)" Logo or an equivalent.
 - c. System overview and layout including area and depth of pool
 - d. Size and elevation of pipe inlet and invert
 - e. Plan, profiles and section or detail views of all system components and appurtenances, as required.
2. Operation and maintenance plan
3. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03(b) (2)).
4. Design modifications during installation as required

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor
2. Verification that client has obtained required permits
3. Staking and layout according to plans and specifications including applicable layout notes
4. Installation inspection
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation
7. Certification that the installation process and materials meets design and permit requirements (NEM Subpart A, 505.03(c) (1)).

CHECK OUT

Deliverables

1. As-built documentation
 - a. Extent of practice units applied

- b. Drawings, Each sheet of the drawing shall have an "As-Built" stamp and date on them. Any changes or modification, addition or deletions to the approved drawings shall be clearly identified with red ink in the as-built drawings.
 - c. As Built drawings shall meet the requirements as set forth in the NEM Part 512 "Construction", Subpart F "As-Built Drawings" including any Arizona supplement thereof
 - d. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits
 3. Progress reporting
 4. Any additional feature, item, or appurtenance not specifically mentioned or addressed that is critical to the proper installation and operation of the practice

Additional Information:

REFERENCES

- Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Water Harvesting Catchment, 636.
- National Engineering Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook

State Contact: Design Engineer