

STATEMENT OF WORK

Waste Treatment

CODE 629

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Practice standard criteria related computations and analyses to develop drawings, plans, and specifications including but not limited to:
 - i. Objectives and outcomes of implementation
 - ii. Process diagram showing volumetric flow rates, waste load projections, unit process volumes and hydraulic retention times, projected air emissions, and projected nutrient fate
 - iii. Expected system performance
 - iv. Annual operating costs where appropriate
 - v. Quantities and fate of any byproducts
 - vi. Control system requirements
 - vii. Process monitoring requirements
2. Documentation showing the facility or process has achieved the intended purpose in similar situations and locations
3. Detailed operation and maintenance requirements including such things as loading rates, O&M manuals for specific components, start-up procedures, trouble shooting guide(s), and monitoring and reporting plans

INSTALLATION

Deliverables

1. Pre Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout of components as shown on the drawings, including layout notes.
4. Facilitate and implement required facility design modifications with client and system provider.
5. System start-up assistance and initiate process monitoring
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.

CHECK OUT

Deliverables

1. Record of application including type and size of components installed
2. Start-up data showing facility or process is working as intended
3. Certification that the facility or process meets NRCS standards
4. Test results and interpretations as required

REFERENCES

- See references listed in Conservation Practice Standard
- CO-ENG Forms: eFOTG Section IV, Tools