

STATEMENT OF WORK
Waste Separation Facility
Code (632)

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - a. List of required permits to be obtained by the client, along with other participant (client) responsibilities (Reference Form CO-ENG-13, Notification of Participant Responsibilities)
 - b. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06).
 - c. List of facilitating practices
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Objectives and outcomes of implementation.
 - ii. Geology and Soil Mechanics (NEM Subpart 531a).
 - iii. Design Capacity for the Facility including process diagram showing volumetric flow rate, waste load projection, unit process volumes, hydraulic retention times, projected air emissions, and projected nutrient fate.
 - iv. Environmental Considerations (e.g. location, water quality, air quality).
 - v. Expected system performance.
 - vi. Structural, Mechanical and Appurtenances.
 - vii. Annual operating costs where appropriate,
 - viii. Process monitoring requirements.
 - ix. Safety Considerations (NEM Part 503- Safety, Subpart A, 503.06 through 503.12).
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. All applicable State and Federal (OSHA) safety requirements shall be addressed in the plans and specifications where appropriate.
3. Design Report as appropriate (NEM Part 511, Subpart B Documentation, 511.11)
4. Construction Quality Assurance Plan, as appropriate, (NEM Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32) to include, but not limited to, the following items:
 - a. General description of work
 - b. Items of work requiring inspection or testing
 - c. Timing of inspections or tests
 - d. Skills or certifications required by inspectors
5. Operation and Maintenance Plan
6. Certifications that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03(b) (2)). For jobs completed by NRCS employees, affix the approval signature of the individual with delegated engineering job approval authority to the drawings. For jobs completed by non-NRCS employees, affix a Colorado Professional Engineer's seal to design and construction documents, when required by state laws and regulations.
7. Itemized cost estimate and list of materials.
8. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor. (Reference Form CO-ENG-13, Notification of Participant Responsibilities)
1. Verification that client has obtained required permits.
2. Staking and layout of components according to plans and specifications including applicable layout notes.
3. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used. (NEM Part 512, Subpart D Quality Assurance Activities, 512.33)
 - b. Inspection records
4. Facilitate and implement required design modifications with client and original designer or system provider.
5. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
6. Certification that the installation process and materials meet design and permit requirements. Form CO-ENG-1 may be used for this certification.

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Record of application including type and size of components installed
3. Start-up data showing facility or process is working as intended
4. Certification that the installation meets NRCS standards, specifications and all design requirements, and is in compliance with permits (NEM Subpart A, 505.03(c) (1)). Form CO-ENG-12 may be used for this certification.
5. Test results and interpretations as required.
6. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Waste Separation Facility, 632.
- NRCS Agricultural Waste Management Field Handbook (AWMFH).
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook.
- NRCS National Cultural Resources Procedures Handbook.
- See references listed in Conservation Practice Standard
- CO-ENG Forms: eFOTG Section IV, Tools