

## Scenario Worksheet

## Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	13
Scenario Name	Alaskan Steeppass
Scenario Description	<p>Alaskan Steeppass fishways are roughened chutes that employ baffles connected to the walls and floor of the chute to provide near continuous energy dissipation throughout the fishway length. A Steeppass is commonly constructed of welded aluminum at an offsite fabrication facility that is later transported to the project site and lowered in place with a boom truck or crane. Steeppasses can be composed of a single length of chute, or chutes connected by reinforced, poured-in-place resting/turn pools at complex or higher barrier sites. These fishways have excellent attraction characteristics when properly sited and provide good passage conditions using relatively low flow amounts. They often do not require auxiliary (pumped) attraction or fishway flow, but are sensitive to tailwater fluctuations. Steeppass fishways are used mainly for sites where the fishway can be closely monitored, such as off-ladder fish trap designs or temporary fishways used during construction of permanent passage facilities. Because of their baffle geometry and narrow flow paths, steeppass fishways are especially susceptible to debris accumulation.</p> <p>Steeppass fishways are designed with a sloped channel that has a constant discharge for a given normal depth, chute gradient, and baffle configuration. Energy is dissipated consistently throughout the length of the fishway via channel roughness, and results in an average velocity compatible with the swimming ability of native aquatic organisms. Target species' mobility data are important factors in determining the length of a Denil or steeppass because there are no resting locations within a given length of these fishways. Once an animal starts to ascend a length of steeppass, it must pass all the way upstream and exit the fishway, or risk injury when falling back downstream. If the steeppass fishway is long, intermediate resting pools may be included in the design, located at intervals determined by the swimming ability of the weakest target species.</p> <p>Steeppass fishways are constructed with equipment used for excavation, placing material, and delivering and removing material. Lifts or booms may be required to place concrete into forms or lift steeppass sections into place. Because ladders are often attached to existing dams, personnel familiar with the dam structure are involved at all phases of the process to ensure that plans conform with site requirements. Bed and bank excavation may be necessary to create the location for fishway components, so site isolation and sediment and erosion control measures are used. Disturbed areas are revegetated using Critical Area Planting (342) and access control and signage are provided. Scenario does not include additional measures in the adjacent active channel necessary to control flow, address channel migration of a number of native aquatic organisms, and suitable spawning and rearing habitats for targeted fish species exists in upstream river reaches. Assessment of site conditions, dam operation, and target species swimming abilities indicate that a concrete ladder will provide suitable passage conditions during the migration season and pass the expected run volume without excessive delays.</p>
Before Practice Situation	An operational, low hazard class fixed crest concrete dam becomes the target of parties interested in providing fish passage. The dam presently blocks the upstream migration of a number of native aquatic organisms, and suitable spawning and rearing habitats for targeted fish species exists in upstream river reaches. Assessment of site conditions, dam operation, and target species swimming abilities indicate that a concrete ladder will provide suitable passage conditions during the migration season and pass the expected run volume without excessive delays.
After Practice Situation	Four sections of Alaskan Steeppass separated by 2 turn/resting pools are installed. The ladder is attached to the face and abutment of the dam, and the entrance is located along the streambank where migrating native fish are likely to encounter it. The ladder passes the estimated run volume with minimal delays, and native aquatic animals are able to reach upstream spawning and rearing areas and successfully produce offspring that become part of the population. The ladder has an operating plan that stipulates actions and responsible parties for every month of the year. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Barrier Height (ft)
Scenario Unit	Vertical Feet
Scenario Typical Size	8

## Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$29,398.00	\$3,674.75
Equipment/Installation	\$43,148.48	\$5,393.56
Labor	\$20,233.80	\$2,529.23
Mobilization	\$1,574.86	\$196.86
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$94,355.14	\$11,794.39

## Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	300	\$228.00
Materials	1839	Steeppass fish ladder, 10'	10' aluminum chute installed in water passage to slow water enabling fish to pass easily. Includes all joint plates and fasteners. Materials and shipping only.	Each	\$6,500.00	4	\$26,000.00
Materials	2228	Adapter plate, steeppass, upstream	Aluminum angle adapter without flanges, upstream configuration. Includes stainless steel fasteners for joining fishway. Materials and shipping only.	Each	\$2,090.00	1	\$2,090.00
Materials	2229	Adapter plate, steeppass, downstream	Aluminum angle adapter without flanges, downstream configuration. Includes stainless steel fasteners for joining fishway. Materials and shipping only.	Each	\$1,080.00	1	\$1,080.00
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-place in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	36	\$18,105.84
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	0.5	\$144.56
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	40	\$1,828.40

Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	80	\$12,588.80
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00
Equipment/Installation	1211	Truck, Concrete Pump	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$183.32	24	\$4,399.68
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	160	\$5,456.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	120	\$9,986.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	3
Scenario Name	Blockage Removal
Scenario Description	<p>Removal of passage barriers, including small relict earthen diversions (e.g., splash dams), failing or undersized culverts, and sediment or large woody material (&gt;10cm diameter and 2m length) from mass wasting or major flood events. Instream material associated with the previously mentioned circumstances or structures prevents aquatic organism passage by the creation of channel-spanning blockages, or areas of shallow depth, high velocities, or extensive changes in water surface elevation. In addition, these features may encourage abrupt channel changes that endanger adjacent capital infrastructure or transportation corridors. Excessive streambank erosion by flows deflected around or impounded behind these features may impair water quality by introducing fine sediment out of phase with the natural hydrograph and the life history requirements of native aquatic species.</p> <p>Removal is done with an assortment of equipment, including tracked excavators outfitted with buckets with "thumbs", bull dozers, skid steers, front-end loaders, and dump trucks. The channel and adjacent floodplain are restored to pre-blockage conditions to the fullest extent practicable. Removed materials are trucked away and disposed or recycled off-site, unless native streambed material found in the blockage can be used in site reclamation. Large woody material, if present, is used for instream reclamation, replaced in the channel downstream of the blockage, or trucked offsite for disposal or stockpiling for future projects. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed in the active channel and floodplain.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels</p> <p>Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information.</p>
Before Practice Situation	An instream feature spanning the active channel creates hydraulic conditions that exceed the swimming or crawling abilities of native aquatic organisms. Event-driven mass wasting or instream deposits of coarse sediment create channel blockages or areas of shallow, fast-moving water. An instream plug of material transported to the site by flood flows or delivered to the channel from a hillslope failure not only blocks passage, but may deflect the stream toward a new course than endangers adjacent capital infrastructure or transportation corridors. Elevated risks associated with eventual over-topping or failure of the blockage to downstream features or communities are imminent in the event of a blockage that forms a temporary dam. Accelerated instream or lateral channel erosion may introduce fine sediment that impairs water quality.
After Practice Situation	The instream barrier is removed by a combination of methods and equipment and the channel and affected floodplain are restored to pre-blockage conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Cubic Yards of mineral sediment, fill or large woody material
Scenario Unit	Cubic Yard
Scenario Typical Size	200

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$152.00	\$0.76
Equipment/Installation	\$15,707.20	\$78.54
Labor	\$7,340.80	\$36.70
Mobilization	\$1,061.76	\$5.31
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$24,261.76	\$121.31

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	200	\$152.00
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	40	\$1,828.40
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	40	\$6,294.40
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	10	\$1,867.20
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Equipment/Installation	1615	Hauling, bulk, highway truck	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.28	2000	\$560.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60

Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	120	\$4,092.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

## Scenario Worksheet

## Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	8
Scenario Name	Bridge, CIP Abutment
Scenario Description	<p>A channel-spanning structure that carries a road or trailway across a river or stream. Constructed of timber, i-beams, or concrete, bridges are attached at either end to prefabricated, reinforced and poured-in-place, or piling abutments capped/surrounded with concrete. Longer span bridges may require instream pilings to support the travel surface. Bridge decking can be timber, concrete, asphalt, or some combination thereof.</p> <p>Bridge design is completed to conform to loading requirements and site conditions. Geotechnical investigations are used to determine the best support structure suited to a given site. The bridge deck is designed to rest on abutments placed on the adjacent floodplain.</p> <p>Bridge components are delivered to the site and assembled by a combination of equipment and manual labor. They are installed with an assortment of equipment used for excavation, placing material, delivering and removing material, and lifting bridge components from delivery trucks onto the constructed bridge support elements. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert (if applicable), and topsoil conservation for site reclamation. Stream diversion is not necessary since the bridge will be constructed above the active channel. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the bridge crossing.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels</p> <p>Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information.</p>
Before Practice Situation	An existing stream crossing outfitted with an undersized culvert has a history of maintenance issues and failure. The downstream channel has experienced bed and bank scour, and the crossing may have to the deposition of a wedge of sediment upstream of the road. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.
After Practice Situation	The undersized culvert is replaced with a timber bridge placed on precast concrete abutments. The bridge deck is composed of timber planks, and elevated, continuous railings run down each side connecting one abutment to its counterpart on the opposite bank. Signs on either approach indicate bridge capacity and weight restrictions. Because the bridge spans the active channel and sits atop the adjacent floodplain surface, geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Linear feet of bridge deck
Scenario Unit	Linear Feet
Scenario Typical Size	30

## Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$10,868.20	\$362.27
Equipment/Installation	\$33,987.84	\$1,132.93
Labor	\$19,551.80	\$651.73
Mobilization	\$1,574.86	\$52.50
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$65,982.70	\$2,199.42

## Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	1044	Dimension Lumber, Treated	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.74	2500	\$1,850.00
Materials	1200	Rock Riprap, graded, angular, material and shipping	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$30.05	100	\$3,005.00
Materials	1599	Epoxy anchor	Galvanized bolts anchored into concrete or stone using epoxy adhesive. Includes materials and labor to drill and install.	Each	\$18.58	12	\$222.96
Materials	1779	Steel, structural steel members	Structural steel, includes materials and fabrication.	Pound	\$0.88	5360	\$4,716.80
Materials	2140	Pipe, PE, 4", DR 9, perforated	Materials: -4" - Perforated PE- 160 psi - ASTM D3035 DR 9	Foot	\$10.62	60	\$637.20
Materials	2166	Galvanized Bolts, large	5/8" x 12" galvanized timber bolts. Materials only.	Each	\$5.51	24	\$132.24
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-place in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	32	\$16,094.08
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	40	\$1,828.40

Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	60	\$9,441.60
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	1211	Truck, Concrete Pump	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$183.32	8	\$1,466.56
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	140	\$4,774.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	120	\$9,986.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

## Scenario Worksheet

## Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	9
Scenario Name	Bridge, Precast Abutment
Scenario Description	<p>A channel-spanning structure that carries a road or trailway across a river or stream. Constructed of timber, i-beams, or concrete, bridges are attached at either end to prefabricated or precast concrete. Longer span bridges may require instream pilings to support the travel surface. Bridge decking can be timber, concrete, asphalt, or some combination thereof.</p> <p>Bridge design is completed to conform to loading requirements and site conditions. Geotechnical investigations are used to determine the best support structure suited to a given site. The bridge deck is designed to rest on abutments placed on the adjacent floodplain.</p> <p>Bridge components are delivered to the site and assembled by a combination of equipment and manual labor. They are installed with an assortment of equipment used for excavation, placing material, delivering and removing material, and lifting bridge components from delivery trucks onto the constructed bridge support elements. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert (if applicable), and topsoil conservation for site reclamation. Stream diversion is not necessary since the bridge will be constructed above the active channel. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the bridge crossing.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water conveyance channels</p> <p>Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information.</p>
Before Practice Situation	An existing stream crossing outfitted with an undersized culvert has a history of maintenance issues and failure. The downstream channel has experienced bed and bank scour, and the crossing may have to the deposition of a wedge of sediment upstream of the road. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.
After Practice Situation	The undersized culvert is replaced with a timber bridge placed on precast concrete abutments. The bridge deck is composed of timber planks, and elevated, continuous railings run down each side connecting one abutment to its counterpart on the opposite bank. Signs on either approach indicate bridge capacity and weight restrictions. Because the bridge spans the active channel and sits atop the adjacent floodplain surface, geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Linear feet of bridge deck
Scenario Unit	Linear Feet
Scenario Typical Size	30

## Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$17,024.60	\$567.49
Equipment/Installation	\$16,427.20	\$547.57
Labor	\$19,551.80	\$651.73
Mobilization	\$1,574.86	\$52.50
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$54,578.46	\$1,819.28

## Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	1044	Dimension Lumber, Treated	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.74	2500	\$1,850.00
Materials	1200	Rock Riprap, graded, angular, material and shipping	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$30.05	100	\$3,005.00
Materials	1599	Epoxy anchor	Galvanized bolts anchored into concrete or stone using epoxy adhesive. Includes materials and labor to drill and install.	Each	\$18.58	12	\$222.96
Materials	1779	Steel, structural steel members	Structural steel, includes materials and fabrication.	Pound	\$0.88	5360	\$4,716.80
Materials	1836	Footing, concrete, precast	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Materials only.	Foot	\$153.91	40	\$6,156.40
Materials	2140	Pipe, PE, 4", DR 9, perforated	Materials: -4" - Perforated PE- 160 psi - ASTM D3035 DR 9	Foot	\$10.62	60	\$637.20
Materials	2166	Galvanized Bolts, large	5/8" x 12" galvanized timber bolts. Materials only.	Each	\$5.51	24	\$132.24
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	40	\$1,828.40

Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	60	\$9,441.60
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	140	\$4,774.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	120	\$9,986.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	10
Scenario Name	Bridge, Prefabricated
Scenario Description	<p>a river or stream. Bridge design is completed to conform to loading requirements and site conditions. The bridge deck is designed to rest on abutments placed on the adjacent floodplain.</p> <p>Bridge components are delivered to the site and assembled by a combination of equipment and manual labor. They are installed with an assortment of equipment used for excavation, placing material, delivering and removing material, and lifting bridge components from delivery trucks onto the constructed bridge support elements. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert (if applicable), and topsoil conservation for site reclamation. Channel diversion or dewatering is required since an existing blockage will be removed for bridge construction. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed to address channel incision, bank stability, and other factors associated with the presence of the bridge crossing.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; SOIL EROSION– Excessive bank erosion from streams shorelines or water</p>
Before Practice Situation	An existing undersized culvert creates an upstream passage blockage to fish and other aquatic organisms. The existing crossing does not meet State or Federal fish passage guidance.
After Practice Situation	The undersized culvert is replaced with a manufactured bridge placed on precast concrete abutments. The bridge deck is composed of concrete or steel and elevated, continuous railings run down each side connecting one abutment to its counterpart on the opposite bank. Signs on either approach indicate bridge capacity and weight restrictions. Because the bridge spans the active channel and sits atop the adjacent floodplain surface, geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. Resource Concerns are addressed within the context of the site. Typical Scenario is for a 30' span bridge 15' wide on precast concrete abutments.
Scenario Feature Measure	Linear Feet of Bridge Deck
Scenario Unit	Foot
Scenario Typical Size	30

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$87,749.80	\$2,924.99
Equipment/Installation	\$24,300.52	\$810.02
Labor	\$13,106.16	\$436.87
Mobilization	\$787.43	\$26.25
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$125,943.91	\$4,198.13

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	2165	Painting, steel surface, Impermeable	Painting of steel surface with an impermeable coating. Includes materials and application	Square Foot	\$0.83	1260	\$1,045.80
Materials	2193	Bridge, steel or concrete, pre-Manufactured Bridge	A premanufactured steel or precast prestressed concrete bridge rated for an HS 25 highway loading. Typical width is 14', length is variable. Includes railing system. Includes materials and shipping only.	Square Foot	\$192.00	450	\$86,400.00
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	18	\$9,052.92
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	40	\$1,828.40
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	20	\$3,147.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	50	\$9,336.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	10	\$936.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	34	\$1,344.36

Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	80	\$2,728.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	20	\$833.60
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	80	\$6,657.60
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	5
Scenario Name	CMP Culvert
Scenario Description	<p>A corrugated metal (galvanized steel or aluminum) pipe culvert (CMP) of any shape (round, elliptical, or squash) used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. CMPs used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, CMPs used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert size—diameter or span—is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert diameter or span is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability.</p> <p>Once the CMP diameter or span is determined, culvert length will be determined by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wingwalls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Culvert wall thickness and corrugations are determined by road loading requirements. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined.</p> <p>CMPs are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. The culvert is placed within the roadway on a subexcavated compacted bed, set at a slope that matches the design longitudinal profile, and backfilled with a bed mixture that mimics adjacent stream characteristics with special attention to channel pattern. Backfill depths are typically at least 20% of the culvert diameter or rise, but may deviate based on the shape of the culvert used, channel dimensions, substrate size, and the site longitudinal profile. Special equipment such as motorized wheelbarrows may be necessary to backfill smaller CMPs. Once the simulated streambed in the culvert barrel is complete, the roadway is replaced and any necessary armoring and revegetating material is placed at the culvert inlet and outlet.</p> <p>An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.</p> <p>The undersized culvert is replaced with a CMP sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.</p>
Before Practice Situation	
After Practice Situation	
Scenario Feature Measure	CMP
Scenario Unit	Linear Foot
Scenario Typical Size	40 8-foot by 40-foot 14 ga. CMP and 75 cubic yards fill

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$6,065.60	\$151.64
Equipment/Installation	\$16,363.60	\$409.09
Labor	\$7,005.20	\$175.13
Mobilization	\$787.43	\$19.69
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$30,221.83	\$755.55

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	300	\$228.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	75	\$2,466.00
Materials	1835	Pipe, CMP, 96", 14 Gauge	96" Corrugated Metal Pipe, Galvanized, Uncoated, 14 gage. Material cost only.	Foot	\$84.29	40	\$3,371.60
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	100	\$244.00
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	40	\$6,294.40
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60

Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	40	\$1,028.40
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	80	\$2,728.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	12
Scenario Name	Complex Denil
Scenario Description	<p>Denil fishways are roughened chutes that employ baffles connected to the walls and floor of the chute to provide near continuous energy dissipation throughout the fishway length. Denils are often reinforced, poured-in-place concrete structures outfitted with removable baffles constructed with treated wood that fits into channels incorporated into the ladder walls. These fishways have excellent attraction characteristics when properly sited and provide good passage conditions using relatively low flow amounts. They often do not require auxiliary (pumped) attraction or fishway flow, but are sensitive to tailwater fluctuations. Denil fishways are used mainly for sites where the fishway can be closely monitored, such as off-ladder fish trap designs or temporary fishways used during construction of permanent passage facilities. Because of their baffle geometry and narrow flow paths, Denil fishways are especially susceptible to debris accumulation.</p> <p>Denil fishways are designed with a sloped channel that has a constant discharge for a given normal depth, chute gradient, and baffle configuration. Energy is dissipated consistently throughout the length of the fishway via channel roughness, and results in an average velocity compatible with the swimming ability of native aquatic organisms. Target species' mobility data are important factors in determining the length of a Denil or steep pass because there are no resting locations within a given length of these fishways. Once an animal starts to ascend a length of Denil, it must pass all the way upstream and exit the fishway, or risk injury when falling back downstream. If the Denil or steep pass fishway is long, intermediate resting pools may be included in the design, located at intervals determined by the swimming ability of the weakest target species.</p> <p>Denil ladders are constructed with equipment used for excavation, placing material, and delivering and removing material. Lifts or booms may be required to place concrete into forms or lift ladder elements into place. Because ladders are often attached to existing dams, personnel familiar with the dam structure are involved at all phases of the process to ensure that plans conform with site requirements. Bed and bank excavation may be necessary to create the location for fishway components, so site isolation and sediment and erosion control measures are used. Disturbed areas are revegetated using Critical Area Planting (342) and access control and signage are provided. Scenario does not include additional measures in the adjacent active channel necessary to control flow, address channel elevation or stability, or encourage fish guidance into the concrete ladder. Scenario does not include structures used as counting stations or to trap and sample upstream migrants.</p>
Before Practice Situation	An operational, low hazard class fixed crest concrete dam becomes the target of parties interested in providing fish passage. The dam presently blocks the upstream migration of a number of native aquatic organisms, and suitable spawning and rearing habitats for targeted fish species exists in upstream river reaches. Assessment of site conditions, dam operation, and target species swimming abilities indicate that a concrete ladder will provide suitable passage conditions during the migration season and pass the expected run volume without excessive delays.
After Practice Situation	A concrete Denil ladder outfitted with treated wood baffles and a turn/resting pool is installed. The ladder is attached to the face and abutment of the dam, and the entrance is located along the streambank where migrating native fish are likely to encounter it. The ladder passes the estimated run volume with minimal delays, and native aquatic animals are able to reach upstream spawning and rearing areas and successfully produce offspring that become part of the population. The ladder has an operating plan that stipulates actions and responsible parties for every month of the year. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Barrier Height (ft)
Scenario Unit	Vertical Feet
Scenario Typical Size	12

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$540,452.00	\$45,037.67
Equipment/Installation	\$19,261.11	\$1,605.09
Labor	\$34,151.00	\$2,845.92
Mobilization	\$1,061.76	\$88.48
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$594,925.87	\$49,577.16

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	1044	Dimension Lumber, Treated	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.74	200	\$148.00
Materials	1838	Denil Ladder	Denil Ladder, designed to meet species passage requirements and site characteristics. Cost is per vertical foot of dam at site, and includes concrete, gates, trash racks, baffles, turn/resting pools, and ladder entrance or exit works.	Foot	\$45,000.00	12	\$540,000.00
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	1	\$289.11
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	60	\$2,742.60
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	60	\$9,441.60
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	60	\$2,119.80
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00

Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	80	\$3,163.20
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	180	\$6,138.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	80	\$3,334.40
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	240	\$19,972.80
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	7
Scenario Name	Concrete Box Culvert
Scenario Description	<p>A four-sided precast concrete box (square or rectangular) culvert used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. Concrete box culverts are generally available in sections of 1-foot increments. Concrete box culverts used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, concrete box culverts used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert width is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert width is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability.</p> <p>Once the culvert width is determined, culvert length will be determined by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wingwalls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined.</p> <p>Concrete box culverts are delivered in sections and assembled onsite, and require adequate bed compaction throughout the crossing section. They are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. The new streambed is set at a slope that matches the design longitudinal profile, and backfilled with a bed mixture that mimics adjacent stream characteristics with special attention to channel pattern. The roadway is replaced and any necessary armoring and revegetating material is placed at the culvert inlet and outlet where it intersects the road fill prism. Other actions include construction staking</p>
Before Practice Situation	An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.
After Practice Situation	The undersized culvert is replaced with a concrete box culvert sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Length of Concrete box culvert
Scenario Unit	Linear Foot
Scenario Typical Size	20 6'X8'X20' concrete box

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$14,631.75	\$731.59
Equipment/Installation	\$19,510.80	\$975.54
Labor	\$8,201.40	\$410.07
Mobilization	\$1,300.53	\$65.03
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$43,644.48	\$2,182.22

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	100	\$76.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	45	\$1,479.60
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	45	\$415.35
Materials	2175	Culvert, box, 6' x 8'	Precast concrete box culvert, 6'X8'. Typically in 4' sections. Materials only.	Foot	\$633.04	20	\$12,660.80
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	100	\$244.00
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	60	\$9,441.60
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00

Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	100	\$3,410.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	1
Scenario Name	Concrete Dam Removal
Scenario Description	<p>Full or partial removal of a concrete dam to restore aquatic organism passage, improve water quality, and promote functional river ecology and geomorphology. The extent of removal (full or partial) is determined through consultations with the dam owner in consideration of prevailing regulations and site historical status. Adjacent floodplain surfaces above and below the target dam are considered in the planning process to account for shifts in streamflow and geomorphic regime. Resulting channel dimensions and profile are determined on a site-specific basis to reflect--to the fullest extent possible--pre-dam conditions.</p> <p>Pre-removal sediment assays are completed to determine the toxicity of sediment stored behind the dam. Planning for the reclamation and management of stored sediments is completed according to geomorphic conditions, prevailing regulations, and the results of sediment toxicity investigations. Removal is done with an assortment of equipment, including tracked excavators outfitted with hydraulic chisels, hammers and/or buckets with "thumbs", bull dozers, skid steers, cranes, front-end loaders, and dump trucks. Alternative demolition techniques may include the use of high explosives, diamond-chain, or similar circular saws to remove the dam in a piecemeal manner. Removed materials are trucked away and disposed or recycled off-site. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed in the active channel and floodplain to account for post-removal changes to stream plan, pattern, or profile, or reclamation of any former impounded areas. Additional structural measures may be necessary to address constructed features associated with the removed dam including canals, raceways, adjacent spillways, navigation locks, access and maintenance roads, or similar civil works.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE --Habitat degradation; EXCESS WATER -- Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION -- Elevated water temperature.</p> <p>Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information.</p>
Before Practice Situation	A channel-spanning concrete dam no longer has functional use, may be failing, or creates a hazard to downstream capital infrastructure or communities. The dam blocks upstream aquatic organism migration, and downstream migrants may be diverted into hydraulic structures that increase mortality or result in migration delays or dead-ends. The dam disrupts the downstream cycling and transport of sediment, woody material and nutrients. The pool created by the dam may impair water quality by increasing temperatures, capturing fine sediment--sometimes laden with heavy metals or other pollutants--later mobilized by high flow events, and creating slackwater habitat for invasive aquatic vegetation. Non-native or exotic fish species inhabit the pool and predate upon and/or displace native fish.
After Practice Situation	The existing dam is removed and reach geometry and slope are restored to pre-dam conditions to the fullest extent practicable. Aquatic organism passage and river ecology and geomorphic conditions are restored to pre-dam conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Cubic Yards of concrete in dam and abutments (if present)
Scenario Unit	Cubic Yard
Scenario Typical Size	250 assume 8' high by 4' wide by 200' crest length plus abutments

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$13,902.50	\$55.61
Equipment/Installation	\$86,205.67	\$344.82
Labor	\$30,142.40	\$120.57
Mobilization	\$1,300.53	\$5.20
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$131,551.10	\$526.20

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	500	\$380.00
Materials	1200	Rock Riprap, graded, angular, material and shipping	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$30.05	450	\$13,522.50
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	1.5	\$433.67
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	320	\$50,355.20
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	160	\$5,652.80
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	50	\$9,336.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	200	\$18,720.00
Equipment/Installation	1615	Hauling, bulk, highway truck	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.28	6100	\$1,708.00

Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	160	\$6,326.40
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	160	\$4,113.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	480	\$16,368.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	80	\$3,334.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	11
Scenario Name	Concrete Ladder
Scenario Description	<p>Formed, reinforced, poured-in-place concrete structures outfitted with baffles (Denil), vertical slots, pools and weirs, submerged orifices, chutes or some combination thereof to provide upstream passage for aquatic organisms over dams and other hydraulic structures. Although fish ladder designs vary according to target species and site conditions, they can generally be described as a three-sided concrete channel with integrated hydraulic features that provide a gradual elevation increase across some distance that allows aquatic organism to swim over a barrier—they convert the total barrier head elevation into passable increments. Concrete ladders are often constructed with resting pools and may have switchbacks. The primary water source for a concrete ladder comes from streamflow diverted into the ladder exit (upstream end) and since it is passed through the ladder to the river below, it is not a consumptive use. These ladders often require flow control and regulating devices (sometimes automated), gates, and may need auxiliary pumps to provide attraction flows at the ladder entrance (downstream end) or augment flow in the ladder. Gages above and below the dam are required to inform ladder operation. Trash racks are used at the upstream end to block debris from entering the ladder. Concrete ladders also require frequent maintenance, and flow through unautomated ladders may need to be adjusted manually when adjacent river conditions or dam operations change.</p> <p>Concrete ladder designs can be complex and require interactions between engineering and ecological sciences for successful implementation. For example, the ladder entrance is one of the most important elements of the structure, and placement of this entrance in the downstream reach is a function of site characteristics and aquatic organism biology. In addition, some aquatic animals will not swim through a submerged orifice, so use of pool-orifice ladders is not recommended. Partners associated with dam ownership and operation, regulatory agencies, and others are consulted and included in the design and construction process. Ladder designs account for run volume and timing, and the swimming capabilities of target species. Some ladders in highly visible areas are finished with masonry facades to blend the ladder to the site in the interest of aesthetics or to conform with historic appearances.</p> <p>Concrete ladders are constructed with equipment for excavation, placing material, and delivering and removing material. Lifts or booms are required to place concrete into forms. Because ladders are often attached to existing dams, personnel familiar with the dam structure are involved at all phases of the process to ensure that plans conform with site requirements. Bed and bank excavation are necessary to create the location for concrete ladders, so site isolation and sediment</p>
Before Practice Situation	An operational, low hazard class fixed crest concrete dam becomes the target of parties interested in providing fish passage. The dam presently blocks the upstream migration of a number of native aquatic organisms, and suitable spawning and rearing habitats for targeted fish species exists in upstream river reaches. Assessment of site conditions, dam operation, and target species swimming abilities indicate that a concrete ladder will provide suitable passage conditions during the migration season and pass the expected run volume without excessive delays.
After Practice Situation	A concrete pool and chute ladder outfitted with aluminum internal features and 2 turn/resting pool is installed. The ladder is attached to the face and abutment of the dam, and the entrance is located along the streambank where migrating aquatic organisms are likely to encounter it. The ladder passes the estimated run volume with minimal delays, and native aquatic animals are able to reach upstream spawning and rearing areas and successfully produce offspring that become part of the population. The ladder has an operating plan that stipulates actions and responsible parties for every month of the year. The ladder is fenced to control access and signage indicating its function and relevant warnings is provided at numerous locations. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Barrier height (feet)
Scenario Unit	Vertical Feet
Scenario Typical Size	20

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$152.00	\$7.60
Equipment/Installation	\$287,021.65	\$14,351.08
Labor	\$29,076.60	\$1,453.83
Mobilization	\$1,574.86	\$78.74
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$317,825.11	\$15,891.26

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	200	\$152.00
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-place in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	500	\$251,470.00
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	3	\$867.33
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	60	\$2,742.60
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	80	\$12,588.80
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	80	\$2,826.40
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	6	\$1,120.32

Equipment/Installation	1211	Truck, Concrete Pump	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$183.32	60	\$10,999.20
Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	60	\$4,407.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	80	\$3,163.20
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	80	\$2,728.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	80	\$3,334.40
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	220	\$18,308.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	2
Scenario Name	Earthen Dam Removal
Scenario Description	<p>Full removal of an earthen dam to restore aquatic organism passage, improve water quality, and promote functional river ecology and geomorphology. The removal extent is determined through consultations with the dam owner in consideration of prevailing regulations and site historical status. Adjacent floodplain surfaces above and below the target dam are considered in the planning process to account for shifts in streamflow and geomorphic regime. Resulting channel dimensions and profile are determined on a site-specific basis to reflect, to the fullest extent possible, pre-dam conditions.</p> <p>Pre-removal sediment assays are completed as necessary to determine the toxicity of sediment stored behind the dam. Planning for the reclamation and management of stored sediments is completed according to geomorphic conditions, prevailing regulations, and the results of sediment toxicity investigations. Removal is done with an assortment of equipment, including tracked excavators outfitted with hydraulic chisels, hammers and/or buckets with "thumbs", bull dozers, skid steers, cranes, front-end loaders, and dump trucks. Removed materials are trucked away and disposed or recycled off-site, unless native streambed material found in the embankment can be used in site reclamation. Disturbed areas are revegetated using Critical Area Planting (342). Scenario does not include additional measures needed in the active channel and floodplain to account for post-removal changes to stream plan, pattern, or profile, or reclamation of any former impounded areas. Additional structural measures may be necessary to address constructed features associated with the removed dam including head gates, canals, raceways, access and maintenance roads, or similar civil works.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature.</p> <p>Payments for these associated practices are made separately and are covered by other typical scenarios and payment schedules. See relevant CPS for additional information.</p>
Before Practice Situation	A channel-spanning earthen dam no longer has functional use, may be failing, or creates a hazard to downstream capital infrastructure or communities. The dam blocks upstream aquatic organism migration, and downstream migrants may be diverted into hydraulic structures that increase mortality or result in migration delays or dead-ends. The dam disrupts the downstream cycling and transport of sediment, woody material and nutrients. The pool created by the dam may impair water quality by increasing temperatures, capturing fine sediment—sometimes laden with heavy metals or other pollutants—later mobilized by high flow events, and creating slackwater habitat for invasive aquatic vegetation. Non-native or exotic fish species inhabit the pool and predate upon and/or displace native fish.
After Practice Situation	The existing dam is removed and reach geometry and slope are restored to pre-dam conditions to the fullest extent practicable. Aquatic organism passage and river ecology and geomorphic conditions are restored to pre-dam conditions to the fullest extent practicable. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Cubic Yards of earthen embankment
Scenario Unit	Cubic Yard
Scenario Typical Size	500 trapezoidal fill 8' top, 6' high, 16' base, 150 feet long

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$13,826.50	\$27.65
Equipment/Installation	\$43,475.93	\$86.95
Labor	\$15,156.80	\$30.31
Mobilization	\$1,574.86	\$3.15
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$74,034.09	\$148.07

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	1200	Rock Riprap, graded, angular, material and shipping	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$30.05	450	\$13,522.50
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	3	\$867.33
Equipment/Installation	927	Dozer, 140 HP	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$102.69	40	\$4,107.60
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	100	\$15,736.00
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	100	\$3,533.00
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	50	\$9,336.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	80	\$7,488.00
Equipment/Installation	1615	Hauling, bulk, highway truck	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.28	8600	\$2,408.00

Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	80	\$2,056.80
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	240	\$8,184.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	80	\$3,334.40
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	14
Scenario Name	Low Water Crossing
Scenario Description	<p>Structure installed on low volume or on unimproved roads at watercourse crossings. Primary use is to allow livestock and equipment access to other parcels of land or operational units. Low-water crossings provide safe and stable stream crossings that don't negatively impact water and ecological quality while remaining stable across a wide range of flows. Variations exist, but a common application consists of an improved or hardened ford located above a hydraulic control (e.g., bedrock outcropping, riffle, or step composed of coarse substrates). Properly designed and installed low water crossings provide aquatic organism passage (AOP), promote stream ecological and geomorphic function, remain stable over time, and can pass sediment and woody debris.</p> <p>Conservation planning and interaction with the landowner is vital to determine if existing crossings can be consolidated into fewer, more reliable locations. Characterizing a site according to its watershed position and geomorphic function will aid design decisions. Optimal AOP conditions are usually realized when the backfill is composed of a mixture that mimics bed material as evaluated from a reference reach adjacent to the crossing—preferably at least 10-20 estimated bankfull channel widths above an existing crossing to avoid effects that alter channel geometry or bedform composition and spacing.</p> <p>Low water crossings are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Low water crossings provide the best mix of function and longevity when they are designed and built to conform to existing channel geometry and slope, constructed to match the shape of the existing channel, and oriented to cross the stream at a 90 degree angle. Crossing width, measured along the downstream axis, should not exceed 2X bankfull width. Low water crossings are commonly constructed by overexcavating the crossing section 6-12 inches below the existing streambed and backfilling the void with well-graded rock back to natural bed elevation. Geotextile lining may be required in some settings. Rock size and gradation is the smallest mix needed to remain stable under prevailing flow conditions—larger rock can endanger livestock and turbulence impairs passage. Sand or soil may be added into the mix to seal the section to ensure that the stream doesn't percolate into the crossing substrate. Smaller material increases bed diversity, chokes voids between bigger stones, and helps preserve passage quality. Smaller rock smaller (&lt; 2 inches) at the finished surface may become lodged in livestock hooves. The road/trail surface of the crossing should be extended to an elevation that exceeds the known high water level on each side of the crossing. The downstream edge of the crossing should not produce a sharp drop in water surface to preserve AOP quality and discourage sediment deposition and debris accumulation. Other actions include construction staking and signage, soil erosion and pollution control, removal and disposal of the old culvert, and topsoil conservation for site reclamation. Disturbed areas are</p>
Before Practice Situation	<p>A small farming operation has a mixture of pastures, hay meadows, and crops that all require seasonal movement of equipment and livestock between parcels. Four unimproved stream crossings provide unreliable access across the property and require yearly maintenance to clear debris and sediment. Farm equipment has gotten stuck in the past, and uncontrolled livestock access and frequent crossing or loafing in the stream contributes to chronic water quality problems associated with elevated fine sediment, high water temperatures, invasive aquatic vegetation, and fecal coliform bacteria. Livestock avoid three of the crossings when streamflow increases moderately. Two of the crossings are overwide and shallow, and impair AOP. The property and landowner's yearly operations are reviewed by conservation planners and—with the input and agreement of the landowner—it is decided that three of the four crossings can be eliminated and consolidated at one site above a cobble/boulder deposit in the stream.</p>
After Practice Situation	<p>An improved ford is constructed by excavating the channel just upstream of the boulder/cobble hydraulic control. The cut is lined with geotextile to control seepage and subsurface flow, and backfilled up to the existing bed elevation with a well-graded mix of rock sized to mimic the material in the channel upstream of the crossing. The finished crossing surface is at grade with the up and downstream channel elevation, and no drop exists along the downstream edge. Approaches on either side of the crossing are extended up to the adjacent floodplain surface, and the finished instream portion of the ford matches the existing channel cross section. Approach slopes are shallow enough for expected equipment traffic, including towed combinations, and armored as needed with larger rock to protect against erosion that may occur when the floodplain is inundated. The crossing is fenced and gated to control livestock access and provide greater flexibility to the landowner's grazing needs. AOP is provided, and the crossing remains stable across a range of flow and sediment and debris transport events. Resource Concerns are addressed within the context of the site.</p>
Scenario Feature Measure	Cubic Yard of Crossing Material
Scenario Unit	Cubic Yard
Scenario Typical Size	42 Assume 15' wide, 50' long, 1.5' deep cut

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$1,654.24	\$39.39
Equipment/Installation	\$5,060.76	\$120.49
Labor	\$2,802.08	\$66.72
Mobilization	\$787.43	\$18.75
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$10,304.51	\$245.35

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	100	\$76.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	48	\$1,578.24
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	0.5	\$144.56
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	85	\$207.40
Equipment/Installation	50	Earthfill, Manually Compacted	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.34	24	\$128.16
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	16	\$2,517.76
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	16	\$565.28
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	16	\$1,497.60

Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	16	\$632.64
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	16	\$411.36
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	32	\$1,091.20
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	16	\$666.88
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	4
Scenario Name	Nature-Like Fishway
Scenario Description	<p>Nature-like fishways, also known as roughened channels, rock ramps, or bypass channels, are constructed features that provide passage around an instream barrier or in place of a removed barrier. Fishway design is based on simulating or mimicking adjacent stream characteristics, using natural materials, and providing suitable passage conditions over a range of flows for a wide variety of fish species and other aquatic organisms. Nature-like fishways provide enhanced passage conditions compared to concrete or aluminum (Alaskan Steeppass) ladders, and are not as susceptible to debris-related operational issues. When used to bypass an instream barrier, they require a larger footprint than instream structures, and may also require control structures to regulate flow through the fishway or address tailwater fluctuations affecting the fishway entrance (downstream end).</p> <p>Fishway design includes an assessment of adjacent stream characteristics, including channel geometry, slope, sediment texture and composition, and major geomorphic units that govern channel plan, pattern and profile. In the case of a fishway that bypasses an instream barrier, the design is tailored to these elements, the elevation required to ascend the barrier, and the known range of flow variation or operations. For fishways constructed in the place of a removed barrier, the design may be a hybrid approach that meets the same criteria, although in a smaller instream footprint.</p> <p>Nature-like fishways are constructed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Large woody material is used to create channel structural elements in some settings, when available and where approved by oversight agencies. Removed materials are trucked away and disposed or recycled off-site, unless excavated native streambed material can be used in fishway construction. Large woody material or removed trees, if present, are used for fishway construction trucked offsite for disposal, or trucked offsite for stockpiling for future projects. Disturbed areas are revegetated using Critical Area Planting (342) and access control and signage are provided. Scenario does not include additional measures needed in the active channel and floodplain or at an existing dam necessary to control flow associated with nature-like fishway.</p>
Before Practice Situation	An instream barrier prevents upstream migration of native aquatic organisms and no support exists for removal. Similarly, an instream barrier is removed, and interested parties require maintenance of an upstream pool or pond. The subject stream contains a number of migrating aquatic organisms ranging in size from small to large with a range of propulsion abilities--weak to strong swimmers and animals that crawl along the bottom. In either case--barrier removal or bypassing an existing barrier--local sentiment to preserve existing or natural conditions and the desire to provide passage for a range of aquatic organisms indicate the use of a nature-like fishway. Adequate space for a bypass channel is available, and adjacent landowners approve.
After Practice Situation	A nature-like fishway is constructed in place of a removed barrier or around an existing barrier. The fishway is designed to mimic the adjacent natural stream, and is constructed of rock and/or large woody material that provides quality passage conditions for a number of species and geomorphic stability over a range of flows. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Length of Fishway
Scenario Unit	Linear Foot
Scenario Typical Size	2000 (assume 20ft wide by 2000 feet long)

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$105,071.00	\$52.54
Equipment/Installation	\$93,092.53	\$46.55
Labor	\$75,176.00	\$37.59
Mobilization	\$1,061.76	\$0.53
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$274,401.29	\$137.20

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	2000	\$1,520.00
Materials	1761	Boulder	Rock boulders. Includes materials and local delivery (less than 50 miles) only.	Ton	\$29.07	1300	\$37,791.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	2000	\$65,760.00
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	3	\$867.33
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	12000	\$29,280.00
Equipment/Installation	926	Backhoe, 80 HP	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.71	160	\$7,313.60
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	160	\$25,177.60
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	200	\$7,066.00
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	200	\$18,720.00

Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	160	\$6,326.40
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	240	\$6,170.40
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	520	\$17,732.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	120	\$5,001.60
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	480	\$39,945.60
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	2	\$548.66
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	16
Scenario Name	Paddlewheel Screen
Scenario Description	<p>A fish screen used at surface (gravity) diversions intended to prevent juvenile or small-bodied adult fish from entering ditches, canals, laterals or other pathways that lead to migration dead-ends or sources of mortality. Paddlewheel screens are active by design, meaning that they are outfitted with mechanisms that automatically cycle to keep the screen free of debris that will restrict the screen area, impede flow through the screen, and may cause the screen to fail. These screens are powered by a paddlewheel driven by flowing water and are thus suitable for remote locations without electrical services. Paddlewheel screens can be installed in the active channel along a streambank, but are most commonly built in a canal below a diversion structure. Aquatic organisms that encounter a screen installed in a canal are diverted back into the adjacent stream through a buried pipe.</p> <p>Screens installed in the active channel are built at the point of diversion with the screen face aligned parallel to the flow of the river. Bankline modifications can be necessary to achieve proper alignment. Screens installed in a canal can be aligned differently and are best sited at a canal location that minimizes the straight-line bypass/return path distance. Again, canal installation is the most common.</p> <p>A fully functional screen is designed to meet criteria intended to protect target organisms from being swept into and pinned against or along the screen face (impingement). When this occurs, animals can be physically harmed or, in the case of a rotating drum screen, introduced into the diversion works behind the screen. Active screens are designed to ensure that the approach velocity will not exceed .4 feet per second (fps). Approach velocity is calculated by dividing the maximum screened flow volume by the vertical projection of the effective screen area at maximum submergence. For a rotating drum screen the design submergence should not be more than 85% or less than 65% of the screen diameter. Screen design should strive to provide nearly uniform flow distribution across the screen surface. Screens longer than 6 feet must be angled to the direction of incoming flow and have sweeping velocities (along the face of the screen) greater than the approach velocity, and sweeping velocities should not decrease along the face of the screen. Screen face openings must not exceed 3/32 inch in diameter, and perforated plate must be smooth to the touch with openings punched through in the direction of approaching flow. Material used for the screen face should be corrosion resistant and sufficiently durable to maintain a smooth uniform surface with long term use. Bypass design flow should be about 5% of the diverted amount, include an easily accessible entrance, and flow velocity in the bypass pipe or channel should not exceed 0.2fps. Minimum design depth in a bypass pipe should be at least 40% of the pipe diameter. Bypass entrances should be installed with independent flow control capability. The face of all screen surfaces must be placed flush (to the extent</p>
Before Practice Situation	An unscreened gravity diversion removes water and fish from a small stream. The ditch under the 5 cfs diversion serves a number of pumps and turnouts used to irrigate alfalfa and flood irrigate hay. The diversion is run from late winter into fall, although the flood irrigated crops are shut off in mid-summer to allow growth and prepare the fields for mowing and haying. Although the diversion is owned by a nth-generation landowner with proven, long-standing rights to the diverted water, recent fish listings under the Endangered Species Act present liability risks in the face of a third party lawsuit. Diverted listed fish are killed in residual depressions in the irrigated meadow, and often become entrained and killed in pumps used to drive wheel lines used to irrigate alfalfa.
After Practice Situation	A modular rotating drum paddlewheel screen is installed in the ditch about 100 feet downstream of the diversion dam. The screen is outfitted with a screw-gated 10-inch smooth HDPE pipe buried below the floodplain that connects the bypass entrance to a deep pool in the adjacent stream. The screen is placed on an excavated bed backfilled with compacted sand and gravel, and bolted to a small reinforced poured-in-place concrete headwall. Inspection during the first operational season following construction confirms that the screen is within hydraulic criteria and providing adequate protection to listed fish. The screen structure is fenced from livestock, and inspected and maintained according to contractual agreements. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	CFS
Scenario Unit	Cubic Feet per Second
Scenario Typical Size	5 modular prefab paddlewheel, concrete headwall with screw gate, gated 100' of 10-inch smooth hdpe bypass pipe

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$152.00	\$30.40
Equipment/Installation	\$23,864.25	\$4,772.85
Labor	\$16,932.60	\$3,386.52
Mobilization	\$865.39	\$173.08
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$41,814.24	\$8,362.85

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	200	\$152.00
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-place in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	15	\$7,544.10
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	1	\$289.11
Equipment/Installation	50	Earthfill, Manually Compacted	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.34	20	\$106.80
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	40	\$6,294.40
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	1211	Truck, Concrete Pump	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$183.32	32	\$5,866.24

Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	32	\$2,350.40
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	60	\$2,372.40
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	40	\$1,364.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	120	\$9,986.40
Mobilization	1043	Mobilization, Material, distance > 50 miles	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been included in the component price.	Dollar	\$1.00	2	\$2.00
Mobilization	1137	Mobilization, very small equipment	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$75.96	1	\$75.96
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	17
Scenario Name	Rotating Drum Screen
Scenario Description	<p>A fish screen used at surface (gravity) diversions intended to prevent juvenile or small-bodied adult fish from entering ditches, canals, laterals or other pathways that lead to migration dead-ends or sources of mortality. Rotating drum screens are active by design, meaning that they are outfitted with mechanisms that automatically cycle to keep the screen free of debris that will restrict the screen area, impede flow through the screen, and may cause the screen to fail. These screens are powered electric motors that rotate a drum covered in fine stainless steel mesh. The drum rotates in the direction of the incoming flow, and is designed to protect fish from entrainment into the diversion while at the same time rolling fine debris attached to the screen face into the ditch or canal below. Rotating drum screens can be installed in the active channel along a streambank, but are most commonly built in a canal below a diversion structure. Aquatic organisms that encounter a screen installed in a canal are diverted back into the adjacent stream through a buried pipe.</p> <p>Screens installed in the active channel are built at the point of diversion with the screen face aligned parallel to the flow of the river. Bankline modifications can be necessary to achieve proper alignment. Screens installed in a canal can be aligned differently and are best sited at a canal location that minimizes the straight-line bypass/return path distance. Again, canal installation is the most common.</p> <p>A fully functional screen is designed to meet criteria intended to protect target organisms from being swept into and pinned against or along the screen face (impingement). When this occurs, animals can be physically harmed or, in the case of a rotating drum screen, introduced into the diversion works behind the screen. Active screens are designed to ensure that the approach velocity will not exceed .4 feet per second (fps). Approach velocity is calculated by dividing the maximum screened flow volume by the vertical projection of the effective screen area at maximum submergence. For a rotating drum screen the design submergence should not be more than 85% or less than 65% of the screen diameter. Screen design should strive to provide nearly uniform flow distribution across the screen surface. Screens longer than 6 feet must be angled to the direction of incoming flow and have sweeping velocities (along the face of the screen) greater than the approach velocity, and sweeping velocities should not decrease along the face of the screen. Screen face openings must not exceed 3/32 inch in diameter, and perforated plate must be smooth to the touch with openings punched through in the direction of approaching flow. Material used for the screen face should be corrosion resistant and sufficiently durable to maintain a smooth uniform surface with long term use. Bypass design flow should be about 5% of the diverted amount, include an easily accessible entrance, and flow velocity in the bypass pipe or channel should not exceed 0.2fps. Minimum design depth in a bypass pipe should be at least 40% of the pipe diameter. Bypass entrances should be installed with independent flow control capability. The face of all screen surfaces must be placed flush (to the extent</p>
Before Practice Situation	An unscreened gravity diversion removes water and fish from a medium-sized stream. The ditch under the 75 cfs diversion serves a number of pumps and turnouts used to irrigate alfalfa and flood irrigate hay. The diversion is run from late winter into fall, although the flood irrigated crops are shut off in mid-summer to allow growth and prepare the fields for mowing and haying. Although the diversion is owned by a nth-generation landowner with proven, long-standing rights to the diverted water, recent fish listings under the Endangered Species Act present liability risks in the face of a third party lawsuit. Diverted listed fish are killed in residual depressions in the irrigated meadow, and often become entrained and killed in pumps used to drive wheel lines used to irrigate alfalfa.
After Practice Situation	A rotating drum screen consisting of three 8-foot wide, 4-foot diameter drums each driven by a 5hp electric motor is installed in the ditch about 200 feet downstream of the diversion dam. The screen is outfitted with a screw-gated 20-inch smooth HDPE pipe buried below the floodplain that connects the bypass entrance to a deep pool in the adjacent stream. The screen is placed in a concrete section extending above, underneath and below the drum location that forms the structure holding the drums, side and bottom seals, bypass entrance, and screen fore and afterbay. A steel I-beam structure is erected to form continuous overhead cover above the screen bays, and outfitted with a traveling electric winch used to raise each drum for periodic maintenance and seal inspection. Inspection during the first operational season following construction confirms that the screen is within hydraulic criteria and providing adequate protection to listed fish. The screen structure is fenced from livestock, and inspected and maintained according to contractual agreements. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	CFS
Scenario Unit	Cubic Feet per Second
Scenario Typical Size	75

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$304.00	\$4.05
Equipment/Installation	\$66,774.35	\$890.32
Labor	\$18,296.60	\$243.95
Mobilization	\$865.39	\$11.54
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$86,240.34	\$1,149.87

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Equipment/Installation	38	Concrete, CIP, formed reinforced	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$502.94	100	\$50,294.00
Equipment/Installation	40	Clearing and Grubbing	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$289.11	1	\$289.11
Equipment/Installation	50	Earthfill, Manually Compacted	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.34	50	\$267.00
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	40	\$6,294.40
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20

Equipment/Installation	1211	Truck, Concrete Pump	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$183.32	32	\$5,866.24
Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	32	\$2,350.40
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	60	\$2,372.40
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	80	\$2,728.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	120	\$9,986.40
Mobilization	1043	Mobilization, Material, distance > 50 miles	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been included in the component price.	Dollar	\$1.00	2	\$2.00
Mobilization	1137	Mobilization, very small equipment	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$75.96	1	\$75.96
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	15
Scenario Name	Step Pool Weir
Scenario Description	<p>Step Pool Weirs are constructed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Disturbed areas are revegetated using Critical Area Planting (342) and access control and signage are provided. Scenario does not include additional measures needed in the active channel and floodplain or at an existing dam necessary to control flow associated with nature-like fishway.</p> <p>RESOURCE CONCERNS: INADEQUATE HABITAT FOR FISH AND WILDLIFE –Habitat degradation; EXCESS WATER – Ponding, flooding, seasonal high water table, seeps, and drifted snow; WATER QUALITY DEGRADATION – Elevated water temperature; EROSION– Excessive bank erosion from streams shorelines or water conveyance channels</p> <p>Associated Practices (326) Clearing and Snagging, (342) Critical Area Planting, (382) Fence, (390) Riparian Herbaceous Cover, (391) Riparian Forest Buffer, (612) Tree/Shrub Establishment, 580 Streambank and Shoreline Protection, (395) Stream Habitat Improvement and Management, (410) Grade Stabilization Structure, (582) Open Channel, (584) Channel Bed Stabilization, (580) Streambank and Shoreline Protection, (587) Structure for Water Control 580 Streambank and Shoreline</p>
Before Practice Situation	An instream barrier prevents upstream migration of native aquatic organisms and no support exists for removal. Similarly, an instream barrier is removed, and interested parties require maintenance of an upstream pool or pond.
After Practice Situation	A step pool weir is constructed in place of a removed barrier. The step pool weir is constructed of rock that provides quality passage conditions for a number of species and geomorphic stability over a range of flows. Resource Concerns are addressed within the context of the site. The typical scenario is for a 35' wide channel 100 feet long with weirs every 10'.
Scenario Feature Measure	Cubic Yard of Material
Scenario Unit	Cubic Yard
Scenario Typical Size	800

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$44,712.96	\$55.89
Equipment/Installation	\$21,978.00	\$27.47
Labor	\$14,428.68	\$18.04
Mobilization	\$787.43	\$0.98
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$81,907.07	\$102.38

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	300	\$228.00
Materials	1761	Boulder	Rock boulders. Includes materials and local delivery (less than 50 miles) only.	Ton	\$29.07	1200	\$34,884.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	292	\$9,600.96
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	390	\$951.60
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	80	\$12,588.80
Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	80	\$2,826.40
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	10	\$1,867.20
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	22	\$869.88
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	40	\$1,028.40
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	160	\$5,456.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	10	\$416.80

Labor	235	Specialist Labor	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$83.22	80	\$6,657.60
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10

**Scenario Worksheet**

**Practice and Scenario Description:**

<b>Information Type</b>	<b>Data</b>
Region	New England
State	Connecticut
Discipline Group	Wildlife Wetland
Practice Code/Name	396 - Aquatic Organism Passage
Scenario ID	6
Scenario Name	Stream Simulation Culvert
Scenario Description	<p>A multi-plate galvanized steel or aluminum culvert (arch or box) used at a road-stream crossing to provide aquatic organism passage (AOP) and promote stream ecological and geomorphic function. They commonly attach to preformed reinforced or poured-in-place concrete footings. Bottomless culverts used for AOP are sized according to geomorphic analyses, not just an estimate of runoff and streamflow at the site from the contributing watershed. In addition, bottomless culverts used for AOP are filled with a mixture of rock and gravel sized to emulate site stream conditions and geomorphic units in the channel. The simulated streambed material is continuous throughout the culvert barrel, and blended with the intact streambed at the culvert inlet and outlet. The first estimate of culvert span is obtained by analyzing bankfull channel width on a reach of stream not affected by an existing road crossing or other conditions that alter self-formed conditions. In the case of a culvert replacement, bankfull investigations are begun at least 10-20 estimated bankfull channel widths above the existing stream crossing. Culvert span is then increased according to channel bed composition and texture, bank characteristics, channel alignment at the crossing section, and other parameters that may affect channel dynamics and stability.</p> <p>Once the culvert span is determined, culvert length will be dictated by roadway geometry and loading requirements, and site stream conditions. Concrete headwalls and/or wingwalls may be necessary in shorter installations and/or where fill/roadway cover is limited or the stream alignment is not perpendicular to the road axis. Culvert wall thickness and footing requirements are determined by road loading requirements and site geotechnical investigations. Generally, the preferred footing is a T-design with a spread footing with stem wall. Connecting the culvert leg to the footing can be done by welding, grouting, bolting. Stream geomorphic characteristics, including the reach longitudinal profile, channel cross-sectional shape, substrate composition and arrangement, and bank shape and composition are determined.</p> <p>Bottomless arch or box culverts are commonly delivered in sections and bolted together in the field. Smaller arches can be delivered in one piece. They are installed with an assortment of equipment used for excavation, placing material, and delivering and removing material. Construction elements generally include an assortment of rock used to create riffles, cascades, or riffle-pool sequences with between 6 to 12 inches of water surface elevation drop between adjacent structures. Stream dewatering and diversion around the work site is often required, and temporary road closure or re-routing may also be required. Channel bed material within the culvert barrel varies according to prevailing stream characteristics at the crossing site. Footings are placed or poured, and the new streambed is set at a slope that</p>
Before Practice Situation	An existing undersized culvert as contributed to general bed and bank scour downstream of a road crossing, and may have contributed to the deposition of a wedge of sediment upstream of the road crossing. The road may be overtopped by high flows, resulting in outright failure, landowner accessibility problems, access by and to emergency services, and hamper post-flood recovery efforts. An upstream impoundment created by the undersized culvert has contributed to water quality problems including high water temperatures and the deposition and later mobilization of polluted fine sediment. Native aquatic organisms are unable to pass through the road crossing because the culvert outlet is perched above the downstream pool, and high velocities are not negotiable by animals that are able to leap into the culvert barrel.
After Practice Situation	The undersized culvert is replaced with a bottomless arch or box culvert sized, placed, and backfilled with material determined by geomorphic analyses performed in a reference reach upstream of the crossing location. Geomorphic and ecological functions are preserved through the crossing site, enhancing AOP, water quality, and culvert longevity. In addition, because the culvert is sized to promote the transport of streamflow and the materials it carries, it requires decreased maintenance activities over time. Landowners are able to access their holdings across a range of flows, and are able to seek and receive emergency and post-flood recovery services. Resource Concerns are addressed within the context of the site.
Scenario Feature Measure	Length of Multi-plate arch or box
Scenario Unit	Linear Foot
Scenario Typical Size	20 10' X 5'3" X 20' arch with 2'X3' precast footings

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$16,115.35	\$805.77
Equipment/Installation	\$19,510.80	\$975.54
Labor	\$8,201.40	\$410.07
Mobilization	\$1,300.53	\$65.03
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$45,128.08	\$2,256.40

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	400	\$304.00
Materials	1834	Aggregate, river rock	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$32.88	45	\$1,479.60
Materials	1836	Footing, concrete, precast	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Materials only.	Foot	\$153.91	40	\$6,156.40
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	45	\$415.35
Materials	1979	Culvert, Multi-Plate arch	Multi-plate arch culvert, typically 7 Gauge corrugated plate. Includes metal arch materials only, does not include footings.	Pound	\$0.97	8000	\$7,760.00
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	100	\$244.00
Equipment/Installation	932	Hydraulic Excavator, 2 CY	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$157.36	60	\$9,441.60

Equipment/Installation	933	Skidsteer, 80 HP	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$35.33	40	\$1,413.20
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	25	\$4,668.00
Equipment/Installation	1400	Truck, dump, 18 CY	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$93.60	40	\$3,744.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	40	\$1,581.60
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	60	\$1,542.60
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	100	\$3,410.00
Labor	234	Supervisor or Manager	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$41.68	40	\$1,667.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20