

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	2
Scenario Name	New 12" gravel road in wet, level terrain
Scenario Description	Newly Constructed gravel road with min. 12 inch thick compacted gravel surface over geotextile in relatively level ground in wet areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travel way for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The road will be 14 feet wide with geotextile and 12 inch gravel surfacing at the top. It is mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$5,494.50	\$10.99
Equipment/Installation	\$4,936.80	\$9.87
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$11,773.82	\$23.55

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	275	\$5,494.50
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	210	\$856.80
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	1000	\$2,440.00
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	410	\$1,640.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	5
Scenario Name	Rehabilitation of existing gravel road in wet, level terrain
Scenario Description	Repair and rehabilitation of gravel road with min. 12 inch thick compacted gravel surface over geotextile on existing alignment in wet, level terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The damaged portions of the road will be repaired to a full 14 feet width with a geotextile and 12" gravel surface at the top, mostly in embankment less than 3 feet in height, (average 2 ft), typical side slopes 2:1. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$1,698.30	\$3.40
Equipment/Installation	\$1,497.20	\$2.99
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$4,538.02	\$9.08

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	85	\$1,698.30
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	65	\$265.20
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	300	\$732.00
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	125	\$500.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	11
Scenario Name	Rehabilitation of existing gravel road in wet, sloped terrain
Scenario Description	Repair and rehabilitation of gravel road with min. 12 inch thick compacted gravel surface over geotextile on existing alignment in wet, steep sloped terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dust. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively wet and swampy land with steep sloped terrain.
After Practice Situation	The damaged portions of the road will be repaired to a full 14 feet width with a geotextile and 12" gravel surface at the top, 50% in embankment and 50% in excavation less than 3 feet in height, (average 2 ft), typical side slopes 2:1. Out of total excavation, 60% is considered common earth and 40% hard dig or rocks. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$1,698.30	\$3.40
Equipment/Installation	\$2,084.80	\$4.17
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$5,125.62	\$10.25

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	85	\$1,698.30
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	120	\$489.60
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	300	\$732.00
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	80	\$363.20
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	125	\$500.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	8
Scenario Name	New 12" gravel road in wet, sloped terrain
Scenario Description	Newly Constructed gravel road with min. 12 inch thick compacted gravel surface over geotextile in steep sloped ground in wet areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travelway for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of wet and swampy land areas with steep sloped terrain.
After Practice Situation	The Road will be 14 feet wide with a geotextile and 12 inch gravel surfacing at the top. It is 50% in embankment and 50% in excavation less than 3 feet in height, (average 2 ft) typical side slopes 2:1. Out of total excavation, 60% is considered common earth and 40% hard dig or rocks. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$5,494.50	\$10.99
Equipment/Installation	\$6,894.70	\$13.79
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$13,731.72	\$27.46

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	275	\$5,494.50
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	395	\$1,611.60
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	1000	\$2,440.00
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	265	\$1,203.10
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	410	\$1,640.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	4
Scenario Name	Rehabilitation of existing earth road in dry, level terrain
Scenario Description	Repair and rehabilitation of compacted earth road in existing alignment in dry, level terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively dry and level terrain lands.
After Practice Situation	The damaged portions of the road will be repaired to a full 14 feet width at the top, mostly in embankment less than 3 feet in height, (average 2 ft), typical side slopes 2:1. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$0.00	\$0.00
Equipment/Installation	\$960.40	\$1.92
Labor	\$316.32	\$0.63
Mobilization	\$700.33	\$1.40
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$1,977.05	\$3.95

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	205	\$820.00
Equipment/Installation	48	Excavation, Common Earth, side cast, small equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.16	65	\$140.40
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10
Mobilization	1138	Mobilization, small equipment	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$187.23	1	\$187.23

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	1
Scenario Name	New earth road in dry, level terrain.
Scenario Description	Newly constructed compacted earth road in relatively level terrain and dry areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travelway for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively dry and level terrain lands.
After Practice Situation	The road will be 14 feet wide at the top, mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$0.00	\$0.00
Equipment/Installation	\$3,133.60	\$6.27
Labor	\$316.32	\$0.63
Mobilization	\$700.33	\$1.40
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$4,150.25	\$8.30

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	670	\$2,680.00
Equipment/Installation	48	Excavation, Common Earth, side cast, small equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.16	210	\$453.60
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10
Mobilization	1138	Mobilization, small equipment	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$187.23	1	\$187.23

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	10
Scenario Name	Rehabilitation of existing earth road in wet, sloped terrain
Scenario Description	Repair and rehabilitation of compacted earth road in existing alignment in relatively dry but steep sloped terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively dry lands with steep sloped terrain.
After Practice Situation	The damaged portions of the road will be repaired to a full 14 feet width at the top, 50% in embankment and 50% in excavation less than 3 feet in height, (average 2:1), typical side slopes 2:1. Out of total excavation, 60% is considered common earth excavation and 40% hard dig or rocks. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$0.00	\$0.00
Equipment/Installation	\$1,422.40	\$2.84
Labor	\$316.32	\$0.63
Mobilization	\$700.33	\$1.40
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$2,439.05	\$4.88

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	200	\$800.00
Equipment/Installation	48	Excavation, Common Earth, side cast, small equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.16	120	\$259.20
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	80	\$363.20
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10
Mobilization	1138	Mobilization, small equipment	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$187.23	1	\$187.23

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	7
Scenario Name	New earth road in dry, sloped terrain
Scenario Description	Newly constructed compacted earth road in steep sloped terrain but relatively dry areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travelway for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively dry lands with steep slopes.
After Practice Situation	The road will be 14 feet wide at the top, 50% in embankment and 50% in excavation less than 5 feet in height, (average 2:1) typical cut and fill side slopes 2:1. Out of total excavation, 60% is considered common earth and 40% hard dig or rocks. A properly constructed, well defined access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$0.00	\$0.00
Equipment/Installation	\$4,736.30	\$9.47
Labor	\$316.32	\$0.63
Mobilization	\$700.33	\$1.40
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$5,752.95	\$11.51

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	670	\$2,680.00
Equipment/Installation	48	Excavation, Common Earth, side cast, small equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.16	395	\$853.20
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	265	\$1,203.10
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	1	\$513.10
Mobilization	1138	Mobilization, small equipment	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$187.23	1	\$187.23

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	6
Scenario Name	Existing geocell road in wet, level terrain
Scenario Description	Repair and rehabilitation of gravel, geotextile, and geocell road with min. 6 inch thick compacted gravel with geocell surface on existing alignment in wet, level terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The road will be 14 feet wide with geotextile, 6 inch gravel, and geocell surfacing. It is mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$3,314.10	\$6.63
Equipment/Installation	\$1,497.20	\$2.99
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$6,153.82	\$12.31

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	240	\$2,215.20
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	55	\$1,098.90
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	65	\$265.20
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	300	\$732.00
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	125	\$500.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	3
Scenario Name	New geocell road in wet, level terrain
Scenario Description	Newly Constructed geotextile, gravel, and geocell road with min. 6 inch thick compacted gravel with geocell surface in relatively level ground in wet areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travel way for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The road will be 14 feet wide with geotextile, 6 inch gravel, and geocell surfacing. It is mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$10,880.50	\$21.76
Equipment/Installation	\$4,936.80	\$9.87
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$17,159.82	\$34.32

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	800	\$7,384.00
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	175	\$3,496.50
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	210	\$856.80
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	1000	\$2,440.00
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	410	\$1,640.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	12
Scenario Name	New geocell road in wet, sloped terrain
Scenario Description	Repair and rehabilitation of gravel, geotextile, and geocell road with min. 6 inch thick compacted gravel with geocell surface on existing alignment in wet, steep sloped terrain. The extent of construction work over an existing alignment is assumed to average 30% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The road will be 14 feet wide with geotextile, 6 inch gravel, and geocell surfacing. It is mostly in embankment less than 3 feet in height, (average 2:1) typical side slopes 2:1. Out of total excavation, 60% is considered common earth and 40% hard dig or rocks. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$3,314.10	\$6.63
Equipment/Installation	\$2,084.80	\$4.17
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$6,741.42	\$13.48

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	240	\$2,215.20
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	55	\$1,098.90
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	120	\$489.60
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	300	\$732.00
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	80	\$363.20
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	125	\$500.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20

Scenario Worksheet

Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Agricultural Engineering
Practice Code/Name	560 - Access Road
Scenario ID	9
Scenario Name	New geocell road in wet, sloped terrain
Scenario Description	Newly Constructed geotextile, gravel, and geocell road with min. 6 inch thick compacted gravel and geocell surface in steep sloped ground in wet areas. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practice.
Before Practice Situation	An agricultural enterprise which requires, but does not have, a fixed travel way for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of relatively wet and swampy but level terrain lands.
After Practice Situation	The Road will be 14 feet wide with geotextile, 6 inch gravel, and geocell surfacing. It is mostly in embankment less than 3 feet in height, (average 2 ft) typical side slopes 2:1. Out of total excavation, 60% is considered common earth and 40% hard dig or rocks. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). When seeding or revegetation is required, use Critical Area Planting (342). Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).
Scenario Feature Measure	Length of Roadway
Scenario Unit	Foot
Scenario Typical Size	500

Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$10,880.50	\$21.76
Equipment/Installation	\$6,894.70	\$13.79
Labor	\$316.32	\$0.63
Mobilization	\$1,026.20	\$2.05
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$19,117.72	\$38.24

Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	1842	Geocell, 6"	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$9.23	800	\$7,384.00
Materials	1099	Aggregate, Gravel, Ungraded, Quarry Run	Includes materials, equipment and labor	Cubic yard	\$19.98	175	\$3,496.50
Equipment/Installation	1228	Excavation, common earth, wet, side cast, large equipment	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.08	395	\$1,611.60
Equipment/Installation	42	Geotextile, woven	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.44	1000	\$2,440.00
Equipment/Installation	47	Excavation, Rock, Ripping	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.54	265	\$1,203.10
Equipment/Installation	49	Earthfill, Roller Compacted	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.00	410	\$1,640.00
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	8	\$316.32
Mobilization	1140	Mobilization, large equipment	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$513.10	2	\$1,026.20