

## Scenario Worksheet

## Practice and Scenario Description:

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Engineering General
Practice Code/Name	578 - Stream Crossing
Scenario ID	1
Scenario Name	Stream Crossing, Bridge
Scenario Description	Install a bridge to allow stream flows to cross under access road or animal trail. Bridge opening determined by sizing for storm event dictated in standard. Scenario includes dewatering, abutments, girders, decking. Work consists of site preparation, dewatering, acquiring and installing abutments, girders, decking with necessary hardware, backfilling abutments, and armoring with geotextile and riprap. Riprap and geotextile are used to stabilize and protect abutments as needed. Scenario based on cast in place concrete abutments, steel girders, and timber deck. Travel surface shall be wooden deck surface. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Span is less than 14 feet. Load is H-20. Width is 14 feet including curbs. Abutments are <= 6 feet. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.
Before Practice Situation	Water flow could not cross access road or trail without erosion, or access road or trail could not cross channel.
After Practice Situation	Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.
Scenario Feature Measure	square footage of bridge deck
Scenario Unit	Square Foot
Scenario Typical Size	252

## Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$8,942.32	\$35.49
Equipment/Installation	\$3,515.15	\$13.95
Labor	\$3,436.00	\$13.63
Mobilization	\$274.33	\$1.09
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$16,167.80	\$64.16

## Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	44	Rock Riprap, Placed with geotextile	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$65.87	20	\$1,317.40
Materials	1496	Block, pre-cast concrete, modular	Pre-cast concrete blocks, typically 2ft x 2ft x 6ft, includes installation and delivery.	Cubic Yard	\$106.54	18	\$1,917.72
Materials	1779	Steel, structural steel members	Structural steel, includes materials and fabrication.	Pound	\$0.88	4200	\$3,696.00
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	100	\$76.00
Materials	46	Aggregate, Gravel, Graded	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$27.76	20	\$555.20
Materials	1045	Dimension Lumber, untreated	Untreated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.69	2000	\$1,380.00
Equipment/Installation	969	Water management, Flooding & dewatering	Includes equipment, power unit and labor costs.	Acre Foot	\$186.72	15	\$2,800.80
Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	8	\$587.60
Equipment/Installation	1227	Excavation, common earth, side cast, large equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.69	75	\$126.75
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	8	\$272.80
Labor	230	Skilled Labor	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.54	80	\$3,163.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33

**Scenario Worksheet**

**Practice and Scenario Description:**

Information Type	Data
Region	New England
State	Connecticut
Discipline Group	Engineering General
Practice Code/Name	578 - Stream Crossing
Scenario ID	2
Scenario Name	Stream Crossing, Culvert Installation
Scenario Description	Install a new culvert. Work includes dewatering, site preparation and removing any old crossing, acquiring and installing culvert pipe with gravel bedding and fill (compacted), and building headwalls. If a different travel surface is needed, refer to another appropriate standard for the surfacing. 30 inch Culvert installation with <75 cy of fill needed and < 2 yds rock riprap for headwalls. Pipe is 40 feet long. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows.
Before Practice Situation	Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.
After Practice Situation	Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.
Scenario Feature Measure	Culvert
Scenario Unit	Inch-Foot
Scenario Typical Size	1200

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$2,554.14	\$2.13
Equipment/Installation	\$956.52	\$0.80
Labor	\$341.00	\$0.28
Mobilization	\$300.54	\$0.25
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$4,152.20	\$3.46

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	44	Rock Riprap, Placed with geotextile	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$65.87	2	\$131.74
Materials	46	Aggregate, Gravel, Graded	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$27.76	50	\$1,388.00
Materials	1247	Pipe, HDPE, CPT, Double Wall, Soil Tight, 30"	Pipe, Corrugated HDPE Double Wall, 30" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$25.86	40	\$1,034.40
Equipment/Installation	931	Hydraulic Excavator, 1 CY	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$94.05	10	\$940.50
Equipment/Installation	50	Earthfill, Manually Compacted	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.34	3	\$16.02
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	10	\$341.00
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33
Mobilization	1142	Mobilization, General labor	Mobilization of general labor: Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$26.21	1	\$26.21

**Scenario Worksheet**

**Practice and Scenario Description:**

<b>Information Type</b>	<b>Data</b>
Region	New England
State	Connecticut
Discipline Group	Engineering General
Practice Code/Name	578 - Stream Crossing
Scenario ID	4
Scenario Name	Hard armored low water crossing
Scenario Description	Stabilize the bottom and slope of a stream channel using rock riprap or cast in place concrete. This scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with rock riprap or cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks or concrete. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.
Before Practice Situation	Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.
After Practice Situation	Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.
Scenario Feature Measure	Crossing dimensions
Scenario Unit	Square Foot
Scenario Typical Size	420

**Cost Summary:**

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$1,223.66	\$2.91
Equipment/Installation	\$177.32	\$0.42
Labor	\$68.20	\$0.16
Mobilization	\$274.33	\$0.65
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$1,743.51	\$4.15

**Cost Details:**

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	50	\$38.00
Materials	44	Rock Riprap, Placed with geotextile	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$65.87	18	\$1,185.66
Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	2	\$146.90
Equipment/Installation	1227	Excavation, common earth, side cast, large equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.69	18	\$30.42
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	2	\$68.20
Mobilization	1139	Mobilization, medium equipment	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$274.33	1	\$274.33

## Scenario Worksheet

## Practice and Scenario Description:

<b>Information Type</b>	<b>Data</b>
Region	New England
State	Connecticut
Discipline Group	Engineering General
Practice Code/Name	578 - Stream Crossing
Scenario ID	3
Scenario Name	Low water crossing using prefabricated products
Scenario Description	To install a stable crossing medium on channel bottom and approaches. Medium includes but not limited to precast concrete blocks, geocells, pavers, and gabions. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.
Before Practice Situation	Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.
After Practice Situation	Access road and waterflow are able to cross each other in a stable manner.Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.
Scenario Feature Measure	low water crossing
Scenario Unit	Square Foot
Scenario Typical Size	420

## Cost Summary:

Cost Category	Scenario Cost	Scenario Cost/Unit
Materials	\$697.94	\$1.66
Equipment/Installation	\$825.32	\$1.97
Labor	\$1,096.60	\$2.61
Mobilization	\$26.21	\$0.06
Acquisition of Technical Knowledge	\$0.00	\$0.00
Foregone Income	\$0.00	\$0.00
Total	\$2,646.07	\$6.30

## Cost Details:

Cost Category	Component ID	Component Name	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Materials	43	Silt Fence	Silt Fence with support post, includes materials, equipment and labor	Foot	\$0.76	50	\$38.00
Materials	45	Aggregate, Sand, Graded, Washed	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$26.71	6	\$160.26
Materials	46	Aggregate, Gravel, Graded	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$27.76	18	\$499.68
Equipment/Installation	1054	GeoCell, 4"	Polymer 3-D cellular grid 4" deep that is filled with stone or earth. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$12.96	50	\$648.00
Equipment/Installation	1215	Truck, dump, 12 CY	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$73.45	2	\$146.90
Equipment/Installation	1227	Excavation, common earth, side cast, large equipment	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.69	18	\$30.42
Labor	233	Equipment Operators, Heavy	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.10	2	\$68.20
Labor	231	General Labor	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$25.71	40	\$1,028.40
Mobilization	1142	Mobilization, General labor	Mobilization of general labor: Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$26.21	1	\$26.21