

Practice: 658 - Wetland Creation

Scenario: #1 - Wetland Creation, Wildlife Pond

Scenario Description: A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation. Work involved includes excavation and removing material to a nearby area. Dozer shapes wetland and disposal areas. Resource concerns are 22 - INADEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation: The site is in cropland on an upland, non floodplain site (interfluve).

After Situation: An excavation with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been hauled to and spread on adjacent areas. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Scenario Feature Measure: Acres of Wetland

Scenario Unit: Acre

Scenario Typical Size: 2

Total Scenario Cost: \$20,004.06

Scenario Cost/Unit: \$10,002.03

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$36.00	96	\$3,455.81
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$25.96	8	\$207.66

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	2	\$974.78
-------------------------------	------	--	------	----------	---	----------

Equipment Installation

Dozer, 105 HP	1320	Track mounted Dozer with horsepower range of 90 to 125. Equipment and power unit costs. Labor not included.	Hour	\$84.20	8	\$673.62
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.68	3227	\$5,426.81
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$96.51	96	\$9,265.38