

**NATURAL RESOURCES CONSERVATION SERVICE  
CONSERVATION PRACTICE STANDARD**

**OBSTRUCTION REMOVAL**

(Ac.)

**CODE 500**

**DEFINITION**

Removal and disposal of buildings, structures, other works of improvement, vegetation, debris or other materials.

**PURPOSE**

To safely remove and dispose of unwanted obstructions in order to apply conservation practices or facilitate the planned land use.

**CONDITIONS WHERE PRACTICE APPLIES**

On any land where existing obstructions interfere with planned land use development, conservation practices, public safety or infrastructure. This standard is not intended for the removal of obstructions from aquatic environments.

**CRITERIA**

All Federal, state, and local laws, rules, and regulations, including local inland wetland agency regulations, governing the construction and use of this practice as well as setbacks from wells, surface water and property boundaries shall be followed. Planned work shall comply with all federal, state, and local laws and permit conditions and requirements.

**The landowner shall obtain all necessary permits prior to construction or any land clearing activities.**

Contact 'Call Before You Dig' two full working days in advance to locate buried lines and cables. Call 1-800-922-4455 or 811 to identify the location of utility lines in the construction area and to arrange the shut off of utilities if necessary.

Remove obstructions by demolition, excavation or other means required for removal. Dispose of all debris from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage.

Dispose of inorganic materials such as rock piles, boulders, stones, concrete or masonry structures and metal or concrete fence posts by reusing, removal or burial at approved locations.

Dispose of organic materials such as wooden fence posts, woody vegetation, and woody building materials by removal to an approved landfill or recycling center, burial at an approved location, burning or other appropriate method. If burning is used, implement appropriate smoke management to protect public health and safety. Woody material may be chipped on site, used for brush piles or left for coarse woody debris in adjacent locations.

Dispose of trash and non-woody building materials in an approved landfill or recycling center.

When removing buildings, ensure that all utilities, such as gas and electric, have been shut off and disconnected from the structure before beginning demolition.

The removal of obstructions can expose toxic or polluted materials. If toxic or polluted materials are expected to be found during the obstruction removal, specify appropriate handling and disposal criteria in the plans and specifications

When removing obstructions that contain chromated copper arsenate (CCA) treated wood, do not burn the wood. Burning of CCA treated wood can release toxic amounts of

arsenic into the air and ash that are very harmful to human and animal health. CCA treated wood should be buried in an approved landfill.

Reshape and regrade all areas disturbed by the obstruction removal so that they blend with the surrounding land features and conditions. Any foundations or below ground portions of the obstruction that remain in place shall have sufficient soil cover to meet the requirements of the planned land use. Compact fill areas according to site specific requirements.

Revegetate or otherwise protect from erosion disturbed areas as soon as possible after construction. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements.

### **CONSIDERATIONS**

The recycling or reuse of materials should be considered as the first option for disposal of materials from obstruction removal. Most woody debris can be recycled into mulch or other products. Recycling or other environmentally friendly options exist for the disposal of many other materials as well.

Demolition activities can generate large amounts of dust. Where necessary, use dust suppression techniques such as spraying water on the removal site to suppress dust.

Obstruction removal can result in the disturbance of large areas that are subject to erosion during the demolition process. Where necessary include provisions in the plans to control erosion and offsite sedimentation.

Obstruction removal often involves heavy equipment working in environmentally sensitive areas. Ensure that servicing and refueling of equipment is done in a manner that prevents spills and minimizes volatilization.

Demolition of structures and the removal of debris can be a hazardous undertaking. This is especially true for the removal of downed and tangled trees. This type of work should be done by well qualified personnel with proper equipment following appropriate safety procedures.

### **NRCS, CT**

**December 2013**

Old buildings, structures and trees can provide habitat for wildlife. The potential for use by and presence of at-risk species should be considered and addressed prior to any obstruction removal activity. The presence of roosting birds and bats may also pose a health and safety hazard to workers that should be considered.

### **PLANS AND SPECIFICATIONS**

Prepare plans and specifications for obstruction removal that describe the requirements for applying the practice according to this standard. Plans and specifications for this practice can be included in the plans and specifications for the practice it supports. As a minimum the plans and specifications shall include:

- A plan view showing the location of obstruction removal site.
- Details and location for the disposal of materials from the obstruction removal.
- Details of how the site will be stabilized after construction.
- Construction specifications that describe in writing, site specific requirements for the obstruction removal.

### **OPERATION AND MAINTENANCE**

Prepare an operation and maintenance (O&M) plan for the operator. O&M may be addressed only in the O&M Plan for Obstruction Removal or in conjunction with other O&M Plans for NRCS practices installed after the obstruction removal. The minimum requirements to be addressed in the operation and maintenance plan are:

- Periodic checking to ensure the site remains stable after the obstruction removal.
- When disposal of debris occurs on site, periodic checking to ensure that the disposal site remains stable.
- Repair any problems as soon as possible.

**REFERENCES**

U. S. Department of Labor. Occupational Safety and Health Administration. Safety and Health Regulations for Construction, 29 CFR 1926. U. S. Washington, DC.