

Practice: 362 - Diversion**Scenario: #1 - Diversion****Scenario Description:**

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, agricultural waste systems, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet, or other suitable outlet. Typical diversion is 400 feet long, 15' wide with 10-15' wide berm, installed on a field slope of 1 percent and requires ~1 CY excavation & compaction per LF. Topsoil is stripped, stockpiled and respread. Channel may be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Diversion is 400 feet long installed using a dozer. Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Scenario Feature Measure: Length of Diversion

Scenario Unit: Linear Feet

Scenario Typical Size: 400

Scenario Cost: \$2,129.40

Scenario Cost/Unit: \$5.32

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$69.03	15	\$1,035.45
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.88	222	\$195.36
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	15	\$505.35
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64