

**Practice: 436 - Irrigation Reservoir****Scenario: #1 - Embankment Dam with On-Site Borrow****Scenario Description:**

The reservoir, created by an embankment built across a natural depression, with an 18" diameter principal spillway outlet through the embankment, is controlled by a canal-style gate. Outlet can also serve as overflow protection with a 12" diameter standpipe and tee to the 18" pipe. Any watershed runoff will be diverted around reservoir. It will be built with approximately 4,500 cubic yards of on-site material. It will be about 19.9 feet high and 200 feet long and hold approximately 1,000,000 gallons (3 acre-feet). The top of berm will be 10 feet wide and the embankment side slopes will be 2.5 H to 1 V up and down stream.

Resource concern: Insufficient Water - Inefficient use of irrigation water.

Associated practices include: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 378 - Pond; 447 - Irrigation System, Tailwater Recovery; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

Divert water around - no spillway

**After Situation:**

This is an embankment, installed across a natural off-stream intermittent watercourse, used to store water for subsequent irrigation. It will be used to accumulate and store water for timely and efficient application of water through an irrigation system. The water source could be a well, irrigation district pipeline, and/or a pump from a stream. It is designed to deliver water by gravity to an open ditch or non-pressurized pipeline, generally in excess of 5 cfs. All earthen materials will be from on-site sources.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit:** Cubic Yards

**Scenario Typical Size:** 4,500

**Scenario Cost:** \$24,211.29

**Scenario Cost/Unit:** \$5.38

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
	1276				1	
<b>Equipment/Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.25	4500	\$19,125.00
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	8	\$340.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	16	\$395.84
<b>Materials</b>						
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$10.97	120	\$1,316.40
Coupling, HDPE CPT Dual Wall, Tee, 18"x18"x12"	1921	Tee, 18"x18"x12" - HDPE CPT Tee. Materials only.	Each	\$270.51	1	\$270.51
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$7.12	36	\$256.32
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	2	\$974.78

**Practice: 436 - Irrigation Reservoir****Scenario: #2 - Embankment Reservoir under 30 Acre-Feet****Scenario Description:**

This is a small rectangular embankment reservoir with a 10" diameter principal spillway through the embankment controlled by a canal-type gate. It is designed to accumulate, store, and deliver water by gravity to an open ditch or non-pressurized pipeline, in excess of 5 cfs. It will have an inside dimension of about 375 feet square, with 12 feet of fill and about 1600 feet total length of embankment (along the centerline). The embankment top will be 10 feet wide and the side slopes will no steeper than 2.5 H to 1 V inside and out. It will be built with approximately 28,500 cubic yards of on-site material. It will have a maximum water depth of 10 feet with 2 feet of freeboard and no auxiliary spillway. Volume is approximately 30 ac-ft (10,000,000 gallons).

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

The square reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream, an irrigation well, or an irrigation district canal.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit:** Cubic Yards

**Scenario Typical Size:** 28,500

**Scenario Cost:** \$125,728.66

**Scenario Cost/Unit:** \$4.41

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
	1276				4	
<b>Equipment/Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.25	28500	\$121,125.00
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	8	\$340.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	16	\$395.84
<b>Materials</b>						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.53	100	\$553.00
Catwalk, metal	1918	Metal pedestrian walk way giving access to the valve on a structure, typically 3' wide with railing. Materials only.	Foot	\$56.34	20	\$1,126.80
Screw gate, cast iron, 10" diameter, 10/0 head	1916	10" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$702.06	1	\$702.06
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	2	\$974.78

**Practice: 436 - Irrigation Reservoir****Scenario: #3 - Embankment Reservoir over 30 Acre-Feet****Scenario Description:**

This is a very large embankment reservoir with a 18" diameter drain pipe through the embankment controlled by a canal-type gate. It is designed to accumulate, store, and deliver water by gravity to an open ditch or non-pressurized pipeline, in excess of 5 cfs. It will have a top width of 12ft and centerline length of embankment of 5,280 feet. Average fill of 10 feet and the side slopes will be no steeper than 3 H to 1 V inside and out. It will be built with approximately 105,000 cubic yards of on-site material. It will have a maximum water depth of 8 feet with 2 feet of freeboard and no auxiliary spillway. Volume is approximately 320 ac-ft (104,500,000 gallons). Critical Area Planting and Mulching is required.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

The rectangular reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or an irrigation district canal.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit:** Cubic Yards

**Scenario Typical Size:** 104,200

**Scenario Cost:** \$458,440.82

**Scenario Cost/Unit:** \$4.40

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
	1276				40	
<b>Equipment/Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.25	104200	\$442,850.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	16	\$395.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	16	\$681.28
<b>Materials</b>						
Pipe, Steel, 18", Std Wt	1366	Materials: - 18" - Steel Std Wt	Foot	\$89.58	100	\$8,958.00
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
Catwalk, metal	1918	Metal pedestrian walk way giving access to the valve on a structure, typically 3' wide with railing. Materials only.	Foot	\$56.34	50	\$2,817.00
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	3	\$1,462.17
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	1	\$255.27

**Practice: 436 - Irrigation Reservoir****Scenario: #4 - Steel Tank****Scenario Description:**

A 20,000 Gallon, above ground, enclosed fabricated Steel or bottomless Corrugated Metal (with plastic liner and cover) tank with fittings, is installed on 6" of well compacted drain rock support pad with sand padding (CM tank), to store water from a reliable source for irrigation of an area less than 5 acres. The scenario assumes the typical dimensions of the tank are 24 feet in diameter and 6 feet tall. The scenario also assumes a 28 feet diameter gravel base pad to extend a minimum of 2 feet past the base of tank for adequate foundation support. This cost estimate scenario is for cost of the tank and pad only and does not include the cost for pumps, pipe, or fittings for the pipeline.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 533 - Pumping Plant; 447 - Irrigation System, Tailwater Recovery.

**Before Situation:**

Insufficient volume of water to complete an irrigation cycle at the required flow rate.

**After Situation:**

An above ground, enclosed fabricated steel or bottomless corrugated metal tank (with plastic liner and cover), capable of withstanding the elements, is used to accumulate and store water between irrigation cycles for a small irrigation system. This allows for an improved flow rate and timing of water application. Sources of water could be a well, a domestic water system, a very large roof area, a water ram , or a pump drawing water from a stream.

**Scenario Feature Measure: Volume of Tank Storage**

**Scenario Unit:** Gallons

**Scenario Typical Size:** 20,000

**Scenario Cost:** \$21,993.19

**Scenario Cost/Unit:** \$1.10

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Plate compactor	1915	Manually guided vibratroy plate compactor. Equipment only.	Hour	\$4.79	12	\$57.48
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	10	\$427.30
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	16	\$546.24
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	40	\$1,703.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	80	\$1,979.20
<b>Materials</b>						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	8	\$275.20
Tank, Corrugated Metal Storage, 20,000 gallon	1920	20,000 gallon capacity enclosed corrugated Metal Storage tank. Includes delivery to the site and anchoring material.	Each	\$16,064.57	1	\$16,064.57
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$24.04	12	\$288.48
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	2	\$140.98
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54

**Practice: 436 - Irrigation Reservoir****Scenario: #5 - Plastic Tank****Scenario Description:**

A 3,000 Gallon, above-ground, High Density Polyethylene plastic enclosed tank, is installed on 6" of well-compacted drain rock or a 4" thick reinforced concrete support pad, to store water from a reliable source for irrigation of an area less than one acre. The scenario assumes the typical dimensions of the tank are 102" in diameter and 93" tall. The scenario also assumes a 126" diameter gravel base or concrete pad to extend a minimum of 12" past the base of tank for adequate foundation support. This cost estimate scenario is for cost of the tank and pad only and does not include estimate for pumps, pipe, or connecting fittings.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 533 - Pumping Plant; 447 - Irrigation System, Tailwater Recovery.

**Before Situation:**

Insufficient volume of water to complete an irrigation cycle at the required flow rate.

**After Situation:**

An above-ground plastic tank, constructed to withstand the elements, is used to accumulate and store water between irrigation cycles for a very small irrigation system. This allows for an improved flow rate and timing of water application. Sources of water could be a well, a domestic water system, a large roof area, a water ram , or a pump drawing water from a stream.

**Scenario Feature Measure: Volume of Tank Storage**

**Scenario Unit:** Gallons

**Scenario Typical Size:** 3,000

**Scenario Cost:** \$3,816.54

**Scenario Cost/Unit:** \$1.27

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	6	\$256.38
Plate compactor	1915	Manually guided vibratroy plate compactor. Equipment only.	Hour	\$4.79	4	\$19.16
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	32	\$791.68
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	6	\$204.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	8	\$340.64
<b>Materials</b>						
Tank, Poly Enclosed Storage, >1,000	1075	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.61	3000	\$1,830.00
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$24.04	2	\$48.08
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	1	\$70.49
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	1	\$255.27

**Practice: 436 - Irrigation Reservoir****Scenario: #6 - Plastic Tank Buried****Scenario Description:**

A 3,000 Gallon, High Density Polyethylene plastic enclosed tank, is buried with a gravel base and 2' of cover, to store water from a reliable source for greenhouse irrigation of an area less than one acre. The tank is buried to prevent freezing if water is needed in the winter when seedling are started. The scenario assumes the typical dimensions of the tank are 102" in diameter and 93" tall. The scenario also assumes a 126" diameter gravel base to extend a minimum of 12" past the base of tank for adequate foundation support. This cost estimate scenario is for cost of the tank, gravel base, excavation and backfill only and does not include estimate for pumps, pipe, or connecting fittings.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 533 - Pumping Plant; 447 - Irrigation System, Tailwater Recovery.

**Before Situation:**

Insufficient volume of water to complete an irrigation cycle at the required flow rate.

**After Situation:**

A buried plastic tank is used to accumulate and store water between irrigation cycles for a very small irrigation system. This allows for an improved flow rate and timing of water application. Sources of water could be a well, a domestic water system, a large roof area, a water ram , or a pump drawing water from a stream.

**Scenario Feature Measure: Volume of Tank Storage**

**Scenario Unit:** Gallons

**Scenario Typical Size:** 3,000

**Scenario Cost:** \$4,493.07

**Scenario Cost/Unit:** \$1.50

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.59	120	\$430.80
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.25	90	\$382.50
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	32	\$791.68
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	8	\$273.12
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	8	\$340.64
<b>Materials</b>						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$24.04	2	\$48.08
Tank, Poly Enclosed Storage, >1,000	1075	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.61	3000	\$1,830.00
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	2	\$140.98
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	1	\$255.27

**Practice: 436 - Irrigation Reservoir****Scenario: #7 - Fiberglass Tank****Scenario Description:**

A 10,000 Gallon above ground, enclosed, fiberglass tank, is installed on 6" of well compacted drain rock support pad. The tank is used to store water from a reliable source for irrigation of areas less than 3 acres. The scenario assumes the typical dimensions of the tank are 15 feet in diameter and 8 feet tall. The scenario also assumes a 19 feet diameter gravel base pad to extend a minimum of 2 feet past the base of tank for adequate foundation support. This cost estimate scenario is for cost of the tank and pad only and does not include estimate for pumps, pipe, fittings for the pipeline, or catchment area.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 533 - Pumping Plant; 447 - Irrigation System, Tailwater Recovery.

**Before Situation:**

Insufficient volume of water to complete an irrigation cycle at the required flow rate.

**After Situation:**

A large fiberglass enclosed tank, capable of withstanding the elements, is used to accumulate and store water between irrigation cycles for a very small irrigation system. This allows for an improved flow rate and timing of water application and better efficiency. Sources of water could be a well, a domestic water system, a very large roof area, a water ram , or a pump drawing water from a stream.

**Scenario Feature Measure: Volume of Tank Storage**

**Scenario Unit:** Gallons

**Scenario Typical Size:** 10,000

**Scenario Cost:** \$11,138.85

**Scenario Cost/Unit:** \$1.11

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	8	\$341.84
Plate compactor	1915	Manually guided vibratroy plate compactor. Equipment only.	Hour	\$4.79	4	\$19.16
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	24	\$1,021.92
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	8	\$273.12
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	40	\$989.60
<b>Materials</b>						
Tank, Fiberglass Enclosed Storage, 10,000 gallon	1919	10,000 gallon capacity enclosed fiberglass water storage tank. Includes tank anchoring materials and delivery.	Each	\$7,697.45	1	\$7,697.45
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$24.04	6	\$144.24
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	2	\$140.98

**Practice: 436 - Irrigation Reservoir****Scenario: #8 - Excavated Spread On Site****Scenario Description:**

A reservoir with top width and lengths of 100'x100', 10ft deep, 1ft freeboard, 2:1 slopes is excavated in a relatively flat site and earthfill is spread on site. It is designed to accumulate, store, deliver or regulate water for a surface irrigation system.

Resource concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

An excavated reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or a spring.

**Scenario Feature Measure:** Volume of excavated earth

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 2,400

**Scenario Cost:** \$16,130.30

**Scenario Cost/Unit:** \$6.72

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$3.88	2400	\$9,312.00
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$184.60	24	\$4,430.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	24	\$593.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	24	\$819.36
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	2	\$974.78



**Practice: 436 - Irrigation Reservoir****Scenario: #9 - Excavated Spread Off Site****Scenario Description:**

A reservoir with top width and lengths of 100'x100', 10ft deep, 1ft freeboard, 2:1 slopes is excavated in a relatively flat site and earthfill is hauled for spreading off site. It is designed to accumulate, store, deliver or regulate water for a surface irrigation system.

Resource concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

An excavated reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or a spring.

**Scenario Feature Measure:** Volume of excavated earth

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 2,400

**Scenario Cost:** \$19,970.30

**Scenario Cost/Unit:** \$8.32

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$3.88	2400	\$9,312.00
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$184.60	24	\$4,430.40
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.32	12000	\$3,840.00
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	24	\$819.36
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	24	\$593.76
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$487.39	2	\$974.78

**Practice: 436 - Irrigation Reservoir****Scenario: #10 - Tailwater Recovery Greenhouse****Scenario Description:**

A 1,000 Gallon, High Density Polyethylene plastic enclosed tank, is installed in a greenhouse to recover, store, and re-use tailwater from ebb and flow benches. Typical sizing would be 0.5 gal/SF of bench area. The tank are typically installed below the greenhouse floor. The scenario assumes a typical 1,000 gal tank dimensions of 100" L x 52" X 66" H. Sand gravel mix is assumed for backfill up to 30". This cost estimate scenario is for cost of the tank and pad only and does not include estimate for pumps, pipe, or connecting fittings.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 430 - Irrigation Pipeline; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 533 - Pumping Plant; 447 - Irrigation System, Tailwater Recovery.

**Before Situation:**

Insufficient volume of water to complete an irrigation cycle at the required flow rate.

**After Situation:**

A below ground plastic tank, is used to accumulate and store water between irrigation cycles for a very small irrigation system. This allows for an improved flow rate and timing of water application. Sources of water could be a well, a domestic water system, a large roof area, a water ram , or a pump drawing water from a stream.

**Scenario Feature Measure: Volume of Tank Storage**

**Scenario Unit:** Gallon

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$4,051.40

**Scenario Cost/Unit:** \$4.05

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	8	\$341.84
Plate compactor	1915	Manually guided vibratroy plate compactor. Equipment only.	Hour	\$4.79	4	\$19.16
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	40	\$989.60
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	8	\$273.12
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	24	\$1,021.92
<b>Materials</b>						
Tank, Poly Enclosed Storage, >1,000	1075	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.61	1000	\$610.00
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$24.04	6	\$144.24
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	2	\$140.98
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54