

Practice: 500 - Obstruction Removal

Scenario: #1 - Removal and Disposal of Brush and Trees up to 6 inch Diameter

Scenario Description:

Remove and disposal of brush and trees < 6 inches in diameter by demolition, excavation or other means required for removal. Dispose of all brush and trees so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all brush and trees by removal to an approved landfill, wood chipping and or land distribution, or recycling center, burial at an approved location or burning. If burning is used, implement appropriate smoke management to protect public health and safety. Remove and dispose of brush and trees in order to apply conservation practices or facilitate the planned land use. Brush and tree removal will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment.

Before Situation:

On any land where existing obstructions interfere with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical area will be a 2.0 acre impaired area. The removal of brush and trees < 6 inch diameter will be performed with the use of equipment and hand labor. Dispose of all brush and trees from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Land Area

Scenario Unit: Acre

Scenario Typical Size: 2

Scenario Cost: \$2,431.67

Scenario Cost/Unit: \$1,215.84

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.81	8	\$294.48
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$123.10	8	\$984.80
Brush Chipper, 6" capacity	938	Brush Chipper, 6" capacity, typically 35 HP. Includes chipper and power unit. Labor not included.	Hour	\$21.88	8	\$175.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.86	8	\$198.88
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$40.66	8	\$325.28
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	8	\$197.92
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	1	\$255.27

Practice: 500 - Obstruction Removal

Scenario: #2 - Removal and Disposal of Brush and Trees over 6 inch Diameter

Scenario Description:

Remove and disposal of brush and trees > 6 inches in diameter by demolition, excavation or other means required for removal. Dispose of all brush and trees so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all brush and trees by removal to an approved landfill, wood chipping and or land distribution, or recycling center, burial at an approved location or burning. If burning is used, implement appropriate smoke management to protect public health and safety. Remove and dispose of brush and trees in order to apply conservation practices or facilitate the planned land use. Brush and tree removal will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment.

Before Situation:

On any land where existing obstructions interfere with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical area will be a 2.0 acre impaired area. The removal of brush and trees > 6 inch diameter will be performed with the use of equipment and hand labor. Dispose of all brush and trees from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Land Area

Scenario Unit: Acre

Scenario Typical Size: 2

Scenario Cost: \$4,629.00

Scenario Cost/Unit: \$2,314.50

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$184.60	12	\$2,215.20
Brush Chipper, 15" capacity	1868	Brush Chipper, 15" capacity, typically 165 HP. Includes chipper and power unit. Does not include labor.	Hour	\$64.80	12	\$777.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.81	12	\$441.72
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	12	\$409.68
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	12	\$296.88
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$40.66	12	\$487.92

Practice: 500 - Obstruction Removal

Scenario: #3 - Removal and Disposal of Fence

Scenario Description:

Remove and disposal of all existing fences by demolition, excavation or other means required for removal. Dispose of all fence materials from the site so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all materials by removal to an approved landfill, wood chipping and land distribution, or recycling center, burial at an approved location or burning. If burning is used, implement appropriate smoke management to protect public health and safety. Remove and dispose of the unwanted fence obstruction in order to apply conservation practices such as Upland Wildlife Habitat Management (645) or facilitate the planned land use. Fence removal will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment and reduce hazards to wildlife.

Before Situation:

On any land where existing fence interferes with planned land use development, public safety, wildlife movement and habitat, or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical fence will be 2640 in linear feet. The removal of the fence will be performed with the use of equipment and hand labor. Dispose of all debris from the fence removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape such as Upland Wildlife Habitat Management (645).

Scenario Feature Measure: Length of Fence

Scenario Unit: Linear Feet

Scenario Typical Size: 2,640

Scenario Cost: \$2,838.07

Scenario Cost/Unit: \$1.08

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.81	20	\$736.20
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	20	\$854.60
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.86	20	\$497.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	20	\$494.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	1	\$255.27

Practice: 500 - Obstruction Removal

Scenario: #4 - Removal and Disposal of Rock and or Boulders

Scenario Description:

Remove and disposal of rock and or boulders by drilling, blasting, demolition, excavation or other means required for removal. Dispose of all rocks and or boulders so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all rock and or boulders by removal to an approved location, or reuse location. Remove and dispose all rock and or boulders in order to apply conservation practices or facilitate the planned land use. Rocks and or boulders will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment.

Before Situation:

On any land where existing obstructions interfere with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical area will be a 20 acre impaired area. The removal of rock and or boulders will be performed by drilling, blasting, demolition, excavation or other means required for removal with the use of heavy equipment and hand labor. Dispose of all rocks and boulders from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Area

Scenario Unit: Acre

Scenario Typical Size: 20

Scenario Cost: \$66,007.20

Scenario Cost/Unit: \$3,300.36

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$55.45	240	\$13,308.00
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$120.04	240	\$28,809.60
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$40.66	240	\$9,758.40
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	240	\$5,937.60
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	240	\$8,193.60

Practice: 500 - Obstruction Removal

Scenario: #5 - Removal and Disposal of Steel and or Concrete Structures

Scenario Description:

Remove and disposal of steel and or concrete structures by demolition, excavation or other means required for removal. Dispose of all steel and or concrete structures so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all steel and or concrete structures by removal to an approved location, or reuse location. Remove and dispose all steel and or concrete structures in order to apply conservation practices or facilitate the planned land use. Steel and or concrete structure removal will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment.

Before Situation:

On any land where existing obstructions interfere with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical area will be a 2000 square feet of impaired land. The removal of steel and or concrete structures will be performed by demolition, excavation or other means required for removal with the use of heavy equipment and hand labor. Dispose of all steel and or concrete structures from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Land Area

Scenario Unit: Square Feet

Scenario Typical Size: 2,000

Scenario Cost: \$29,416.32

Scenario Cost/Unit: \$14.71

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$184.60	64	\$11,814.40
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$55.45	64	\$3,548.80
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$120.04	64	\$7,682.56
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$40.66	64	\$2,602.24
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	64	\$1,583.36
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	64	\$2,184.96

Practice: 500 - Obstruction Removal

Scenario: #6 - Removal and Disposal of Wood Structures

Scenario Description:

Remove and disposal of wood structures by demolition, excavation or other means required for removal. Dispose of all wood structures so that it does not impede subsequent work or cause onsite or offsite damage. Dispose of all wood structures by removal to an approved location, landfill, or reuse location. Remove and dispose all wood structures in order to apply conservation practices or facilitate the planned land use. Wood structure removal will address the resource concerns of the prevention or hindrance to the installation of conservation practices or present a hazard to their use and enjoyment.

Before Situation:

On any land where existing obstructions interfere with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The typical area will be a 2000 square feet of impaired land. The removal of wood structures will be performed by demolition, excavation or other means required for removal with the use of heavy equipment and hand labor. Dispose of all wood structures from the obstruction removal so that it does not impede subsequent work or cause onsite or offsite damage. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Land Area

Scenario Unit: Square Feet

Scenario Typical Size: 2,000

Scenario Cost: \$14,708.16

Scenario Cost/Unit: \$7.35

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$184.60	32	\$5,907.20
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$55.45	32	\$1,774.40
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$120.04	32	\$3,841.28
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	32	\$791.68
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$40.66	32	\$1,301.12
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	32	\$1,092.48

Practice: 500 - Obstruction Removal

Scenario: #7 - Rock Excavation

Scenario Description:

Drilling, blasting, excavation and removal of "competent" (non-rippable) rock. Rock is excavated so that it does not impede the installation of a conservation practice. Excavated rock is hauled to an approved staging area for reuse or disposal area. Rock excavation is necessary to install a conservation practices or to facilitate the planned land use. Resource concerns is the prevention and/or hindrance of installing a conservation practices or removal of a safety hazard.

Before Situation:

On any land where "competent rock" interferes with planned land use development, public safety or infrastructure. The site may be abandoned mine lands, construction sites, recreation areas, farms, ranches, and areas affected by natural disasters. This is not intended for the removal of obstructions from aquatic environments.

After Situation:

The excavation of "compentent" (non-rippable) rock will be performed by drilling, blasting, excavation, demolition, or other means required for removal with the use of heavy equipment. Rock shall be removed from the sites so that it does not impede in the subsequent installation of conservation practices or cause a safety hazard. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. Refer to NRCS Conservation Practice Standard 342, Critical Area Planting for seedbed preparation, seeding, fertilizing, and mulching requirements. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape.

Scenario Feature Measure: Cubic Yards of Rock to be Excavated

Scenario Unit: Cubic Yard

Scenario Typical Size: 200

Scenario Cost: \$8,099.21

Scenario Cost/Unit: \$40.50

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$120.04	15	\$1,800.60
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$4.20	200	\$840.00
Drilling & Blasting Rock, Bulk with blasting mats	1397	Bulk drilling & Blasting of rock or boulders in locations requiring the use of blasting mats (Min. 175 CY, Max 1500 CY). Includes all equipment, labor and supplies to complete the blast.	Cubic Yard	\$17.71	200	\$3,542.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	15	\$638.70
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	15	\$512.10
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	3	\$765.81

Practice: 500 - Obstruction Removal

Scenario: #8 - Concrete Slab Removal

Scenario Description:

Cutting, demolition, excavation and removal of concrete slab. Concrete slab is demolished and removed so that it does not impede the installation of a conservation practice. Excavated concrete rubble is hauled to an approved disposal area. Concrete slab demolition and removal is necessary to install a conservation practices or to facilitate the planned land use. Resource concerns is the prevention and/or hindrance of installing a conservation practices or removal of a safety hazard.

Before Situation:

On any land where an existing concrete slab interferes with planned land use development, public safety or infrastructure. The site may be an existing heavy use area (barnyard), waste storage facility, building foundation, etc.

After Situation:

The demolition and removal of a concrete slab will be performed by cutting the concrete with a diamond saw, breaking and removing the concrete with an excavator, removing the concrete rubble from the construction site with a skidsteer load and hauling the rubble off site with a dump truck. Concrete slab shall be removed from the sites so that it does not impede in the subsequent installation of conservation practices or cause a safety hazard. Revegetate or otherwise protect from erosion disturbed areas as soon as possible. The practice is to improve site conditions in order to apply conservation practices or facilitate better use of the landscape. Other associated practices are 313 - Waste Storage Facility, 561 - Heavy Use Area Protection, 634 - Waste Transfer, 533 - Pumping Plant, 558 - Roof Runoff Structure, etc.

Scenario Feature Measure: Square Feet of Concrete Slab to be Removed

Scenario Unit: Square Foot

Scenario Typical Size: 750

Scenario Cost: \$2,747.04

Scenario Cost/Unit: \$3.66

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$42.73	5	\$213.65
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$112.94	5	\$564.70
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$95.88	5	\$479.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	3	\$74.22
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$34.14	10	\$341.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.58	1	\$42.58
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.86	5	\$124.30
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$70.49	2	\$140.98
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	3	\$765.81