

Practice: 575 - Animal Trail or Walkway**Scenario: #1 - Natural Trail or Walkway****Scenario Description:**

Layout and construct a trail or walkway of natural surfacing to facilitate animal movement, to provide or improve access to forage, water, working/handling facilities, and/or shelter. Improve grazing efficiency and distribution, and/or protect ecologically sensitive, erosive and/or potentially erosive sites and address soil erosion and water quality resource concerns. Costs include excavation, shaping, grading, and all equipment, labor and incidental materials necessary to install the practices.

Before Situation:

On farmstead area and pastureland and rangeland areas where control of animal movement is needed and needing to address soil erosion and water quality resource concerns.

After Situation:

The typical trail or walkway will be a 12 foot wide 300 foot long, 3600 square foot lane. All excavation, grading and shaping necessary to provide a smooth permanent travel surface for livestock. No surface materials are included with this practice..Consider the adequacy of natural surfacing. If the lane is vegetated and requires planting, the vegetation shall be planted according to Critical Area Planting, Code 342. Where vegetation is not practical, Heavy Use Area Protection, Code 561, shall be used to provide adequate surface protection. Stream Crossing, Code 578, will be used when the trail or lane crosses streams or shallow water areas. Consider the use of water bars or culverts to control and direct water flow, use Access Road, Code 560. Diversion, Code 362, may also be beneficial. Fencing, Code 382, will be used when needed to control animal movement.

Scenario Feature Measure: Area of Lane or Trail

Scenario Unit: Square Foot

Scenario Typical Size: 3,600

Scenario Cost: \$1,578.28

Scenario Cost/Unit: \$0.44

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$4.25	133	\$565.25
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.29	133	\$304.57
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.74	8	\$197.92
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$255.27	2	\$510.54