

**Practice: 578 - Stream Crossing**

**Scenario: #1 - Culvert Installation, >30 inch diameter**

**Scenario Description:**

Install a new culvert greater than 30" in diameter. HDPE and CMP are acceptable materials under this scenario. For culverts less than 30" use Practice Standard 587 Structure for Water Control. Work includes dewatering, site preparation and removing any old crossing, acquiring and installing culvert pipe with gravel bedding and fill (compacted), and building headwalls. If a different travel surface is needed, refer to another appropriate standard for the surfacing. 36 inch Culvert installation with <75 cy of fill needed and < 2 yds rock riprap for headwalls. Pipe is 40 feet long. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows and culverts less than 30" in diameter.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure: Culvert**

**Scenario Unit: Inch-Foot**

**Scenario Typical Size: 1,440**

**Scenario Cost: \$5,185.79**

**Scenario Cost/Unit: \$3.60**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.75	3	\$17.25
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$117.15	10	\$1,171.50
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	10	\$336.90
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	50	\$1,786.50
Pipe, HDPE, CPT, Double Wall, Soil Tight, 36"	1248	Pipe, Corrugated HDPE Double Wall, 36" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$36.03	40	\$1,441.20
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	2	\$169.80
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

**Practice: 578 - Stream Crossing**

**Scenario: #2 - Low Water Crossing, Riprap**

**Scenario Description:**

Stabilize the bottom and slope of a stream channel using rock riprap or cast in place concrete. This scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with rock riprap or cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks or concrete. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Cubic Yards of Riprap Installed (In Place, Not Loose)

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 16

**Scenario Cost:** \$1,897.61

**Scenario Cost/Unit:** \$118.60

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	16	\$37.76
<b>Materials</b>						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	16	\$1,358.40
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

**Practice: 578 - Stream Crossing**

**Scenario: #3 - Low water crossing using prefabricated products**

**Scenario Description:**

To install a stable crossing medium on channel bottom and approaches. Medium includes but not limited to precast concrete blocks, geocells, pavers, and gabions. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** low water crossing

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 420

**Scenario Cost:** \$4,937.79

**Scenario Cost/Unit:** \$11.76

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	18	\$33.30
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$99.46	8	\$795.68
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	40	\$979.20
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	8	\$269.52
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	18	\$643.14
GeoCell, 4"	1054	Precast Manhole with base and top delivered. 4' diameter x 4' depth. Materials only.	Square Yard	\$30.08	50	\$1,504.00
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	6	\$211.50
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

**Practice: 578 - Stream Crossing**

**Scenario: #4 - Low Water Crossing, River Rock**

**Scenario Description:**

Stabilize the bottom and slope of a stream channel using natural river rock to achieve a more natural low water crossing. This scenario includes site preparation, dewatering, acquiring and installing geotextile with river rock on channel bottom and approaches. Final travel surface shall be the river rocks. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Cubic Yards of River Rock Installed (In Place, Not Loose)

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 16

**Scenario Cost:** \$1,914.45

**Scenario Cost/Unit:** \$119.65

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.51	47	\$117.97
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$117.15	4	\$468.60
Clearing and Grubbing	40	Clearing and Grubbing, includes materials, equipment and labor	Acre	\$316.37	0.1	\$31.64
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	4	\$134.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
<b>Materials</b>						
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$29.97	24	\$719.28
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

**Practice: 578 - Stream Crossing**

**Scenario: #5 - Bridge with a span of less than or equal to 14 feet**

**Scenario Description:**

Install a bridge to allow stream flows to cross under access road or animal trail. Bridge opening determined by sizing for storm event dictated in standard. Scenario includes dewatering, abutments, girders, decking. Work consists of site preparation, dewatering, acquiring and installing abutments, girders, decking with necessary hardware, backfilling abutments, and armoring with geotextile and riprap. Riprap and geotextile are used to stabilize and protect abutments as needed. Scenario based on cast in place concrete abutments, steel girders, and timber deck. Travel surface shall be wooden deck surface. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Span is less than 14 feet. Load is H-20. Width is 14 feet including curbs. Abutments are <= 6 feet. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** square footage of bridge deck

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 252

**Scenario Cost:** \$18,268.26

**Scenario Cost/Unit:** \$72.49

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	75	\$138.75
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$99.46	8	\$795.68
Water management, Flooding & dewatering	969	Includes equipment, power unit and labor costs.	Acre Foot	\$232.61	15	\$3,489.15
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	8	\$269.52
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	80	\$3,159.20
<b>Materials</b>						
Steel, structural steel members	1779	Structural steel, includes materials and fabrication.	Pound	\$1.04	4200	\$4,368.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	20	\$1,698.00
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	20	\$714.60
Dimension Lumber, untreated	1045	Untreated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners.	Board Foot	\$0.75	2000	\$1,500.00
Block, pre-cast concrete, modular	1496	Pre-cast concrete blocks, typically 2ft x 2ft x 6ft, includes installation and delivery.	Cubic Yard	\$104.04	18	\$1,872.72
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

**Practice: 578 - Stream Crossing**

**Scenario: #6 - Bridge with cast in place abutments, span > 14 feet**

**Scenario Description:**

Install a bridge to allow stream flows to cross under access road or animal trail. Bridge opening determined by sizing for storm event dictated in standard. Scenario includes dewatering, abutments, girders, decking. Work consists of site preparation, dewatering, acquiring and installing abutments, girders, decking with necessary hardware, backfilling abutments, and armoring with geotextile and riprap. Riprap and geotextile are used to stabilize and protect abutments as needed. Scenario based on cast in place concrete abutments, steel girders, and timber deck. Travel surface shall be wooden deck surface. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Span is greater than 14 feet. Load is H-20. Width is 15 feet including curbs. Abutment height as needed from design. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Linear feet of bridge deck

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 30

**Scenario Cost:** \$73,585.50

**Scenario Cost/Unit:** \$2,452.85

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.52	40	\$2,300.80
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$499.74	32	\$15,991.68
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.33	40	\$1,773.20
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	60	\$11,750.40
Truck, Concrete Pump	1211	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equi	Hour	\$192.58	8	\$1,540.64
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	40	\$4,981.60
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$101.60	120	\$12,192.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	140	\$4,716.60

**Labor**

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	40	\$1,579.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	40	\$1,632.80

**Materials**

Epoxy anchor	1599	Galvanized bolts anchored into concrete or stone using epoxy adhesive. Includes materials and labor to drill and install.	Each	\$18.73	12	\$224.76
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.85	2500	\$2,125.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	40	\$3,396.00
Galvanized Bolts, large	2166	5/8" x 12" galvanized timber bolts. Materials only.	Each	\$4.51	24	\$108.24
Steel, structural steel members	1779	Structural steel, includes materials and fabrication.	Pound	\$1.04	5360	\$5,574.40
Pipe, PE, 4", DR 9, perforated	2140	Materials: -4" - Perforated PE- 160 psi - ASTM D3035 DR 9	Foot	\$11.68	60	\$700.80

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	2	\$525.28
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	2	\$1,002.90

**Practice: 578 - Stream Crossing**

**Scenario: #7 - Bridge with precast abutments, span > 14 feet**

**Scenario Description:**

Install a bridge to allow stream flows to cross under access road or animal trail. Bridge opening determined by sizing for storm event dictated in standard. Scenario includes dewatering, abutments, girders, decking. Work consists of site preparation, dewatering, acquiring and installing abutments, girders, decking with necessary hardware, backfilling abutments, and armoring with geotextile and riprap. Riprap and geotextile are used to stabilize and protect abutments as needed. Scenario based on precast concrete abutments, steel girders, and timber deck. Travel surface shall be wooden deck surface. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Span is greater than 14 feet. Load is H-20. Width is 15 feet including curbs. Abutment height as needed from design. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Linear feet of bridge deck

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 30

**Scenario Cost:** \$58,306.38

**Scenario Cost/Unit:** \$1,943.55

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	40	\$4,981.60
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.33	40	\$1,773.20
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	60	\$11,750.40
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.52	40	\$2,300.80
<b>Labor</b>						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$101.60	120	\$12,192.00
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	40	\$1,579.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	40	\$1,632.80
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	140	\$4,716.60
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80

**Materials**

**Materials**

Footings, concrete, precast	1836	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Includes materials only.	Foot	\$56.33	40	\$2,253.20
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.85	2500	\$2,125.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	40	\$3,396.00
Steel, structural steel members	1779	Structural steel, includes materials and fabrication.	Pound	\$1.04	5360	\$5,574.40
Pipe, PE, 4", DR 9, perforated	2140	Materials: -4" - Perforated PE- 160 psi - ASTM D3035 DR 9	Foot	\$11.68	60	\$700.80
Epoxy anchor	1599	Galvanized bolts anchored into concrete or stone using epoxy adhesive. Includes materials and labor to drill and install.	Each	\$18.73	12	\$224.76
Galvanized Bolts, large	2166	5/8" x 12" galvanized timber bolts. Materials only.	Each	\$4.51	24	\$108.24

**Mobilization**

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	2	\$1,002.90
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	2	\$525.28

**Practice: 578 - Stream Crossing**

**Scenario: #8 - Bridge, Prefabricated for Stream Crossing**

**Scenario Description:**

Install a bridge to allow stream flows to cross under access road or animal trail. Bridge opening determined by sizing for storm event dictated in standard. Scenario includes dewatering, abutments, girders, decking installed as a prefabricated unit. Work consists of site preparation, dewatering, acquiring and installing the prefabricated unit with necessary hardware, backfilling abutments, and armoring with geotextile and riprap. Riprap and geotextile are used to stabilize and protect abutments as needed. Scenario based on prefabricated bridge structure. Travel surface shall be part of the prefabricated bridge structure. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Load is H-20. Width is 15 feet including curbs. Abutment height as needed from design. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Linear feet of bridge deck

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 30

**Scenario Cost:** \$72,793.37

**Scenario Cost/Unit:** \$2,426.45

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	10	\$1,245.40
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$499.74	18	\$8,995.32
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.52	40	\$2,300.80
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	20	\$3,916.80
Water management, Flooding & dewatering	969	Includes equipment, power unit and labor costs.	Acre Foot	\$232.61	50	\$11,630.50
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	80	\$2,695.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	20	\$816.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$101.60	80	\$8,128.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80

**Labor**

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	34	\$1,342.66
---------------	-----	---	------	---------	----	------------

**Materials**

Bridge, steel or concrete, pre-Manufactured Bridge	2193	A premanufactured steel or precast prestressed concrete bridge rated for an HS 25 highway loading. Typical width is 14', length is variable. Includes railing system. Includes materials and shipping only.	Square Foot	\$63.04	450	\$28,368.00
Painting, steel surface, Impermeable	2165	Painting of steel surface with an impermeable coating. Includes materials and application	Square Foot	\$0.89	1260	\$1,121.40

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

**Practice: 578 - Stream Crossing**

**Scenario: #9 - Stream Simulation Culvert, with Headwalls**

**Scenario Description:**

Install a stream simulation culvert with a headwall where a particular culvert geometry is needed even though aquatic organism passage may not be the primary concern. For culverts less than 30" use Practice Standard 587 Structure for Water Control. Work includes dewatering, site preparation and removing any old crossing, acquiring and installing culvert pipe with gravel bedding and fill (compacted), and building headwalls. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Pipe is 20 feet long and headwalls are included. Typical arch size may be 10' X 5'3" X 20' arch with 2'X3' precast footings Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows and culverts less than 30" in diameter.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Length of Multi-plate arch or box

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 20

**Scenario Cost:** \$50,363.04

**Scenario Cost/Unit:** \$2,518.15

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.33	40	\$1,773.20
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	40	\$4,981.60
Water management, Flooding & dewatering	969	Includes equipment, power unit and labor costs.	Acre Foot	\$232.61	25	\$5,815.25
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	60	\$11,750.40
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.51	100	\$251.00
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	40	\$1,579.60
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	100	\$3,369.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	40	\$1,632.80
<b>Materials</b>						
Culvert, Multi-Plate arch	1979	Multi-plate arch culvert, typically 7 Gauge corrugated plate. Includes metal arch materials only, does not include footings.	Pound	\$1.40	8000	\$11,200.00

**Materials**

Geocell, 6"	1842	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$37.20	45	\$1,674.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$29.97	45	\$1,348.65
Footing, concrete, precast	1836	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Includes materials only.	Foot	\$56.33	40	\$2,253.20

**Mobilization**

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	2	\$1,002.90
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

**Practice: 578 - Stream Crossing**

**Scenario: #10 - Stream Simulation Culvert, without Headwalls**

**Scenario Description:**

Install a stream simulation culvert without a headwall where a particular culvert geometry is needed even though aquatic organism passage may not be the primary concern. For culverts less than 30" use Practice Standard 587 Structure for Water Control. Work includes dewatering, site preparation and removing any old crossing, acquiring and installing culvert pipe with gravel bedding and fill (compacted). If a different travel surface is needed, refer to another appropriate standard for the surfacing. Pipe is 40 feet long and therefore headwalls are not included. Typical arch size may be 10' X 5'3" X 40' arch with 2'X3' precast footings Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows and culverts less than 30" in diameter.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Length of Multi-plate arch or box

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 40

**Scenario Cost:** \$59,389.89

**Scenario Cost/Unit:** \$1,484.75

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	40	\$4,981.60
Water management, Flooding & dewatering	969	Includes equipment, power unit and labor costs.	Acre Foot	\$232.61	25	\$5,815.25
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.33	40	\$1,773.20
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	60	\$11,750.40
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.51	200	\$502.00
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	40	\$1,579.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	40	\$1,632.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	100	\$3,369.00
<b>Materials</b>						
Culvert, Multi-Plate arch	1979	Multi-plate arch culvert, typically 7 Gauge corrugated plate. Includes metal arch materials only, does not include footings.	Pound	\$1.40	10500	\$14,700.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$29.97	90	\$2,697.30

**Materials**

Geocell, 6"	1842	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$37.20	90	\$3,348.00
Footing, concrete, precast	1836	Precast spread footing with stemwall, T-shaped, with channel built to accept arched culvert leg. Includes materials only.	Foot	\$56.33	80	\$4,506.40

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	2	\$1,002.90

**Practice: 578 - Stream Crossing**

**Scenario: #11 - Concrete Box Culvert**

**Scenario Description:**

Install a concrete box culvert where a particular culvert geometry is needed even though aquatic organism passage may not be the primary concern. For culverts less than 30" use Practice Standard 587 Structure for Water Control. Work includes dewatering, site preparation and removing any old crossing, acquiring and installing concrete box culvert with gravel bedding and fill (compacted). If a different travel surface is needed, refer to another appropriate standard for the surfacing. Concrete box culvert is a 6' by 8' box and is 20 feet long. Headwalls are not included. Typical concrete box culvert size is 6' by 8' by 20'. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows and culverts less than 30" in diameter.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Length of concrete box culvert

**Scenario Unit:** Linear Foot

**Scenario Typical Size:** 20

**Scenario Cost:** \$43,838.44

**Scenario Cost/Unit:** \$2,191.92

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, dump, 18 CY	1400	Dump truck for moving bulk material. Typically capacity is 25 ton or 18 cubic yards. Includes equipment only.	Hour	\$124.54	40	\$4,981.60
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.51	100	\$251.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$195.84	60	\$11,750.40
Water management, Flooding & dewatering	969	Includes equipment, power unit and labor costs.	Acre Foot	\$232.61	25	\$5,815.25
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.33	40	\$1,773.20
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	60	\$1,468.80
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$39.49	40	\$1,579.60
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	100	\$3,369.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	40	\$1,632.80
<b>Materials</b>						
Culvert, box, 6' x 8'	2175	Precast concrete box culvert, 6'X8'. Typically in 4' sections. Materials only.	Foot	\$346.43	20	\$6,928.60

**Materials**

Geocell, 6"	1842	6-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$37.20	45	\$1,674.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$29.97	45	\$1,348.65

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	2	\$1,002.90

**Practice: 578 - Stream Crossing**

**Scenario: #12 - Bridge, Light Weight Timber**

**Scenario Description:**

Light Weight Timber bridge is constructed of 6" x 10" timbers side by side bolted together by ASTM A307 Bolts to provide a deck for animal traffic and light weight equipment such as ATV's. Deck is fabricated into 3 - 4'x20' panels which are moved into position by an excavator. Bridge is placed across a narrow incised stream where installing a ford or other type of crossing is not practical. Bridge deck is mounted on precast concrete blocks which are buried 1/2 to 3/4 into the ground. Approaches to both ends of the bridge are graded to meet the contour of the existing or proposed animal trail. Bridge opening determined by sizing for storm event dictated in standard. Streambanks and bed at crossing location are generally stable. Work consists of furnishing and installing four precast blocks to mount bridge, furnishing 24 - 6" x 10" timbers and assembling the bridge on site, necessary hardware, and lifting bridge panels into place by hydraulic excavator. Span is less than 14 feet. Bridge is intended for cattle passage and not for heavy weight equipment. Bridge width is 12 feet. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Access to pasture is not possible without causing excessive erosion and other water quality water concerns.

**After Situation:**

Access and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for light weight equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Area of Bridge Deck in Square Feet (12' wide x 20' long)

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 240

**Scenario Cost:** \$7,783.90

**Scenario Cost/Unit:** \$32.43

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$117.15	8	\$937.20
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	16	\$391.68
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	8	\$269.52
<b>Materials</b>						
Bolt, All Thread Rod, ASTM A307, 1" Dia. x 4'	2528	Hot Dipped Galvanized All Thread Rod, ASTM A307, 1" Dia. X 4' Long with two - nuts and flat washers. Includes materials and shipping only.	Each	\$100.98	18	\$1,817.64
Lumber, planks, posts and timbers, untreated	1623	Untreated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	\$1.46	2400	\$3,504.00
Block, pre-cast concrete, modular	1496	Pre-cast concrete blocks, typically 2ft x 2ft x 6ft , includes installation and delivery.	Cubic Yard	\$104.04	3.6	\$374.54
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.52	2	\$145.04