

Practice: 620 - Underground Outlet**Scenario: #1 - 4 inch Corrugated Plastic Pipe (CPP) only****Scenario Description:**

Install 75 feet of 4" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated 52" deep and 24" wide by hydraulic track excavator. Costs include 4" CPT or PVC pipe, trench excavation, pipe bedding, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with roof runoff practices.

Before Situation:

Roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

"Clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342) and Roof Runoff Structure (558).

Scenario Feature Measure: Length of Conduit

Scenario Unit: Foot

Scenario Typical Size: 75

Scenario Cost: \$1,008.61

Scenario Cost/Unit: \$13.45

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	20	\$41.80
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	44	\$103.84
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Materials						
Pipe, PVC, 4", SDR 35	992	Materials: - 4" - PVC - SDR 35 - ASTM D3034	Foot	\$1.71	10	\$17.10
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Pipe, HDPE, 4", PCPT, Single Wall	1270	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 4" diameter - ASTM F405. Material cost only.	Foot	\$0.46	65	\$29.90
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	4	\$141.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	0.25	\$21.23
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #2 - 6 inch Corrugated Plastic Pipe (CPP) only****Scenario Description:**

Install 150 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated approximately 54" deep and 24" wide by excavator. Costs include 6" HDPE corrugated single wall plastic tubing, trench excavation, trench backfill and compaction, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit:** Feet**Scenario Typical Size:** 150**Scenario Cost:** \$1,649.19**Scenario Cost/Unit:** \$10.99**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	89	\$164.65
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	39	\$81.51
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.82	10	\$38.20
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.12	140	\$156.80
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	11	\$387.75
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #3 - 8 inch Corrugated Plastic Pipe (CPP) only****Scenario Description:**

Install 150 feet of 8" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated approximately 54" deep and 24" wide by excavator. Costs include 8" HDPE corrugated single wall plastic tubing, trench excavation, trench backfill and compaction, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit: Feet****Scenario Typical Size: 150****Scenario Cost: \$2,041.52****Scenario Cost/Unit: \$13.61****Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	33	\$68.97
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	83	\$153.55
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 8" diameter	2530	Mild steel prong type rodent guard, 8 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$9.55	1	\$9.55
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	17	\$599.25
Pipe, HDPE, 8", PCPT, Single Wall	1272	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 8" diameter - ASTM F667. Material cost only.	Foot	\$2.00	140	\$280.00
Pipe, PVC, 8", SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$6.86	10	\$68.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #4 - 10 inch High Density Polyethylene (HDPE) Pipe only****Scenario Description:**

Install 150 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit:** Feet**Scenario Typical Size:** 150**Scenario Cost:** \$2,745.47**Scenario Cost/Unit:** \$18.30**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	78	\$184.08
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	28	\$58.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	22	\$775.50
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.68	150	\$852.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 10" diameter	2531	Mild steel prong type rodent guard, 10 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$13.77	1	\$13.77
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #5 - 4 to 6 inch Corrugated Plastic Pipe (CPP) with Riser****Scenario Description:**

Install 150 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated approximately 54" deep and 24" wide by excavator. Costs include 6" HDPE corrugated single wall plastic tubing, 8" Perforated PVC Riser Inlet, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$1,861.97

Scenario Cost/Unit: \$12.41

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	38	\$79.42
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	88	\$162.80
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Materials						
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Inlet, riser, 8"	1262	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 8" diameter. Materials only.	Each	\$108.36	2	\$216.72
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.12	140	\$156.80
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.82	10	\$38.20
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	11	\$387.75
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90

Mobilization

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
--------------------------------	------	---	------	----------	---	----------

Practice: 620 - Underground Outlet**Scenario: #6 - 4 to 6 inch Polyvinyl Chloride (PVC) Pipe with Catch Basin upto 50 feet in length****Scenario Description:**

Install 50 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated 52" deep and 24" wide by hydraulic track excavator. Costs include 6" SDR-35 pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways, roof runoff structures, or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), Roof Runoff Structure (558), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 50

Scenario Cost: \$1,900.38

Scenario Cost/Unit: \$38.01

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	11	\$22.99
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.75	6	\$34.50
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	25	\$46.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Materials						
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.82	50	\$191.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #7 - 4 to 6 inch Polyvinyl Chloride (PVC)Pipe with Catch Basin over 50 feet in length****Scenario Description:**

Install 150 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated 52" deep and 24" wide by hydraulic track excavator. Costs include 6" SDR-35 pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways, roof runoff structures, or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), Roof Runoff Structure (558), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$2,432.11

Scenario Cost/Unit: \$16.21

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	33	\$68.97
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	50	\$92.50
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.75	16	\$92.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Materials						
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.82	150	\$573.00
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #8 - 8 to 12 inch High Density Polyethylene (HDPE) Pipe with Riser****Scenario Description:**

Install 150 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, 12" Perforated PVC Riser Inlet, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit:** Feet**Scenario Typical Size:** 150**Scenario Cost:** \$3,039.33**Scenario Cost/Unit:** \$20.26**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	28	\$58.52
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	78	\$184.08
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.68	150	\$852.00
Inlet, riser, 10"	1263	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 10" diameter. Materials only.	Each	\$146.93	2	\$293.86
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	22	\$775.50
Rat Guard, 10" diameter	2531	Mild steel prong type rodent guard, 10 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$13.77	1	\$13.77

Mobilization

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
--------------------------------	------	---	------	----------	---	----------

Practice: 620 - Underground Outlet**Scenario: #9 - 8 to 12 inch High Density Polyethylene (HDPE) Pipe with Catch Basin upto 50 feet in length****Scenario Description:**

Install 50 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit:** Feet**Scenario Typical Size:** 50**Scenario Cost:** \$2,313.62**Scenario Cost/Unit:** \$46.27**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	32	\$75.52
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	12	\$25.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	2	\$48.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
Materials						
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.68	50	\$284.00
Rat Guard, 10" diameter	2531	Mild steel prong type rodent guard, 10 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$13.77	1	\$13.77
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	9	\$317.25
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #10 - 8 to 12 inch High Density Polyethylene (HDPE) Pipe with Catch Basin over 50 feet in length****Scenario Description:**

Install 150 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$3,733.39

Scenario Cost/Unit: \$24.89

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	36	\$75.24
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	97	\$228.92
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.68	150	\$852.00
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 10" diameter	2531	Mild steel prong type rodent guard, 10 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$13.77	1	\$13.77
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	26	\$916.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64

Practice: 620 - Underground Outlet**Scenario: #11 - 14 to 18 inch High Density Polyethylene (HDPE) Pipe with Catch Basin****Scenario Description:**

Install 150 feet of 18" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 66" deep x 39" wide. Costs include 18" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit**Scenario Unit:** Feet**Scenario Typical Size:** 150**Scenario Cost:** \$5,045.52**Scenario Cost/Unit:** \$33.64**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	171	\$316.35
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	72	\$150.48
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 18" diameter	2534	Mild steel prong type rodent guard, 18 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$70.44	1	\$70.44
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	26	\$928.98
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$11.29	150	\$1,693.50

Mobilization

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45
-------------------------------	------	--	------	----------	---	----------

Practice: 620 - Underground Outlet**Scenario: #12 - 20 to 24 inch High Density Polyethylene (HDPE) Pipe with Catch Basin****Scenario Description:**

Install 150 feet of 24" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 72" x 48" wide. Costs include 24" HDPE pipe, Precast concrete drop inlet with steel grate, 24" HDPE pipe, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. Practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$7,129.52

Scenario Cost/Unit: \$47.53

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	134	\$247.90
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	89	\$186.01
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.51	89	\$223.39
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	4	\$97.92
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2.5	\$102.05
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 24"	1246	Pipe, Corrugated HDPE Double Wall, 24" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$18.98	150	\$2,847.00
Rat Guard, 24" diameter	2536	Mild steel prong type rodent guard, 24 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$98.66	1	\$98.66
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	38	\$1,357.74
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36

Materials

Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
---------------------------------	------	--	-------------	---------	----	----------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

Practice: 620 - Underground Outlet**Scenario: #13 - 26 to 30 inch High Density Polyethylene (HDPE) Pipe with Catch Basin****Scenario Description:**

Install 200 feet of 30" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 78" deep x 56" wide. Costs include 30" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 200

Scenario Cost: \$12,361.32

Scenario Cost/Unit: \$61.81

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	122	\$254.98
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	226	\$418.10
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.51	122	\$306.22
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	3	\$122.46
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	5	\$122.40
Materials						
Manhole, 4' x 4'	1053	Precast Manhole with base and top delivered. 4' diameter x 4' depth. Materials only.	Each	\$1,726.37	1	\$1,726.37
Rat Guard, 30" diameter	2537	Mild steel prong type rodent guard, 30 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$119.59	1	\$119.59
Pipe, HDPE, CPT, Double Wall, Soil Tight, 30"	1247	Pipe, Corrugated HDPE Double Wall, 30" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$27.72	200	\$5,544.00
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	67	\$2,393.91
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	3	\$254.70

Materials

Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
---------------------------------	------	--	-------------	---------	----	----------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

Practice: 620 - Underground Outlet**Scenario: #14 - Over 30 inch High Density Polyethylene (HDPE) Pipe with Catch Basin****Scenario Description:**

Install 200 feet of 36" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 84" deep x 64" wide. Costs include 36" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 200

Scenario Cost: \$16,856.22

Scenario Cost/Unit: \$84.28

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	157	\$328.13
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	275	\$508.75
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.51	157	\$394.07
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	5	\$122.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	4	\$163.28
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 36"	1248	Pipe, Corrugated HDPE Double Wall, 36" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$36.03	200	\$7,206.00
Manhole, 4' x 4'	1053	Precast Manhole with base and top delivered. 4' diameter x 4' depth. Materials only.	Each	\$1,726.37	1	\$1,726.37
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Rat Guard, 36" diameter	2538	Mild steel prong type rodent guard, 36 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$145.48	1	\$145.48
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$35.73	135	\$4,823.55

Materials

Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	4	\$339.60
-------------------------------------	----	---	------------	---------	---	----------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$501.45	1	\$501.45

Practice: 620 - Underground Outlet**Scenario: #15 - 4 to 6 inch Polyvinyl Chloride (PVC) Pipe with Catch Basin w/ Horizontal Boring****Scenario Description:**

Install 150 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated 52" deep and 24" wide by hydraulic track excavator. 50' of pipe installed under road with horizontal boring equipment. Costs include 6" SDR-35 pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, hor. boring equipment, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways, roof runoff structures, or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), Roof Runoff Structure (558), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$6,195.07

Scenario Cost/Unit: \$41.30

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.75	11	\$63.25
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	22	\$45.98
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.85	50	\$92.50
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$117.15	4	\$468.60
Horizontal Boring, > 3" diameter	1132	Includes equipment, labor and setup.	Foot	\$53.75	50	\$2,687.50
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	4	\$134.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	6	\$244.92
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	6	\$146.88
Materials						
Rat Guard, 6" diameter	2529	Mild steel prong type rodent guard, 6 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$7.64	1	\$7.64
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50

Materials

Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.82	150	\$573.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	2	\$525.28
--------------------------------	------	---	------	----------	---	----------

Practice: 620 - Underground Outlet**Scenario: #16 - 8 to 12 inch High Density Polyethylene (HDPE) Pipe with Catch Basin w/ Horizontal Boring****Scenario Description:**

Install 150 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. 50' of pipe installed under road with horizontal boring equipment. Costs include 10" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, hor. boring equipment, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways, roof runoff structures, or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 150

Scenario Cost: \$7,073.21

Scenario Cost/Unit: \$47.15

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.09	36	\$75.24
Horizontal Boring, > 3" diameter	1132	Includes equipment, labor and setup.	Foot	\$53.75	50	\$2,687.50
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$117.15	4	\$468.60
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$2.36	97	\$228.92
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.48	6	\$146.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.82	2	\$81.64
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$33.69	4	\$134.76
Materials						
Rat Guard, 10" diameter	2531	Mild steel prong type rodent guard, 10 inch diameter. Attaches to the top of outlet pipe. Includes materials and shipping only.	Each	\$13.77	1	\$13.77
Headwall, stone or concrete bag	1418	Laid up stone or concrete bag headwall for a pipe inlet. Square Foot unit is a vertical area measurement of the headwall cross-section. Includes materials, equipment and labor.	Square Foot	\$33.45	10	\$334.50
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$785.36	1	\$785.36

Materials

Pipe, HDPE, CPT, Double Wall, Soil Tight, 10"	1243	Pipe, Corrugated HDPE Double Wall, 10" diameter with soil tight joints - AASHTO M252. Material cost only.	Foot	\$5.68	150	\$852.00
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$84.90	1	\$84.90
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$35.25	26	\$916.50

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$262.64	1	\$262.64
--------------------------------	------	---	------	----------	---	----------