

**STATEMENT OF WORK**  
**Bedding (310)**  
**Florida**

**These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.**

## **DESIGN**

---

### **Deliverables**

1. Design documents that demonstrate criteria in Florida NRCS practice standard have been met and are compatible with planned and applied practices
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. Compliance with NRCS national and state utility safety policy (NEM part 503-Safety, Section 503.00 through 503.22)
  - d. List all required and/or facilitating practices
  - e. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
    - i. Florida Supplement, National Engineering Field Handbook (NEFH), Part 650, Chapter 1
    - ii. Soils and slope
    - iii. Water budget (e.g. volume, velocity, movement)
    - iv. Bed crown height, width and length
    - v. Safety Considerations (NEM Part 503 – Safety, Subpart A, 503.06 through 503.12)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits (Florida Supplement, NEFH, Part 650, Chapter 1).
3. Operation and maintenance plan.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03(b)(2) and Florida Supplement, NEFH, Part 650, Chapter 1).
5. Design modifications during installation as required.

## **INSTALLATION**

---

### **Deliverables**

1. Pre-installation conference with client.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation guidance as needed.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

**STATEMENT OF WORK  
Bedding (310)  
Florida**

**CHECK OUT**

---

**Deliverables**

1. Check out notes as specified in the Florida Supplement, NEFH, Part 650 Chapter 1
2. As-Built documentation
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities
3. Certification that the application meets NRCS standards and specifications and is in compliance with permits.
4. Progress reporting.

**REFERENCES**

---

- Florida Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Bedding – 310
- Check out notes as specified in the Florida Supplement, NEFH, Part 650 Chapter 1, Procedure for Documenting, Planning, Design, Construction, and Checkout of Engineering Conservation Practices.
- NRCS National Engineering Manual (NEM)
- NRCS National Agronomy Manual (NAM)
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook

**STATE CONTACT**

---

Jesse T. Wilson  
State Conservation Engineer  
(352) 338-9555  
jesse.wilson@fl.usda.gov