

Practice: 614 - Watering Facility**Scenario: #1 - Less than 100 gal****Scenario Description:**

A permanent watering facility for livestock and or wildlife constructed of approved materials with less than 100 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of less than 100 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Scenario Feature Measure: Permanent Drinking/Storage <100 Gallons

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$128.20

Scenario Cost/Unit: \$128.20

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.32	2	\$72.64
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	2	\$37.50
Materials						
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.90	2	\$15.80
Tank, Galvanized Steel Livestock, ≤ 75 gallon	1066	Includes tank materials and float valve	Gallon	\$2.26	1	\$2.26

Practice: 614 - Watering Facility**Scenario: #2 - Less than 100-200 gal****Scenario Description:**

A permanent watering facility for livestock and or wildlife constructed of approved materials for 100- 200 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of 100-200 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Scenario Feature Measure: Permanent Drinking/Storage 100-200 Gallons

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$273.03

Scenario Cost/Unit: \$273.03

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.32	1	\$36.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	2	\$37.50
Materials						
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.90	2	\$15.80
Tank, Galvanized, 200 gallon	278	Tank Galvanized - 200 gallon capacity	Each	\$183.41	1	\$183.41

Practice: 614 - Watering Facility**Scenario: #3 - Less than 201-400 gal****Scenario Description:**

A permanent watering facility for livestock and or wildlife constructed of approved materials for 201-400 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of 200-400 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Scenario Feature Measure: Permanent Drinking/Storage -201-400 Gallons

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$323.48

Scenario Cost/Unit: \$323.48

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.32	1	\$36.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	2	\$37.50
Materials						
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.90	2	\$15.80
Tank, Galvanized, 400 gallon	279	Tank Galvanized - 400 gallon capacity	Each	\$233.86	1	\$233.86

Practice: 614 - Watering Facility**Scenario: #4 - Less than 401-600 gal****Scenario Description:**

A permanent watering facility for livestock and or wildlife constructed of approved materials for 401-600 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of 401-600 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Scenario Feature Measure: Permanent Drinking/Storage --401-600 Gallons

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$510.44

Scenario Cost/Unit: \$510.44

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$22.91	2	\$45.82
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.32	1	\$36.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	2	\$37.50
Materials						
Tank, Galvanized Steel Livestock, > 300 - 1,000 gallon	1068	Includes tank materials and float valve	Gallon	\$0.75	500	\$375.00
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.90	2	\$15.80

Practice: 614 - Watering Facility**Scenario: #5 - Greater Than 600 gal****Scenario Description:**

A permanent watering facility for livestock and or wildlife constructed of approved materials for greater than 600 gallons of capacity that stores adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with a capacity of greater than 600 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife for storage and or direct drinking access and provides improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations or overflow from the watering facility will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Scenario Feature Measure: Permanent Drinking/Storage Greater than 600 Gallons

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$709.10

Scenario Cost/Unit: \$709.10

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$22.91	3	\$68.73
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$36.32	1	\$36.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	2	\$37.50
Materials						
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.90	2	\$15.80
Tank, Galvanized Steel Livestock, > 300 - 1,000 gallon	1068	Includes tank materials and float valve	Gallon	\$0.75	700	\$525.00
Mobilization						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been included in the component price.	Dollar	\$1.03	25	\$25.75

Practice: 614 - Watering Facility**Scenario: #11 - Storage Tank for Solar Systems****Scenario Description:**

A storage tank for a permanent watering facility for livestock and or wildlife using solar power to provide water using approved materials that stores adequate quantity and quality of water. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water and power are not available in sufficient quantities, and habitat, water quality, plant productivity and health needs to be improved.

After Situation:

A storage tank for a permanent watering facility with a capacity of 10000 gallons is installed with all tank materials, tank plumbing and float valve, to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife and provides improved plant productivity and health, water quality, and habitat. The storage tank will provide a 5 day supply of water for 100 beef cattle during times when the solar pump is nonfunctional based on weather conditions. All storage tanks are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Livestock Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Livestock Pipeline (516) as appropriate.

Scenario Feature Measure: Volume of Collection (Tank)**Scenario Unit: Gallon****Scenario Typical Size: 10,000****Scenario Cost: \$10,495.72****Scenario Cost/Unit: \$1.05****Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$356.90	4	\$1,427.60
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$65.66	1.5	\$98.49
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.75	4	\$75.00
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$23.79	1.5	\$35.69
Materials						
Tank, Fiberglass Enclosed Storage, 10,000 gallon	1919	10,000 gallon capacity enclosed fiberglass water storage tank. Includes tank anchoring materials and delivery.	Each	\$7,888.14	1	\$7,888.14
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$249.80	1	\$249.80
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been included in the component price.	Dollar	\$1.03	700	\$721.00