

**Practice: 672 - Building Envelope Improvement****Scenario: #1 - Building Envelope - Attic Insulation****Scenario Description:**

Install a minimum R-7 insulation in addition to existing attic or ceiling to reduce heat transfer. Increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

**Before Situation:**

A poultry house with an inefficient building envelope with limited attic insulation.

**After Situation:**

A more effective and efficient building envelope can be created through addition of, or increased, attic insulation. Associated practices/activities: 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

**Scenario Feature Measure:** Area of Attic Insulated

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 20,000

**Scenario Cost:** \$12,600.00

**Scenario Cost/Unit:** \$0.63

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Materials</b>						
Insulation, Fiberglass or cellulose, R-15	1196	Fiberglass or cellulose insulation R-15, includes materials, equipment and labor to install.	Square Foot	\$0.63	20000	\$12,600.00

**Practice: 672 - Building Envelope Improvement****Scenario: #2 - Building Envelope - Wall Insulation****Scenario Description:**

Enclose both sidewalls and endwalls from ceiling to floor in one of two manners: 1) metal exterior, 3.5" fiberglass batts (R-11), vapor barrier, & interior plywood or OSB sheathing, or 2) closed-cell polyurethane foam application (minimum 1" thickness (R-7) of 2.5 lbs/cu.ft. or higher density, (3.0 or higher density preferred) with a form of physical protective barrier on lower 2' (may be 6 lbs/cu.ft. or higher density 1/8" thick foam, or treated lumber). Based on a 40' x 400' poultry house.

**Before Situation:**

A poultry house with an inefficient building envelope with limited wall insulation.

**After Situation:**

A more effective and efficient building envelope can be created through addition of, or increased, insulation. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

**Scenario Feature Measure:** Square foot of wall insulated

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 4,500

**Scenario Cost:** \$6,930.00

**Scenario Cost/Unit:** \$1.54

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Materials</b>						
Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheeting barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	\$1.54	4500	\$6,930.00

**Practice: 672 - Building Envelope Improvement****Scenario: #3 - Building Envelope - Sealant****Scenario Description:**

A typical scenario is sealing the gaps between walls, gables, ceiling, etc. in a poultry house or greenhouse. Sealing is performed by a professional contractor, not merely use of spray foam from a can. The unit basis of payment in this scenario is each house based on 60' x 500' poultry house with an assumed need of sealant to seal 2400 linear feet of gap.

**Before Situation:**

An agricultural facility with an inefficient building envelope with gaps between walls, ceiling, etc. for a total of 2400 linear feet.

**After Situation:**

A more effective and efficient building envelope can be created through interior sealing of the exterior walls at the footer plate, eaves, ridge cap, and gable ends. The sealant reduces seasonal heat loss and heat gain due to infiltration which reduces the respective need for heating and cooling equipment to operate. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

**Scenario Feature Measure:** Perimeter of heated structure

**Scenario Unit:** Foot

**Scenario Typical Size:** 2,400

**Scenario Cost:** \$3,216.00

**Scenario Cost/Unit:** \$1.34

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Materials</b>						
Sealant	1150	Greenhouse and building gap sealant. Performed by a professional contractor spraying the areas with an approved sealant for poultry production facilities. Includes materials, equipment and labor to install.	Foot	\$1.34	2400	\$3,216.00

**Practice: 672 - Building Envelope Improvement****Scenario: #4 - Building Envelope - Greenhouse Screens****Scenario Description:**

The mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven strips of aluminum fiber, polyethylene, nylon or other synthetic material. The screen provides a means to better control solar heat gain and heat transfer during night or cold weather conditions to reduce energy use. Screens and similar devices may also be used to divide internal areas and allow for differentiated heating, ventilation, or cooling system operation to reduce energy use.

**Before Situation:**

Heating and cooling of an existing greenhouse, or similar structure with conditioned spaces, is inefficient due to poorly regulated heat transfer. A need to regulate an entire space for uniform conditions when some portions have differing, intermittent requirements can also reduce efficiency.

**After Situation:**

The greenhouse is fitted with a mechanically controlled energy screen installed truss-to-truss or gutter-to-gutter, with side screens as necessary, reducing heat loss in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

**Scenario Feature Measure:** Area of Screen

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 25,000

**Scenario Cost:** \$47,409.76

**Scenario Cost/Unit:** \$1.90

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.61	16	\$409.76
<b>Materials</b>						
Thermal blanket 10,001 - 50,000 square foot	1148	Thermal blanket greenhouse screens: mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven. Size Range is 10,001 to 50,000 square feet. Materials only.	Square Foot	\$1.88	25000	\$47,000.00

**Practice: 672 - Building Envelope Improvement****Scenario: #5 - Greenhouse - Insulate Unglazed Walls****Scenario Description:**

A typical scenario is the installation insulation in green house to address energy loss. The insulation can be either of the cellulose or bubble type (or equivalent). The increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

**Before Situation:**

Green house with standard glazing, plastic or polycarbonate walls and no insulation. Heating and cooling of an existing greenhouse is inefficient due to excessive heat loss.

**After Situation:**

The greenhouse is fitted with insulation installed truss-to-truss or gutter-to-gutter and/or non glazed endwalls and/or sidewalls, reducing heat loss and gain in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

**Scenario Feature Measure:** Square Feet of insulation

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 25,000

**Scenario Cost:** \$7,159.76

**Scenario Cost/Unit:** \$0.29

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.61	16	\$409.76
<b>Materials</b>						
Insulation, Greenhouse, Reflective Bubble	2410	Double bubble reflective insulation with aluminum foil on both sides. Includes materials and shipping only.	Square Foot	\$0.27	25000	\$6,750.00