

**NATURAL RESOURCES CONSERVATION SERVICE
PACIFIC ISLANDS AREA**

CONSERVATION PRACTICE SPECIFICATION

ANIMAL TRAILS AND WALKWAYS (575)

SCOPE

The work consists of construction of animal trails and walkways to the lines and grades as shown on the construction drawings and these specifications and as staked in the field.

SAFETY

Landowners or operators, sponsoring organizations, and contractors, shall be liable for damage to utilities and damage resulting from disruption of service caused by construction activities. The Natural Resources Conservation Service makes no representation on the existence or non-existence of any utilities. Absence of utilities on the drawings is not assurance that no utilities are present at the site.

It is the responsibility of the landowner or operator to determine if there are buried or overhead utilities in the vicinity of the proposed work. They should take proper procedures to insure that the utilities shall not be jeopardized and that equipment operators and others will not be injured during construction operations.

CONSTRUCTION OPERATIONS

Construction operations shall be carried out in such a manner and sequence that erosion and air and water pollution are minimized and held within legal limits.

The owner, operator, contractor or other persons will conduct all work and operations in accordance with proper safety codes for the type of construction being performed with due regards to the safety of all persons and property.

INSTALLATION

Site Preparation. Remove the vegetation along the tread width with as little soil disturbance as possible. Scatter all removed vegetation to the lower side of the trail.

All trees, shrubs, and fallen timber shall be removed for the minimum tread distance of 2.5 feet and a maximum tread distance of 5 feet on each side of the trail centerline. Stumps and exposed roots within the tread area shall be cut off, at or below ground level and, if necessary, treated to prevent re-sprouting. All protruding limbs shall be removed for a distance of at least 4 feet on each side of the trail centerline and to a height of at least 10 feet.

All other undesirable material, such as soil high in organic matter and large stones, shall be removed from the tread area of the trail.

Grading. All grading and shaping shall be to the lines, grades, and cross sections shown on the drawings and as staked in the field. Fills shall be installed in layers not over 6 inches thick.

Related Appurtenances. All bridges, culverts, swales, dips, and other drainage structures shall be installed according to the drawings.

Surfacing. The surfacing applied shall be of the type shown and as specified in the design.

WORKMANSHIP

All construction shall be performed in a workmanlike manner, and the job site shall have a neat appearance when finished.

All disturbed areas not graveled or paved will be vegetated to control erosion.

BASIS OF ACCEPTANCE

The acceptability of this practice shall be determined by inspections during and following construction to ensure compliance with all provisions of this specification and the construction drawings.