

Practice: 371 - Air Filtration and Scrubbing

Scenario: #1 - Single Pit Fan Biofilter

Scenario Description: Establishment of a biofilter used to treat the air flow from a single waste pit ventilation fan in instances where control of the exhaust from all pit ventilation fans is not needed. Adequate moisture in the wood chip media is maintained for proper growth of bacteria. For each waste pit ventilation fan servicing a waste storage facility that is identified as exhausting odorous and/or particulate laden air into the atmosphere, a separate biofilter is installed. Payment includes materials, equipment, and labor costs for installing the biofilter. A stabilized area around the biofilter is not included and must be addressed through the associated practice of Heavy Use Area Protection (561), if needed.

Before Situation: One or more pit ventilation fans of a manure storage facility on a Headquarters site are exhausting odorous and/or particulate laden air into the atmosphere.

After Situation: Air Quality resource concerns are addressed through installation of the practice by reducing odors and/or particulate matter emissions. Exhaust from a 24" waste pit ventilation fan is piped to a 16' wide by 20' long by 4' high horizontal biofilter constructed of a formed concrete bin that is filled with wood chip media, capable of handling 5,500 cubic feet per minute of airflow. The loading of odor and/or particulates into the air at the production facility is significantly reduced, resulting in a substantial improvement in air quality. Ammonia emissions are reduced approximately 60%; hydrogen sulfide about 80% and odor 60 to 80%. Associated practices include Heavy Use Area Protection (561), Amendments for Treatment of Agricultural Waste (591), Windbreak (380), Waste Storage Facility (313) and CAP-Comprehensive Air Quality Management Plan (126).

Scenario Feature Measure: Number of Biofilters Installed

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$12,546.20

Scenario Cost/Unit: \$12,546.20

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Aggregate, Wood Chips	1098	Includes materials, equipment and labor	Cubic Yard	\$21.82	24	\$523.59
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$368.92	11.3	\$4,168.80
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$237.21	10	\$2,372.08
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.16	33	\$71.17
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	8	\$171.42

Materials

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	11	\$281.28
Articulated precast concrete planking, 5 Foot Wide block	1906	Articulated precast concrete blocks with a typical thickness of 4.5 inches. Includes materials only.	Square Foot	\$5.40	320	\$1,728.00
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.92	80	\$73.32
Geotextile, non-woven, light weight	1209	Non-woven less than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only.	Square Yard	\$1.17	36	\$42.23
Micro Irrigation, surface drip tubing	1488	Tubing is installed above ground for surface drip irrigation, includes installation, and connections to the supply and flushing laterals. Tubing has emitters built in.	Foot	\$0.34	100	\$33.97
Pipe, PE, 3/4", DR 9	996	Materials: - 3/4" - PE - 160 psi - ASTM D3035 DR 9	Foot	\$0.34	50	\$16.97
Pipe, PVC, 24", SCH 40	2046	Materials: - 24" - PVC - SCH 40 - ASTM D1785	Foot	\$45.42	40	\$1,816.94

Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	0.25	\$103.47
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$160.35	1	\$160.35

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	6	\$130.25
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.88	2	\$63.76

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	1	\$169.24
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$69.48	1	\$69.48