

**Practice:** 382 - Fence

**Scenario:** #1 - Permanent Wildlife Exclusion

**Scenario Description:** Installation of a taller than normal permanent fence to prevent conflicts between humans, livestock, and wildlife species. Such a fence would exclude wildlife from areas used by livestock.

**Before Situation:** Wildlife negatively impacting sensitive areas such as riparian areas, windbreaks and shelterbelts or feed storage. Disease transmission from wildlife poses a significant health risk to domestic animals.

**After Situation:** Installation of fence reduces resource concerns associated with livestock and wildlife interaction and prevents conflicts involving threatened, endangered or sensitive species. Fence includes posts, wire, fasteners, gates, etc. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$9,468.12

**Scenario Cost/Unit:** \$7.17

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Gate, Game, 8' High X 16'	1086	16' Wide Game Gate (8' Tall). Includes materials and shipping only.	Each	\$420.04	1	\$420.04
Post, Steel T, 1.33 lbs, 10'	17	Steel Post, Studded 10' - 1.33 lb. Includes materials and shipping only.	Each	\$10.93	66	\$721.35
Post, Wood, CCA treated, 6" x 12-14'	13	Wood Post, Line/End 6" X 12-14', CCA Treated. Includes materials and shipping only.	Each	\$26.98	76	\$2,050.16
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Wire, Woven, Wildlife, 96"	6	High Tensile 12.5 gauge, 96" - 330' roll. Includes materials and shipping only.	Each	\$455.40	4	\$1,821.60

**Labor**

Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$23.59	30	\$707.56
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	70	\$1,519.62

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	21	\$150.98
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	40	\$974.69
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	30	\$642.84

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #2 - Permanent Barbed Wire Multi Strand

**Scenario Description:** Scenario is for the establishment of permanent multi strand barbed wire fence for livestock.

**Before Situation:** On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds. Fence installation conditions are for difficult sites such as poor access, steep slopes, rocky sites, dense brush, wet conditions etc.

**After Situation:** Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, brace posts, etc... Fence will be installed with wildlife friendly considerations. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$2,749.16

**Scenario Cost/Unit:** \$2.08

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$218.59
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	68	\$425.73
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	5	\$355.95

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	24	\$521.01
---------------	-----	--	------	---------	----	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	12	\$86.27
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	12	\$292.41
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	12	\$257.14

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #3 - Permanent High Tensile Electric 2-3 Strand

**Scenario Description:** Scenario is for the installation of a permanent high tensile electric fence of either 2 or 3 strands. Fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Constructed using fencing materials rather than a pre-manufactured gate.

**Before Situation:** On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, livestock access to water bodies is uncontrolled. Reduced vegetative cover increases opportunity for encroachment of noxious and invasive weeds.

**After Situation:** Installation of fence will allow for implementation of a rotational grazing plan that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. This scenario consists of installing a permanent high tensile electric fence with 2-3 wires with wooden post of 50' centers, battens between the post, single H brace assemblies, energizer, and all apputenances. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$1,995.38

**Scenario Cost/Unit:** \$1.51

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Fence, Wire Assembly, High Tensile, Electric, 2 Strand	33	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.07	1320	\$90.97
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	29	\$181.56
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	2	\$228.16

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	12	\$260.51
---------------	-----	--	------	---------	----	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	6	\$43.14
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	6	\$146.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	6	\$128.57

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #4 - Permanent High Tensile Electric Single Strand

**Scenario Description:** Scenario is for the installation of a permanent high tensile electric single strand fence. Installation of fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds.

**Before Situation:** On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds.

**After Situation:** Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, fence charger, etc. Fence will be installed with wildlife friendly considerations. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$1,361.26

**Scenario Cost/Unit:** \$1.03

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Cutoff Switch	25	Electric, Cutoff Switch for electric fence. Includes materials and shipping only.	Each	\$8.53	1	\$8.53
Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Electric, Ground Rod Clamps	21	Electric, Ground Rod Clamps for electric fence. Includes materials and shipping only.	Each	\$1.81	4	\$7.24
Electric, Ground Rods	20	Electric, Ground Rod for electric fence. Includes materials and shipping only.	Each	\$10.51	4	\$42.03
Electric, Lightening Diverter	22	Electric, Lightening diverter for electric fence. Includes materials and shipping only.	Each	\$10.27	1	\$10.27
Fence, Wire Assembly, High Tensile, Electric, 1 Strand	32	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.02	1320	\$31.91
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	24	\$150.26
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	1	\$114.08

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	6	\$130.25
---------------	-----	--	------	---------	---	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	3	\$21.57
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	3	\$73.10
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	3	\$64.28

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #5 - Permanent High Tensile, Minimum 4 Strand, Posts 12 to 18ft Centers

**Scenario Description:** Establishment of permanent electric or non-electric high tensile fence for livestock. Fence is designed using minimum of 4 strands with posts on 12 to 18 foot centers. Uses single or double H bracing depending on site conditions.

**Before Situation:** This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

**After Situation:** This scenario consists of installing a permanent high tensile fence with a minimum of 4 wires with wooden posts on 12 to 18 foot centers, with single or double H brace assemblies, as called for by site conditions, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control.

**Scenario Feature Measure:** Length of fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$3,032.96

**Scenario Cost/Unit:** \$2.30

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Fence, Wire Assembly, High Tensile, Electric, 2 Strand	33	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.07	1320	\$90.97
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	87	\$544.68
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	6	\$67.57
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	2	\$228.16

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	25	\$542.72
---------------	-----	--	------	---------	----	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	15	\$107.84
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	15	\$365.51
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	10	\$214.28

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #6 - Permanent High Tensile, Minimum 4 Strand, Posts >18ft Centers

**Scenario Description:** Establishment of permanent electric or non-electric high tensile fence for livestock. Fence is designed using minimum of 4 strands with posts on >18 foot centers using single or double H bracing depending on site conditions. Also used for small ruminant High Tensile electrified woven wire fence product.

**Before Situation:** This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

**After Situation:** Typical size for this scenario is 1320 feet. This scenario consists of installing a permanent high tensile fence with a minimum of 4 wires with wooden posts on >18 foot centers and battens between the posts, single or double H brace assemblies, depending on site conditions, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area.

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$2,432.35

**Scenario Cost/Unit:** \$1.84

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Fence, Wire Assembly, High Tensile, Electric, 2 Strand	33	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.07	1320	\$90.97
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	68	\$425.73
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	2	\$228.16

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	16	\$347.34
---------------	-----	--	------	---------	----	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	8	\$57.52
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	8	\$194.94
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	8	\$171.42

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #7 - Permanent Woven Wire

**Scenario Description:** Establishment of woven wire fence for livestock.

**Before Situation:** This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

**After Situation:** Typical size for this scenario is 1320 feet. This scenario consists of installing a permanent woven wire fence with wooden posts of 20' centers and single H brace assemblies. Also includes one strand barbed top wire, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$3,352.54

**Scenario Cost/Unit:** \$2.54

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Fence, Wire Assembly, Woven Wire	35	Brace pins, twist sticks, staples. Includes materials and shipping only.	Foot	\$0.12	1320	\$160.21
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	65	\$406.95
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	6	\$67.57
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	1	\$71.19
Wire, Woven, Galvanized, 12.5 Gauge, 48"	4	Galvanized 12.5 gauge, 48" - 330' roll. Includes materials and shipping only.	Each	\$257.12	4	\$1,028.49

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	24	\$521.01
---------------	-----	--	------	---------	----	----------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	12	\$86.27
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	12	\$292.41
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	8	\$171.42

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #8 - Temporary/Portable Fence

**Scenario Description:** Establishment of temporary or portable fence for livestock to facilitate a more intensive grazing system such as stockpiling or stripgrazing.

**Before Situation:** This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

**After Situation:** Consists of installing a single strand polywire/polytape fence with step in/fiberglass posts on 50' centers, solar energizer, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$626.72

**Scenario Cost/Unit:** \$0.47

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Post, Fiberglass, 11/16" X 6'	19	Fiberglass line post, 11/16" diameter X 6' length. Includes materials and shipping only.	Each	\$6.50	26	\$168.93
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	2	\$95.22

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	1	\$21.71
---------------	-----	--	------	---------	---	---------

**Equipment Installation**

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	1	\$21.43
---------------	-----	---	------	---------	---	---------

**Practice:** 382 - Fence

**Scenario:** #9 - Safety

**Scenario Description:** A barrier (fence) implemented on an NRCS constructed waste storage system according to engineering design to exclude human access. Permanently installed fence built to (1) keep humans away from waste ponds & lagoons, or (2) to protect sensitive areas (riparian areas, wetlands, springs, etc.) from heavy livestock pressure. Heavy grade fence materials and close post spacing required.

**Before Situation:** Where a NRCS designed and constructed waste storage pond is planned whereby significant risk to human safety is determined to be evident. Livestock has access to sensitive areas that may cause detrimental effect to animal/human health and wildlife habitat. Resource concerns affected are plant health and vigor, wildlife habitat, compaction of soils, runoff of sediment or water quality due to turbidity..

**After Situation:** Humans and livestock are excluded from the waste storage pond for safety purposes by installing a fence around a waste holding pond. The fence would typically be 100 wide x 175 long with one gate and installed by a fencing contractor. Woven wire fence with one strand of barb wire on top with a gate. Improved livestock control and access to water or other sensitive areas will promote safety for livestock/humans improve health, vigor of sensitive species, limiting soil erosion, and condition.

**Scenario Feature Measure:** Length of Fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 450

**Total Scenario Cost:** \$2,377.49

**Scenario Cost/Unit:** \$5.28

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	43	\$287.38
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	8	\$50.09
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	13	\$196.30
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	1	\$71.19
Wire, Woven, Galvanized, 12.5 Gauge, 32"	3	Galvanized 12.5 gauge, 32" - 330' roll. Includes materials and shipping only.	Each	\$175.97	2	\$351.94

**Labor**

Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$23.59	12	\$283.02
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	15	\$325.63

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.19	5	\$35.95
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$24.37	5	\$121.84
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	5	\$107.14

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 382 - Fence

**Scenario:** #10 - Temporary\_Portable for Small Livestock

**Scenario Description:** Establishment of temporary or portable fence for small livestock to facilitate a more intensive grazing system such as stockpiling or stripgrazing.

**Before Situation:** This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

**After Situation:** Consists of installing a prefabricated fence that has 10 horizontal twines; is 42 in. tall installed, and has plastic vertical struts every 12", solar energizer, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

**Scenario Feature Measure:** Length of fence

**Scenario Unit:** Foot

**Scenario Typical Size:** 1320

**Total Scenario Cost:** \$1,896.79

**Scenario Cost/Unit:** \$1.44

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Wire, Electric Netting, 42"	2382	Electric netting, 42" tall, 10 horizontal strands, vertical struts every 12 inches, single spike. Material only.	Foot	\$1.16	1320	\$1,534.22

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	1	\$21.71
---------------	-----	--	------	---------	---	---------

**Equipment Installation**

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$21.43	1	\$21.43
---------------	-----	---	------	---------	---	---------