

Practice: 449 - Irrigation Water Management

Scenario: #1 - IWM for row crops

Scenario Description: Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management on a row crop operation. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation: The irrigator decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with a sprinkler irrigation system.

After Situation: Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Scenario Feature Measure: Irrigated Area Managed

Scenario Unit: Acre

Scenario Typical Size: 125

Total Scenario Cost: \$1,429.14

Scenario Cost/Unit: \$11.43

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	8	\$173.67
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.23	32	\$1,255.47

Practice: 449 - Irrigation Water Management

Scenario: #2 - IWM for microirrigation systems and specialty crops

Scenario Description: Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management on a specialty crop operation, or an operation utilizing microirrigation. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation: The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 15 acre specialty crop field with a surface irrigation system.

After Situation: Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. Associated Practices:441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Scenario Feature Measure: Irrigated Area Managed

Scenario Unit: Acre

Scenario Typical Size: 15

Total Scenario Cost: \$868.35

Scenario Cost/Unit: \$57.89

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	40	\$868.35
---------------	-----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	---------	----	----------

Practice: 449 - Irrigation Water Management

Scenario: #3 - IWM for Seasonal High Tunnels

Scenario Description: Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management in Seasonal High Tunnels. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation: The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success.

After Situation: Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. The typical irrigated area is approximately 2,000 sq ft under a Seasonal High Tunnel. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Scenario Feature Measure: Number of High Tunnels

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$434.18

Scenario Cost/Unit: \$434.18

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	20	\$434.18
---------------	-----	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	---------	----	----------

Practice: 449 - Irrigation Water Management

Scenario: #4 - Soil Moisture Sensors - 1st Year

Scenario Description: This practice includes the installation of soil moisture sensors such as tensiometers, gyp blocks, capacitance sensors etc, that are installed and read to determine point in time soil moisture by depth; and the labor of using the equipment for the first year. The installation includes the purchase of soil moisture meters and sensors, installation equipment, and labor to install and utilize sensors and readings in making IWM decisions during first year. Typical Scenario involves installation of resistance sensor blocks in a 80 acre field of irrigated cropland. Producer periodically monitors soil moisture sensors during the growing season. Meters used to read sensors may be portable. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities.

Before Situation: Producer uses feel method to estimate soil moisture for scheduling irrigation.

After Situation: Producer has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer uses periodic soil moisture measurements to schedule irrigation resulting in improved irrigation water management and reduced energy use. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Scenario Feature Measure: Number of Measuring Sites

Scenario Unit: Each

Scenario Typical Size: 2

Total Scenario Cost: \$2,478.71

Scenario Cost/Unit: \$1,239.36

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	12	\$260.51
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.23	40	\$1,569.33

Mobilization

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$69.48	1	\$69.48
------------------------------------	------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	---------	---	---------

Materials

Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	\$285.50	1	\$285.50
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	8	\$293.89

Practice: 449 - Irrigation Water Management

Scenario: #5 - Soil Moisture Sensors with Data Recorder-1st Year

Scenario Description: This practice includes the installation of electrical soil moisture sensors such as capacitance or resistance sensors that are monitored to determine soil moisture. The installation includes the purchase of soil moisture sensors, installation equipment (probe or auger), and a data logger to log continuous soil moisture data that can be downloaded to a personal computer and associated graphing software. Scenario also includes the labor associated with using the equipment for the first year. Typical Scenario involves installation of resistance sensor blocks in a 120 acre field of sprinkler irrigated cropland. Producer periodically monitors soil moisture sensors during the growing season. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities.

Before Situation: Producer uses feel method to estimate soil moisture for scheduling irrigation in the field.

After Situation: Producer has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer periodically downloads continuously recorded soil moisture measurements that are used to schedule irrigation more effectively resulting in improved irrigation water management and reduced energy use. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface., 587-Structure for water Control, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Scenario Feature Measure: Number of Measuring Sites

Scenario Unit: Each

Scenario Typical Size: 2

Total Scenario Cost: \$3,386.20

Scenario Cost/Unit: \$1,693.10

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	12	\$260.51
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.23	40	\$1,569.33

Mobilization

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$69.48	1	\$69.48
------------------------------------	------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	---------	---	---------

Materials

Data Logger	1453	Data Logger W/Graphic Output for water management. Materials only.	Each	\$596.50	2	\$1,192.99
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	8	\$293.89

Practice: 449 - Irrigation Water Management

Scenario: #15 - Advanced IWM

Scenario Description: A high intensity irrigation water management system for producers using a checkbook method with advanced methods of determining irrigation water applied, and estimating crop evapotranspiration, monitoring field soil moisture, or monitoring crop temperature stress. Typical methods include flow measurement, daily record keeping, and use of real-time evapotranspiration estimates (such as those provided dedicated weather stations) and/or soil moisture sensors with automated data logging to monitor field soil moisture content and/or crop temperature. For this scenario, soil moisture is determined by automated soil moisture monitoring stations equipped with telemetry data. Telemetry data is automatically sent to a computer with irrigation software. Irrigator also receives real time data via mobile phone applications. Some data such as total water applied may be entered into computer software manually. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System, Microirrigation; 442-Irrigation System, Sprinkler; 443-Irrigation System, Surface and Subsurface.

Before Situation: The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with sprinkler irrigation.

After Situation: Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Scenario Feature Measure: Irrigated Area Managed

Scenario Unit: Acre

Scenario Typical Size: 125

Total Scenario Cost: \$2,230.54

Scenario Cost/Unit: \$17.84

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	16	\$347.34
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.23	48	\$1,883.20