

**Practice:** 490 - Tree/Shrub Site Preparation

**Scenario:** #1 - Chemical Application

**Scenario Description:** This practice involves the use of various herbicides applied using ground-based machinery in order to remove undesirable vegetation and improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestland that was recently harvested. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

**Before Situation:** Undesirable vegetation is present on the site including herbaceous plants and woody vegetation. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

**After Situation:** Undesirable vegetation has been treated using appropriate herbicides, reducing competition for target trees and/or shrubs. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 40

**Total Scenario Cost:** \$2,003.96

**Scenario Cost/Unit:** \$50.10

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$15.93	40	\$637.05
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$22.61	40	\$904.50
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$1.30	40	\$51.82

**Equipment Installation**

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.03	40	\$241.35
------------------------------	-----	---	------	--------	----	----------

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	1	\$169.24
-------------------------------	------	--	------	----------	---	----------

**Practice:** 490 - Tree/Shrub Site Preparation

**Scenario:** #2 - Light Mechanical

**Scenario Description:** This practice involves the use of light/moderate machinery to clear above ground vegetation and to also rip/cut/lift underground root systems in order to improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestlands that have been harvested. This following resource concerns: soil quality degradation - compaction, soil erosion - sheet and rill, and degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

**Before Situation:** Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs. Soils are compacted as a result of harvesting heavy equipment activities or other land uses.

**After Situation:** Undesirable vegetation has been removed using a bush hog to knock down stand vegetation and heavy tillage equipment is used to breakup and lift root systems, breakup plow pans (<18" deep), thus enhancing the conditions for planting and survival of trees and/or shrubs. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 40

**Total Scenario Cost:** \$2,186.02

**Scenario Cost/Unit:** \$54.65

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Labor**

Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$23.59	16	\$377.36
----------------------------	-----	---	------	---------	----	----------

**Equipment Installation**

Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$51.06	16	\$816.91
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.33	40	\$653.27

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	2	\$338.48
-------------------------------	------	--	------	----------	---	----------

**Practice:** 490 - Tree/Shrub Site Preparation

**Scenario:** #3 - Light Mechanical with Chemical

**Scenario Description:** This practice involves the use of light/moderate machinery to clear above ground vegetation and to also rip/cut/lift underground root systems followed by appropriate herbicide application in order to improve site conditions for establishing trees and/or shrubs. Typical sites include small trees (<2" dbh) and brush cover on less than 60% of area that is not appropriate to the site or providing the desired condition for the landowner. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestlands that have been harvested. This following resource concerns: soil quality degradation - compaction, soil erosion - sheet and rill, and degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

**Before Situation:** Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs. Soils are compacted as a result of harvesting heavy equipment activities or other land uses.

**After Situation:** Undesirable vegetation has been removed using a bush hog to knock down stand vegetation and heavy tillage equipment is used to breakup and lift root systems, breakup plow pans (<18" deep), thus enhancing the conditions for planting and survival of trees and/or shrubs. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 40

**Total Scenario Cost:** \$4,189.98

**Scenario Cost/Unit:** \$104.75

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Labor**

Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$23.59	16	\$377.36
----------------------------	-----	---	------	---------	----	----------

**Materials**

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$15.93	40	\$637.05
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$22.61	40	\$904.50
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$1.30	40	\$51.82

**Equipment Installation**

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.03	40	\$241.35
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$51.06	16	\$816.91
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.33	40	\$653.27

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	3	\$507.71
-------------------------------	------	--	------	----------	---	----------

**Practice:** 490 - Tree/Shrub Site Preparation

**Scenario:** #4 - Heavy Mechanical with Chemical

**Scenario Description:** This practice involves the use of heavy machinery combined with appropriate herbicide application to treat an area in order to improve site conditions for establishing trees and/or shrubs. Typical sites include large trees(>2"dbh) and brush cover on 60% of area that is not appropriate to the site or providing the desired condition for the landowner. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition and soil quality degradation - soil erosion - sheet and rill.

**Before Situation:** The site is dominated by undesirable vegetation including herbaceous plants and significant amounts of woody vegetation (trees and brush) occupying the site. There is also a significant component of woody debris onsite. Noxious and invasive species may also be present on the site. Soils are compacted as a result of past heavy equipment activities or from other land uses. Sheet and rill erosion is occurring in areas where the soil was severely disturbed exposing bare soil. If left untreated, soil compaction and erosion issues will result in poor survival or reduced growth of trees/shrubs to be established on the site.

**After Situation:** Undesirable vegetation has been removed using mechanical methods reducing competition for target trees and/or shrubs. Woody debris has been removed to facilitate tree/shrub planting operations. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 40

**Total Scenario Cost:** \$13,136.97

**Scenario Cost/Unit:** \$328.42

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.71	8	\$173.67
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.23	8	\$313.87

**Materials**

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$15.93	40	\$637.05
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonyleurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$22.61	40	\$904.50
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$1.30	40	\$51.82

**Equipment Installation**

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.03	40	\$241.35
Heavy mechanical site prep, raking	1317	Mechanical operations that pushing and raking trees and vegetation. Requires heavy equipment such as dozers. Includes equipment, power unit and labor costs.	Acre	\$187.19	24	\$4,492.58
Heavy mechanical site prep, shearing, V-blade, K-G blading	1314	Mechanical operations that shear trees and vegetation. Requires heavy equipment such as dozers, Includes equipment, power unit and labor costs.	Acre	\$216.34	24	\$5,192.06

**Mobilization**

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$480.42	2	\$960.84
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$169.24	1	\$169.24