

STATEMENT OF WORK

Saturated Buffer (604)

Iowa

This Statement of Work lists the minimum deliverables required for this individual practice. For deliverables required for other planned practices, refer to those specific Statements of Work.

PRE-DESIGN

Deliverables (Usually completed by NRCS; must be in the case file prior to beginning design.)

1. Documents that demonstrate that adequate planning activities have been completed.
 - a. Report or conservation assistance notes summarizing pre-design meeting(s) with the client.
 - i. Identify the resource concern being addressed and the landowner objectives.
 - ii. Define roles and responsibilities of all parties that will be involved in the project.
 1. Landowner
 2. Designer
 3. NRCS and/or other funding source(s)
 4. Contractor
 - iii. Advise client on potential compliance issues with federal, state, tribal, and local laws, regulations, and NRCS policies.
 - b. The practice is included in a conservation plan and meets one or more of the purpose(s) described in the Conservation Practice Standard.
 - c. Completed IA-CPA-52 showing NEPA requirements have been met and documented (i.e.: cultural resources and threatened and endangered (T&E) species).

DESIGN

Deliverables (Completed by the responsible designer)

1. Copy of survey notes which shows that a thorough and detailed site survey was completed.
 - a. Survey notes shall be in accordance with NRCS Technical Release 62, Engineering Field Handbook (EFH), Chapter 1, Engineering Surveys, and/or standard industry practice.
 - b. Rod readings or Elevations shall be referenced to a benchmark. A temporary benchmark is acceptable. The TBM shall be selected to ensure its availability through completion of construction activities.
 - c. Elevation data collected with LiDAR meeting Iowa Standard or FEMA Compliant specifications may be used for planning and watershed delineation but not for final design.
2. Design documentation that will demonstrate that the criteria in the NRCS practice standard have been met and are compatible with other planned and applied practices:
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Impacts on adjacent properties and structures.
 - d. Compliance with NRCS national and state utility safety policy (National Engineering Manual (NEM), Part 503-Safety, Subpart A, Engineering Activities Affecting Utilities, 503.0 through 503.6 and Iowa NEM Amendment, Parts 503.0 through 503.5).
 - e. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM, Part 531, Subpart A, Geologic Investigations). (Example: Soil log and testing reports.)
 - ii. Hydrology/Hydraulics.
 - iii. Structural design. Include hazard class documentation as appropriate.
 - iv. Vegetation.
 - v. A tile map that includes tile sizes, materials, depth, and locations of all tile draining to the saturated buffer. Provide documentation on how the saturated buffer was sized, including drainage area.
3. Written plans and specifications including drawings provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Include the following, at a minimum:
 - a. Location map with legal descriptions.
 - b. A plan view of the layout of the water distribution system, and relevant benchmark elevations and descriptions.
 - c. Profile(s) of the existing drain, distribution pipe, and outlet channel.
 - d. Details of required structure(s) for water level control.
 - e. Vegetation establishment requirements.

- f. Quantities of all components.
 - g. Construction and material specifications that describe site-specific installation requirements.
 - h. Utility safety statement requiring notification of the Iowa One-Call System prior to construction.
 - i. Additional notes as necessary to identify avoidance and protection areas and boundaries associated with cultural resources, threatened or endangered species, or other resources needing temporary protection during installation.
 - j. Signature/initials and date for design and design check. Design check to be completed by an individual other than the designer.
4. Operation and Maintenance (O&M) Plan developed in accordance with the requirements of Conservation Practice Standard 604, Saturated Buffer.
 5. Certifications that the design meets practice standard criteria and complies with applicable laws and regulations, or is approved by an employee with the appropriate delegated engineering job approval authority.

INSTALLATION

Deliverables (Completed by the responsible designer)

1. Conduct a preconstruction meeting with client, contractor, and NRCS representative.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan):
 - a. Actual materials used (NEM, Part 512, Subpart D, Quality Assurance Activities, 512.33).
 - b. Inspection records.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations, and NRCS policies during installation.
7. Certification that the installation process and materials meet design and permit requirements.

CHECK OUT

Deliverables (Completed by the responsible designer)

1. Survey for Checkout conducted and recorded as for the design survey.
 - a. Location of the practice components installed.
 - b. As-Built elevations of the structure(s).
 - c. Profiles along the routes of pipe installation.
2. As-Built documentation:
 - a. Extent of practice units applied.
 - b. Documentation of materials installed (i.e. pipe materials, structures, seed tags, etc.).
 - c. As-built plan is required when a significant change in design or layout occurs during construction or when the job is designated Class V or higher. Identify "As Built" on plan. Superimpose changes on the as-built plan using a different color or otherwise clearly differentiating the as-built dimensions.
 - d. For practices not requiring an as-built plan, survey notes documenting critical dimensions, elevations, and materials.
 - e. Final quantities.
3. Certification that the practice has been installed in accordance with NRCS practice standard criteria and specifications and complies with applicable laws and regulations, or is approved by an employee with the appropriate delegated engineering job approval authority.
4. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (FOTG), Section IV, Conservation Practice Standard 604 – Saturated Buffer
- NRCS National Engineering Handbook, Part 624, Section 16, Drainage
- NRCS National Engineering Handbook, Part 650, Chapter 14, Water Management (Drainage)
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook