

ILLINOIS STATEMENT OF WORK
Animal Mortality Facility (316)

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM Part 531 – Geology, Subpart A)
 - ii. Size, type and number of animals or other sources of organic feedstock
 - iii. Size and capacity needed
 - iv. Structural, Mechanical and Appurtenance design
 - v. Environmental Considerations (e.g. air quality, bio-security)
 - vi. Safety Considerations (NEM Part 503-Safety, Subpart A)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits, including but not limited to:
 - a. Location Map with legal description
 - b. Plan View drawing showing the location of the practice to be constructed, relevant benchmark elevations and descriptions
 - c. Detail drawings for the animal mortality facility showing sizes of all features and relevant elevations
 - d. Cross-sections showing the type and required thickness of the structure's liner.
 - e. Detail drawings for appurtenances
 - f. Construction and Material specifications
 - g. Specifications for vegetative establishment
 - h. Construction notes as needed to clarify components and provide directions for installation.
 - i. Utility safety statement requiring notification of the Illinois One-Call System prior to construction.
 - j. Additional notes as necessary to identify avoidance and protection areas and boundaries associated with cultural resources, threatened and endangered species, or other resources needing temporary protection during installation
 - k. Signatures/initials and date for design and design check. Design check to be completed by an individual other than the designer.
2. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.32 through 512.33)
3. Operation and Maintenance Plan developed in accordance with the requirements of IL NRCS Conservation Practice Standard 316, Animal Mortality Facility. For a composting facility, include a table or chart to show the proposed management schedule.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Part 505, Subpart A, 505.3 (B)). Design, Installation and Certification requirements specific to Illinois are located in NEM Part 505, Section IL505.43, Exhibits C, D and E.
5. Design modifications during installation as required.

ILLINOIS STATEMENT OF WORK
Animal Mortality Facility (316)

INSTALLATION

Deliverables

1. Preconstruction conference with client and contractor (NEM Part 512, Subpart B, IL 512.13(d)).
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used (Part 512, Subchapter D Quality Assurance Activities, 512.33)
 - b. Inspection record
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements (NEM Part 505, Subpart A, 505.3 (C)).

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied
 - b. As-built plan is required when a significant change in design occurs during construction or when the job is designated Class V or higher. Identify "As Built" on plan. Superimpose changes on the as-built plan using a different color or otherwise clearly differentiating the as-built dimensions.
 - c. For practices not requiring an as-built plan, survey notes documenting critical dimensions, elevations, and materials are sufficient.
 - d. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Animal Mortality Facility, 316
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook
- National Engineering Handbook (NEH), Part 651, Agricultural Waste Management Field Handbook (AWMFH)
- National Engineering Handbook Part 637, Chapter 2 – Composting