

NATURAL RESOURCES CONSERVATION SERVICE
ADDITIONAL DOCUMENT FOR
GRASSED WATERWAY

CODE 412

Stormwater Pollution Prevention Plan Guidelines

The stormwater pollution prevention plan shall have sections that contain the following:

- Site map
- Erosion control measures

Each plan shall identify protection and vegetative establishment activities such as the following:

- All earthwork construction will be completed within a short time (such as 10 days) of the site disturbance or commencement of construction.
- The waterway will be seeded within a short time (such as 5 days) after construction shaping is completed.
 - The permanent seeding mixture (species) will be seeded if the calendar date is within the timetable listed in Conservation Practice Standard 342, Critical Area Planting, for the species being planted.
 - During other times of the year, a cover crop meeting Conservation Practice Standard 340, Cover Crop, will be seeded. The permanent grass mixture will be seeded later at the proper time of the year.

- If the construction and seeding is completed during the dormant (non-growing) season time of the year (December 1 through March 15), mulching will be applied and anchored in accordance with Conservation Practice Standard 484, Mulching, for all waterways with a channel grade (slope) steeper than 2 percent.